# Sampling Design for Spatial Cluster Randomized Trials Under Heterogeneous Incidence

Andrew Walther[1], Ashkan Habib[2], Ross Joseph Simpson, Jr.[3], and Feng-Chang Lin[1]

[1]Department of Biostatistics, University of North Carolina at Chapel Hill, Chapel Hill, NC, USA
[2]Department of Epidemiology, University of North Carolina at Chapel Hill, Chapel Hill, NC, USA
[3]Division of Cardiology, University of North Carolina School of Medicine, Chapel Hill, NC, USA
*Corresponding author: Feng-Chang Lin, flin33@email.unc.edu

## Introduction

Cluster randomized trials (CRTs) randomize intact groups, such as clinics, schools, or geographic areas, rather than individuals, and are the standard design when an intervention is delivered at the group level or when individual randomization would create unacceptable contamination between arms [1, 2]. A central assumption underlying standard CRT analysis is the no-interference component of the stable unit treatment value assumption (SUTVA): a cluster's outcome must not depend on which other clusters were assigned to treatment [3]. This assumption, borrowed from individually randomized trial theory, can fail once clusters are spatially arranged, and so can the weaker assumption of partial interference, under which outcomes may depend on assignments within prespecified groups but not across them [4]. Tobler's first law of geography, "everything is related to everything else, but near things are more related than distant things" [5], implies that an intervention delivered in one location can plausibly influence outcomes in geographically adjacent locations through shared populations, service networks, information diffusion, or environmental pathways. Documented examples of this kind of spatial spillover span public health and development economics: in a trial of insecticide-treated bed nets in

northern Ghana, child mortality was lower in control villages close to treated villages than in control villages farther away [6], and a school-based deworming trial in Kenya found health and attendance benefits among untreated children near treated schools [7]. When control clusters benefit from nearby treatment in this way, an unadjusted comparison of treated and control clusters may understate the direct effect, and how much contamination occurs can depend on the spatial arrangement of treated and control clusters, not only on the number of clusters allocated to each arm.

## The design-stage gap in the spatial interference literature

The methodological literature addressing spatial interference in CRTs has concentrated on analysis-stage correction (Chapter 1). Spatial autocorrelation statistics such as Moran's $I$ [8] detect residual spatial dependence once outcomes have been observed, and spatial regression models, such as the spatial lag model [9] estimated by maximum likelihood [10] and implemented in software [11], allow an analyst to separate a direct treatment effect from a spillover effect after the fact. In their systematic review of spatial analysis methods for cluster randomized trials, Jarvis and colleagues placed trials that used spatial separation or buffers outside the primary review of statistical methods [12]. The literature therefore offers much more guidance on analyzing spatial effects than on how the choice of treatment assignment itself, made before any data are collected, might reduce the problem.

Design-stage tools do exist, but they were largely developed for a different purpose. Restricted and covariate-constrained randomization address the baseline imbalance that a limited number of clusters can produce [13, 14]; Crisp and colleagues noted that their extension, which selects clusters from a larger eligible set, also increases spatial dispersion among the selected clusters [15]. Their dispersion criterion concerns which clusters are selected rather than how they are assigned to arms, and balancing a covariate across arms does not by itself determine whether treated and control clusters are spatially interspersed in a way that induces contamination. Work that

addresses the problem studied here more directly includes randomized saturation designs, which assign different fractions of units treated to different groups so that direct and spillover effects can be jointly identified [16]; the selection of whole clusters for inclusion or exclusion in place of a "fried-egg" design that omits each cluster's outer area from analysis [17]; and recent theoretical designs under spatial, network and cross-cluster interference and spatio-temporal heterogeneity [18, 19, 20, 21]. This chapter complements this work with a simulation comparison of concrete assignment strategies that a trial team could implement, under heterogeneous baseline incidence and a range of spatial dependence and spillover conditions.

## Extending a small-grid proof of concept

Chapter 2 examined block-stratified allocation as a practical way to obtain reasonably good estimation while limiting poor-allocation risk in its studied settings; this chapter evaluates both criteria across a broader set of designs under heterogeneous incidence. We retain its simple random assignment benchmark and strict alternating allocation, called Checkerboard here, while adding incidence balancing, targeting, saturation and isolation strategies. The grid comparison increases the number of clusters from 8–12 to 100, considers queen as well as rook neighbors, and includes heterogeneous baseline incidence in the outcome model. These changes extend the design question rather than provide a direct numerical replication of Chapter 2. In Chapter 2, $\beta$ denotes the intervention effect; here that effect is $\tau$, while $\beta$ denotes the coefficient of the incidence covariate. Our observed-incidence application subsequently uses the North Carolina (NC) community college geography and a continuous education outcome, without assuming that historical sudden unexpected death (SUD) incidence predicts baseline education performance.

## Aims

This chapter has three aims: compare assignment designs by mean squared error (MSE), bias and confidence interval coverage; assess how conclusions depend on incidence heterogeneity,

spatial dependence, spillover regime and treatment-effect magnitude; and assess both average accuracy and allocation-specific downside for planning a SUD-prevention education pilot on an observed North Carolina geography. The detailed grid results retain a six-design presentation, with the two related variants documented in the appendix. A main-text benchmark includes all eight strategies and simple random sampling (SRS). The completed application evaluates all nine strategies separately for each observed planning year. The application simulates outcomes and assignments; it does not report outcomes from an implemented intervention.

# Methods

## Spatial structure and outcome model

We simulated a $10 \times 10$ regular grid of 100 clusters under two definitions of adjacency. Under queen contiguity, two clusters are neighbors if they share an edge or a corner; under rook contiguity, they must share an edge. Queen contiguity is the primary analysis in this chapter. Rook contiguity is a sensitivity analysis and the case that continues Chapter 2, whose grids used rook neighbors. For each definition, the binary adjacency matrix was row-standardized to form the spatial weights matrix $W$, so that $WZ$ gives, for each cluster, the proportion of its neighbors that are treated, and $WY$ gives the average outcome among its neighbors. Row-standardization expresses each cluster's spillover exposure as an average over its own neighborhood rather than a raw sum, which would otherwise depend on how many neighbors the cluster has. Within a scenario, the same neighbor type defines $W$ in the outcome model, in the Isolation Buffer design, and in the fitted model.

Cluster-level outcomes $Y$ were generated from a spatial lag model with a spillover term,

$$Y = (I - \rho W)^{-1} \left[\tau Z + S(Z) + \beta X + \epsilon\right], \qquad \epsilon \sim N(0, \sigma^2 I), \tag{1}$$

where $Z \in \{0,1\}^{100}$ is the treatment assignment produced by the design under evaluation, $\tau$ is the direct treatment effect of interest, $S(Z)$ is the spillover term defined in Equation 2, $\rho$ is the spatial autoregressive coefficient governing dependence in the outcome beyond that induced by treatment and spillover, $X$ is the baseline incidence covariate with coefficient $\beta = 1$, and $\sigma = 1$. The spatial multiplier $(I - \rho W)^{-1}$ propagates each cluster's shocks through the network of neighbors. We tested $\rho \in \{0, 0.01, 0.20, 0.50\}$. When $\rho = 0$ the multiplier is the identity and the model is a linear regression with independent errors, $Y = \tau Z + S(Z) + \beta X + \epsilon$, in which spatial structure enters only through the spillover term; larger values of $\rho$ induce progressively stronger spatial clustering in the outcome.

We evaluated two spillover regimes,

$$S(Z) = \gamma\, WZ \quad \text{(both arms)}, \qquad S(Z) = \gamma\, WZ \circ (1 - Z) \quad \text{(control only)}, \tag{2}$$

where $\circ$ denotes the elementwise product. Under the control-only regime, only untreated clusters respond to the treatment status of their neighbors, which represents classical contamination: an untreated cluster's outcome rises with the share of its neighbors that are treated. Under the both-arms regime, every cluster responds to its neighbors' treatment regardless of its own assignment, so neighboring treatment adds to a treated cluster's own effect. We tested four spillover magnitudes, $\gamma \in \{0.5, 0.6, 0.7, 0.8\}$, and five magnitudes of the direct effect, $\tau \in \{0.8, 1.0, 1.5, 2.0, 3.0\}$, with $\tau = 1$ as the primary scenario throughout.

## Heterogeneous baseline incidence

Chapter 2 assumed a spatially uniform baseline outcome risk. Cluster-level health outcomes typically vary across space, and the designs studied here differ in whether and how they use that variation. We generated the baseline incidence covariate $X$, with values in $(0, 1)$, under three mechanisms. Under the independent (iid) mechanism, each $X_i$ is drawn from a Uniform$(0, 1)$

distribution, with no spatial structure. Under the spatially autocorrelated mechanism, $X = \Phi\{(I - \rho_X W_Q)^{-1} u\}$, where $u \sim N(0, I)$, $\Phi$ is the standard normal distribution function applied elementwise, $W_Q$ is the queen weights matrix, and $\rho_X \in \{0.20, 0.50\}$. Under the Poisson mechanism, a spatially autocorrelated log-rate surface, $\log \lambda = \log(35/100{,}000) + (I - \rho_X W_Q)^{-1} u$ with $\rho_X \in \{0.20, 0.50\}$, generates cluster death counts $C_i \sim \text{Poisson}(\lambda_i P)$, with an equal population of $P = 100{,}000$ in every cluster, so that a cluster at the base rate expects 35 deaths. The observed rates $C_i/P$ are then rank-normalized to $X_i = (r_i - 0.5)/N$, where $r_i$ is the rank of cluster $i$'s rate among the $N = 100$ clusters and tied rates share their average rank. Ties remain at this population size: the Poisson surfaces used here have between 60 and 76 distinct values among the 100 clusters. The base rate of 35 per 100,000 was chosen to be representative of published SUD incidence: it lies between the SUD incidence rates that Mirzaei and colleagues estimated for US men (49.3 per 100,000) and women (21.7 per 100,000) aged 20–64, close to their average [22]. It is not the observed rate of the county data described in the Application section, which come from a different source, age range, period, and case definition. The incidence filters always use the queen weights $W_Q$, whichever neighbor type the scenario uses, so the incidence surfaces are identical under rook and queen contiguity. The iid mechanism and the two strengths of each of the other two mechanisms give five incidence configurations.

For each configuration we generated $K = 10$ incidence surfaces, $X_1, \ldots, X_{10}$, each from its own seed. The same ten surfaces are used by every scenario in that configuration, across neighbor types, outcome-model parameters, designs, and values of $\tau$; the design draws and the outcome noise are shared more selectively, as described under Simulation design, resampling, and metrics. Each design is applied to the surface that generates the outcome: assignments for surface $k$ are drawn from $X_k$, and the outcome and the fitted model for those assignments use $X_k$ as well. This assumes that the incidence observed when a trial is planned is the incidence that drives its outcome (the matched-surface assumption). The target of each scenario is performance averaged over incidence surfaces; for example, $\text{MSE} = E_X E_{Z|X} E_\epsilon[(\hat{\tau} - \tau)^2]$, with $X$ drawn from

the configuration's generator, $Z$ from the design given $X$, and $\epsilon \sim N(0, I)$. Bias, coverage, and power are defined in the same way.

## Treatment assignment designs

We implemented eight treatment assignment designs and present six of them as the primary comparison set in this chapter. The other two, Saturation Quadrants and Balanced Halves, each share the mechanism of a retained design, and in a comparison of the eight designs and SRS at $\tau = 1$ neither could be distinguished from its counterpart under either neighbor type (Appendix A1). Saturation Quadrants assigns the saturations 20%, 40%, 60%, and 80% to the four $5 \times 5$ quadrants of the grid in random order, without reference to incidence. Its retained counterpart, Incidence-Guided Saturation, assigns the higher saturations to the quadrants with higher mean incidence (Table 1). On the NC map, both designs use four fixed geographic regions in place of the quadrants. Balanced Halves divides clusters into two halves by incidence rank and treats 25 at random in each; its retained counterpart, Balanced Quartiles, uses four strata. In each pair the excluded design had the marginally lower mean squared error or average rank under at least one neighbor type, so the choice of representative does not rest on performance. The two saturation designs performed similarly, so incidence guidance matches the accuracy of Saturation Quadrants while directing the highest treatment saturations to the quadrants or regions with the highest incidence. How much treatment it redirects depends on how much incidence differs between regions (see Application). The accuracy advantage of both designs over SRS, which arises under control-only spillover (see SRS benchmark and allocation-specific risk), comes from the saturation structure they share. Both variants are included in the full benchmark with SRS and in the application.

Table 1 describes the six retained designs, and Figure 1 shows one assignment from each, and from SRS, on a single illustrative incidence surface. Checkerboard is the strict block-stratified allocation of Chapter 2, in which no two rook neighbors share an arm. Chapter 2's Block

Stratified Sampling design also admitted relaxed allocations on its $3 \times 3$ grid, where the arms cannot be balanced; on its $2 \times 4$ and $3 \times 4$ grids, as on the $10 \times 10$ grid here, the strict allocations are the two checkerboard patterns. We use the two names interchangeably for this allocation and use Checkerboard in the rest of this chapter. Checkerboard is the only deterministic design: it gives the same assignment in every draw, although each of its fits still receives its own outcome noise. Every other design was drawn independently 25 times for each incidence surface. Designs that rank clusters by incidence break ties at random, afresh for each draw. High Incidence Focus is random only through that tie-breaking; under the iid and spatial mechanisms incidence values are distinct, so it gives the same assignment in all 25 draws on a surface, and its assignment changes only from one surface to the next. Isolation Buffer builds its assignment from the neighbor type of the scenario, and it treats 38 clusters on average under rook contiguity and 21 under queen contiguity. Every other design treats exactly 50.





Figure 1: One example assignment from each of the six designs and SRS on the $10 \times 10$ grid, with the designs in the order of Table 1 followed by SRS. Every example uses the illustrative incidence surface in the first panel (darker is higher; dashed lines mark the quadrants), a spatially autocorrelated surface with $\rho_X = 0.5$ generated with a fixed seed; it is not one of the simulation's incidence surfaces. Blue clusters are treated and white clusters are controls. Lines mark the $2 \times 2$ blocks and the quadrants, numbers in the Balanced Quartiles panel give each cluster's incidence quartile, and percentages in the Incidence-Guided Saturation panel give each quadrant's treated share. Isolation Buffer is shown under queen contiguity.

Table 1: The six treatment assignment designs compared in this chapter, ordered by mean squared error under queen contiguity at $\tau = 1$, pooled over the five incidence configurations (Table 2). A cluster's incidence rank is its rank by the baseline incidence surface $X_k$, with ties broken at random in every draw. Clusters treated is the number of clusters treated per assignment; for Isolation Buffer, which depends on the neighbor type, it is the mean over its assignments under each neighbor type.

| Design | Assignment rule | Clusters treated | Deterministic |
|---|---|---|---|
| Incidence-Guided Saturation | The grid is divided into its four $5 \times 5$ coordinate quadrants. Quadrants are ranked by mean incidence and given saturations of 80%, 60%, 40%, and 20% from highest to lowest mean; within each quadrant, that share of its 25 clusters is treated at random | 50 | No |
| Balanced Quartiles | Clusters are divided by incidence rank into four strata of 25. Twelve clusters are treated at random in each stratum, and one more in each of two randomly chosen strata | 50 | No |
| Isolation Buffer | Clusters are treated one at a time, each chosen at random from those that are neither treated nor adjacent to a treated cluster, until none remain (a greedy random maximal independent set); no two treated clusters are neighbors | 38 rook, 21 queen (mean) | No |
| High Incidence Focus | The 50 clusters with the highest incidence rank are treated | 50 | No |
| 2×2 Blocking | The grid is divided into 25 non-overlapping 2×2 blocks; two of the four clusters in each block are treated at random | 50 | No |
| Checkerboard (strict Block Stratified Sampling allocation in Chapter 2) | Clusters whose grid coordinates $(x, y)$ have an odd sum $x + y$ are treated, so treatment alternates from cluster to cluster; under rook contiguity every neighbor of a treated cluster is a control, and every neighbor of a control is treated | 50 | Yes |

## Estimation

We estimated $\tau$ with two maximum likelihood spatial lag models, both fit to every simulated outcome and both including an intercept. The primary, oracle model has the spatial lag $\rho WY$ and the covariates $Z$, Spill $= S(Z)$, and $X_k$, so it matches the outcome model in Equation 1, including the true regime-specific spillover covariate from Equation 2. The oracle model assumes that the analyst knows the form of the spillover mechanism and has the exact exposure term, so its results are a best case for each design; we return to this assumption as a limitation. The non-oracle model, a sensitivity analysis, has the covariates $Z$ and $X_k$ only and omits the spillover

term. Both models are fit to the same outcomes.

We fit both models with our own implementation of the maximum likelihood estimator of the spatial lag model [23], the same estimator that the `lagsarlm` function of the R package `spatialreg` computes with `method = "eigen"`. It maximizes the concentrated log-likelihood over $\rho$, computing the log-determinant from the eigenvalues of $W$ [10], estimates the remaining coefficients by least squares given $\hat{\rho}$, and computes standard errors from the analytic information matrix. On 5,120 validation fits it agreed with `lagsarlm` to within $9.7 \times 10^{-8}$ in $\hat{\tau}$ and to a relative difference of $1.1 \times 10^{-8}$ in its standard error, at roughly 1% of the computing time; we also refit a 1% sample of the full simulation with `lagsarlm` itself as a check. Confidence intervals are 95% intervals with a $t$ reference distribution and a degrees-of-freedom-corrected standard error, $\hat{\tau} \pm t_{0.975,\,N-p}\,\widehat{\mathrm{SE}}\sqrt{N/(N-p)}$, where $\widehat{\mathrm{SE}}$ is the estimated standard error, $N = 100$ is the number of clusters and $p$ is the number of regression coefficients plus $\rho$ (5 for the oracle model; 4 for the non-oracle model and for rook Checkerboard, whose aliased spillover column is dropped). The application uses the same interval. The 95% Wald interval, $\hat{\tau} \pm 1.96\,\widehat{\mathrm{SE}}$, covered about one percentage point less for every design.

Checkerboard illustrates why interspersion alone cannot guarantee precision. Under rook contiguity on the rectangular grid, $WZ = 1 - Z$, so treatment and spillover cannot be separately identified; the fitted coefficient on treatment estimates $\tau - \gamma$. Under queen contiguity, treatment is identified but control-only spillover is weakly separated from treatment. We retain Checkerboard in the main design comparison and flag aliased estimates. Exact matrix identities, boundary information and the rare Isolation Buffer aliases are detailed in Appendix A7. These diagnostics concern the models implemented here.

## Simulation design, resampling, and metrics

The full simulation crossed five values of $\tau$, five incidence configurations, two neighbor types, four values of $\rho$, four values of $\gamma$, two spillover regimes, and eight designs, for $5 \times 5 \times 2 \times 4 \times 4 \times 2 \times 8 =$

12,800 scenarios, of which the six designs reported in this chapter account for 9,600. We call a combination of incidence configuration, neighbor type, $\rho$, $\gamma$, and spillover regime a block; there are $5 \times 2 \times 4 \times 4 \times 2 = 320$ blocks, 160 for each neighbor type. At the primary scenario, $\tau = 1$, the six designs give 1,920 scenarios, and every block contains all six.

Within each scenario, we drew $J = 25$ assignments from each of the $K = 10$ incidence surfaces, for 250 fits per scenario, and gave every fit its own noise vector, so that fit $(k, j)$ has outcome $Y_{kj} = (I - \rho W)^{-1}[\tau Z_{kj} + S(Z_{kj}) + \beta X_k + \epsilon_{kj}]$; Checkerboard's 250 fits share one assignment but have 250 distinct noise vectors. The ten surfaces are independent, so the surface is the primary sampling unit. Each estimator was fit 3.2 million times. SRS, which assigns exactly 50 of the 100 clusters to treatment by complete randomization, ignoring incidence and geography, was subsequently run with the same matched surfaces, noise keys and 250-fit structure, bringing the complete benchmark to 14,400 scenarios and 3.6 million fits per estimator; the original eight-design results were unchanged.

Every random draw was seeded from a key that names the draw, so the results do not depend on the order in which scenarios are run, and the keys give common random numbers: within a block, all designs share the same noise vectors and incidence surfaces; the five values of $\tau$ reuse the same assignments and noise; and the oracle and non-oracle models are fit to the same outcomes. Blocks within an incidence configuration share its ten surfaces.

For each scenario and estimator, we computed bias, the standard deviation (SD) of $\hat{\tau}$, MSE, coverage of the 95% interval, and power, the fraction of fits whose interval lies above zero (a one-sided test of $\tau = 0$ at level 0.025). For both estimators, every one of the 250 fits in every scenario was valid, with a finite estimate and standard error, and the fitting routine raised no warning other than the aliasing flags described above. Because each metric is estimated from a finite number of simulated datasets, it carries simulation (Monte Carlo) error; its Monte Carlo standard error measures this uncertainty and shrinks as more datasets are simulated. Monte

Carlo standard errors come from the surface-level metrics: with $m_k$ a metric computed on the 25 fits from surface $k$, $\mathrm{SE}(m) = \mathrm{sd}(m_1, \ldots, m_{10})/\sqrt{10}$, and, for metrics pooled over the five incidence configurations, from the 50 independent configuration-by-surface means. Appendix A2 gives the parameter grid, the seed keys, and the exact formulas for the metrics, their standard errors, and paired differences between designs.

We compared designs within each neighbor type with a Friedman rank-sum test on scenario MSE [24], treating the 160 blocks as repeated measures across the six designs and SRS. SRS is the usual default for a cluster randomized trial, so it enters every test as a seventh member and each design is compared with it as well as with the other designs. At $\tau = 1$ we followed the Friedman test with Nemenyi post-hoc comparisons [25, 26] and paired Wilcoxon signed-rank tests [27] with Holm's adjustment for multiple comparisons [28] for all 21 pairs, and we repeated the Friedman test at each other value of $\tau$. Blocks within an incidence configuration share their surfaces, so these tests treat dependent blocks as independent, which overstates the information about variation from surface to surface. We therefore also ran paired Wilcoxon signed-rank tests over 50 independent units, the 5 configurations times 10 surfaces, with each unit's MSE averaged over that surface's blocks, and $t_{49}$ intervals for the mean difference. These tests compared each pair of designs adjacent in the mean-MSE order, and each design with SRS within each spillover regime, with Holm's adjustment over the eight designs compared with SRS. Because the values of $\tau$ share assignments and noise, Friedman tests at different values of $\tau$ are not independent confirmations of one another.

We report results separately for each neighbor type, with queen contiguity primary, and no number is averaged over the two. Unless stated otherwise, every number in the Results is pooled over the five incidence configurations, and every table and figure caption states whether it pools the configurations or shows them separately. We report the ranking within each configuration separately and show the split wherever a conclusion changes.

# Results

## Design performance under queen contiguity

At the primary scenario, $\tau = 1$, under queen contiguity and pooled over the five incidence configurations, Incidence-Guided Saturation had the lowest mean squared error (MSE = 0.091), followed by Balanced Quartiles (0.131), Isolation Buffer (0.160), High Incidence Focus (0.245), $2 \times 2$ Blocking (0.319), and Checkerboard (1.087) (Table 2, Figure 2). Coverage of the 95% intervals was between 0.946 and 0.950 for all six designs (Figure 14 in Appendix A5). Power to reject $\tau = 0$ was 0.921 for Incidence-Guided Saturation, 0.814 for Balanced Quartiles, 0.706 for Isolation Buffer, 0.629 for $2 \times 2$ Blocking, 0.582 for High Incidence Focus, and 0.538 for Checkerboard.

Table 2: Performance of the six designs at the primary scenario, $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity), pooled over the five incidence configurations. Each entry averages the 160 scenarios of one design and neighbor type (5 incidence configurations $\times$ 4 values of $\rho$ $\times$ 4 values of $\gamma$ $\times$ 2 spillover regimes), each summarizing 250 fits of the oracle model. Rows in both panels are in order of mean squared error (MSE) under queen contiguity. Monte Carlo standard errors of MSE, in parentheses, are computed from the 50 configuration-by-surface means (Methods); those of bias, coverage, and power are all below 0.007. Average rank is the mean of each design's within-block MSE rank among the six designs and SRS over the 160 blocks (1 = lowest MSE). SRS's average rank is 2.600 under queen contiguity and 2.450 under rook contiguity. Clusters treated is the mean number of clusters treated per assignment. Under rook contiguity, $\tau$ is not identified for Checkerboard ($WZ = 1 - Z$); its estimates are kept and flagged, and its coefficient on $Z$ estimates $\tau - \gamma$.

| Design | MSE (SE) | Bias | Coverage | Power | Average rank | Clusters treated |
|---|---|---|---|---|---|---|
| *Queen contiguity (primary)* | | | | | | |
| Incidence-Guided Saturation | 0.091 (0.0008) | 0.032 | 0.947 | 0.921 | 1.775 | 50 |
| Balanced Quartiles | 0.131 (0.0011) | 0.017 | 0.946 | 0.814 | 2.688 | 50 |
| Isolation Buffer | 0.160 (0.0011) | 0.003 | 0.949 | 0.706 | 4.194 | 21.4 |
| High Incidence Focus | 0.245 (0.0047) | 0.031 | 0.948 | 0.582 | 5.763 | 50 |
| 2×2 Blocking | 0.319 (0.0032) | 0.010 | 0.948 | 0.629 | 5.244 | 50 |
| Checkerboard | 1.087 (0.0101) | 0.001 | 0.950 | 0.538 | 5.737 | 50 |
| *Rook contiguity (sensitivity)* | | | | | | |
| Incidence-Guided Saturation | 0.072 (0.0006) | 0.018 | 0.952 | 0.956 | 1.831 | 50 |
| Balanced Quartiles | 0.084 (0.0006) | 0.008 | 0.948 | 0.907 | 2.225 | 50 |
| Isolation Buffer | 0.133 (0.0009) | 0.003 | 0.950 | 0.784 | 4.206 | 38.2 |
| High Incidence Focus | 0.206 (0.0030) | 0.018 | 0.948 | 0.617 | 5.969 | 50 |
| 2×2 Blocking | 0.128 (0.0012) | 0.004 | 0.948 | 0.803 | 4.331 | 50 |
| Checkerboard (flagged) | 0.480 (0.0015) | −0.652 | 0.162 | 0.390 | 6.987 | 50 |

Incidence-Guided Saturation also led block by block. Of the 160 queen blocks at $\tau = 1$, Incidence-Guided Saturation had the lowest MSE of the six designs in 95 (59%), Balanced Quartiles in 58 (36%), and Isolation Buffer in 7 (4%); no other design had the lowest MSE in any block.





Figure 2: Mean squared error (MSE) of the oracle estimate of $\tau$ by design at $\tau = 1$, under queen contiguity. Columns of panels correspond to the four levels of outcome spatial dependence $\rho$, rows to the both-arms (top) and control-only (bottom) spillover regimes, and bar colors to the spillover magnitude $\gamma$. Each bar overlays the MSEs of the five incidence configurations for one combination of design, $\rho$, $\gamma$, and regime: the bar's height is the largest of the five, and the horizontal lines within it mark the other four. Designs are ordered by pooled mean MSE (Table 2). The gray dashed line in each panel marks simple random sampling (SRS), the largest of its five configuration MSEs averaged over the four values of $\gamma$. The vertical scale is set separately for each row. Figure 16 in Appendix A5 shows rook contiguity.

The Friedman test rejected equal MSE ranks across the six designs and SRS under queen contiguity at $\tau = 1$ ($\chi^2 = 560.33$, df $= 6$, 160 blocks, $p < 2.2 \times 10^{-16}$). Nemenyi comparisons (critical difference 0.712) separated 17 of the 21 pairs. Incidence-Guided Saturation ranked significantly better than every other design and than SRS ($p = 0.011$). SRS and Balanced Quartiles, whose average ranks were 2.60 and 2.69, could not be distinguished from each other ($p = 1.00$), and both ranked significantly better than the remaining four designs. The other three pairs not separated all lay among the bottom three designs. Holm-adjusted Wilcoxon signed-rank tests separated 20 of the 21 pairs, all except Balanced Quartiles against SRS ($p = 0.15$). Because blocks within an incidence configuration share their ten surfaces, we also compared each pair of

designs adjacent in the mean-MSE order over the 50 independent configuration-by-surface units; every adjacent pair differed significantly (Wilcoxon $p \leq 4.9 \times 10^{-9}$), and the better design had the lower MSE in all 50 units for every pair except High Incidence Focus against $2 \times 2$ Blocking (48 of 50). Appendix A3 gives the pairwise results and the critical-difference diagrams.

The bottom three designs were ordered differently by average rank and by mean MSE: by mean MSE, High Incidence Focus (0.245), $2 \times 2$ Blocking (0.319), and Checkerboard (1.087); by average rank, $2 \times 2$ Blocking (5.24), Checkerboard (5.74), and High Incidence Focus (5.76). Both reversals arise because the MSEs of $2 \times 2$ Blocking and Checkerboard depended strongly on the spillover regime. Each had a lower MSE than High Incidence Focus in all 80 both-arms blocks (mean MSE 0.062 for each, against 0.162) and a higher MSE in all 80 control-only blocks (0.576 and 2.111, against 0.329). Average rank counts each block once, so their wins under the both-arms regime offset their losses under the control-only regime; mean MSE weights those losses by their size, and the surface-level comparison, which averages each unit over both regimes, also separated High Incidence Focus from $2 \times 2$ Blocking.

## Design rankings by incidence configuration

Table 3 gives each design's MSE within each of the five incidence configurations. Under queen contiguity, the mean-MSE order within every configuration was the same as the pooled order: Incidence-Guided Saturation, Balanced Quartiles, Isolation Buffer, High Incidence Focus, $2 \times 2$ Blocking, and Checkerboard. The configuration changed each design's MSE only slightly: in this order, each design's highest MSE across the five configurations was lower than the next design's lowest. Incidence-Guided Saturation had the lowest MSE in 18 to 21 of the 32 blocks in each configuration. Coverage did not depend on the configuration either: within each configuration, every design's coverage, averaged over its 32 scenarios, was between 0.941 and 0.952. The mechanism that generated the incidence surface therefore did not change the ranking. This includes High Incidence Focus, the design that uses the incidence ranks most directly: its MSE

was no higher under the two Poisson configurations than under the iid and spatial configurations.

Table 3: Mean squared error by design within each of the five incidence configurations at $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity). Each entry averages the 32 scenarios of one design, neighbor type, and configuration (4 values of $\rho \times 4$ values of $\gamma \times 2$ spillover regimes), each summarizing 250 fits of the oracle model. The spatially autocorrelated and Poisson configurations are labeled by the strength of dependence in the incidence surface, $\rho_X$. Rows in both panels are ordered by pooled mean MSE under queen contiguity (Table 2). Under rook contiguity, $\tau$ is not identified for Checkerboard; its estimates are kept and flagged.

| | | Spatial | | Poisson | |
|---|---|---|---|---|---|
| Design | iid | $\rho_X = 0.20$ | $\rho_X = 0.50$ | $\rho_X = 0.20$ | $\rho_X = 0.50$ |
| *Queen contiguity* | | | | | |
| Incidence-Guided Saturation | 0.093 | 0.087 | 0.092 | 0.090 | 0.092 |
| Balanced Quartiles | 0.130 | 0.130 | 0.131 | 0.128 | 0.135 |
| Isolation Buffer | 0.160 | 0.159 | 0.159 | 0.162 | 0.161 |
| High Incidence Focus | 0.245 | 0.267 | 0.245 | 0.232 | 0.238 |
| 2×2 Blocking | 0.311 | 0.315 | 0.323 | 0.326 | 0.320 |
| Checkerboard | 1.091 | 1.068 | 1.086 | 1.112 | 1.077 |
| *Rook contiguity* | | | | | |
| Incidence-Guided Saturation | 0.072 | 0.072 | 0.073 | 0.073 | 0.069 |
| Balanced Quartiles | 0.081 | 0.084 | 0.084 | 0.084 | 0.085 |
| Isolation Buffer | 0.131 | 0.131 | 0.132 | 0.136 | 0.134 |
| High Incidence Focus | 0.205 | 0.213 | 0.200 | 0.202 | 0.211 |
| 2×2 Blocking | 0.129 | 0.125 | 0.129 | 0.130 | 0.129 |
| Checkerboard (flagged) | 0.480 | 0.482 | 0.474 | 0.481 | 0.482 |

## Sensitivity to spatial dependence, spillover magnitude, and spillover regime

Under queen contiguity, neither the strength of spatial dependence in the outcome nor the spillover magnitude changed the ranking. Across $\rho \in \{0, 0.01, 0.20, 0.50\}$, no design's MSE changed by more than 0.02. Across $\gamma \in \{0.5, 0.6, 0.7, 0.8\}$, the MSE of every design except Checkerboard also varied by less than 0.02, and Checkerboard's varied between 1.052 and 1.108 with no trend in $\gamma$ (Tables 14 and 16 in Appendix A4). Under rook contiguity, $\gamma$ mattered for Checkerboard alone, for the reason given in the rook results below.

The spillover regime was the one factor that changed the queen ranking (Table 4, Figure 2). Under the both-arms regime, Balanced Quartiles had the lowest MSE (0.042), followed by Incidence-Guided Saturation (0.046), $2 \times 2$ Blocking (0.062), Checkerboard (0.062), Isolation Buffer (0.161), and High Incidence Focus (0.162). Under the control-only regime, the order was Incidence-Guided Saturation (0.135), Isolation Buffer (0.159), Balanced Quartiles (0.219), High

Incidence Focus (0.329), $2 \times 2$ Blocking (0.576), and Checkerboard (2.111); at larger values of $\tau$, Isolation Buffer matched or passed Incidence-Guided Saturation under this regime (see Stability across treatment effect sizes). For Isolation Buffer, no treated cluster has a treated neighbor, so $WZ = 0$ at every treated cluster and $WZ \circ (1 - Z) = WZ$. The two regimes in Equation 2 therefore define the same outcome model, and so the same expected MSE; the observed values, 0.161 and 0.159, differ only by Monte Carlo error, because the two regimes use separate draws. Every other design had a higher MSE under the control-only regime, and the increase was largest for Checkerboard and $2 \times 2$ Blocking, which went from close to the best designs under the both-arms regime to the two worst under the control-only regime. Among the six detailed designs, Incidence-Guided Saturation was first or second under both regimes, at this and every other value of $\tau$. In the full benchmark that includes SRS (Table 6), its both-arms MSE was 8% above that of SRS, a small but statistically detectable difference (Figure 4). This matters because a trial team may not know in advance which regime applies.

Table 4: Mean squared error by design under each spillover regime at $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity), pooled over the five incidence configurations. Each entry averages 80 scenarios (5 incidence configurations $\times$ 4 values of $\rho$ $\times$ 4 values of $\gamma$). Rows are ordered by pooled mean MSE under queen contiguity (Table 2). Under rook contiguity, $\tau$ is not identified for Checkerboard; its estimates are kept and flagged.

| | Queen | | Rook | |
|---|---|---|---|---|
| Design | Both arms | Control only | Both arms | Control only |
| Incidence-Guided Saturation | 0.046 | 0.135 | 0.045 | 0.098 |
| Balanced Quartiles | 0.042 | 0.219 | 0.042 | 0.125 |
| Isolation Buffer | 0.161 | 0.159 | 0.131 | 0.134 |
| High Incidence Focus | 0.162 | 0.329 | 0.164 | 0.249 |
| 2×2 Blocking | 0.062 | 0.576 | 0.051 | 0.206 |
| Checkerboard (flagged under rook) | 0.062 | 2.111 | 0.477 | 0.483 |

The increase under the control-only regime was variance, not bias. The oracle model includes the true regime-specific spillover covariate, so it has no omitted-variable bias. At $\tau = 1$, in every combination of design and regime under queen contiguity, the absolute bias was at most 0.048 and squared bias, averaged over scenarios, was at most 2.2% of MSE. Checkerboard showed the mechanism most clearly: under the control-only regime its spillover covariate is a linear

combination of the intercept and $Z$ at every interior cluster, so only the boundary clusters separate the spillover effect from the treatment effect (Methods). Checkerboard's MSE rose from 0.062 under the both-arms regime to 2.111 under the control-only regime, while its bias stayed near zero (0.004) and its coverage stayed at 0.951: its intervals widened with its variance. Its pooled MSE of 1.087 was almost entirely variance: squared bias, averaged over scenarios, was 0.0045, less than 0.5% of MSE (Figure 15 in Appendix A5 shows the decomposition for the Poisson configuration with $\rho_X = 0.20$). $2 \times 2$ Blocking showed the same pattern on a smaller scale, with MSE rising from 0.062 to 0.576 and a bias of 0.016 under the control-only regime.

## Rook contiguity

Under rook contiguity at $\tau = 1$, pooled over the five incidence configurations, the mean-MSE order was Incidence-Guided Saturation (0.072), Balanced Quartiles (0.084), $2\times2$ Blocking (0.128), Isolation Buffer (0.133), High Incidence Focus (0.206), and Checkerboard (0.480) (Table 2; Figure 16 in Appendix A5), and the same order held within each of the five incidence configurations (Table 3). Incidence-Guided Saturation had the lowest MSE in 97 of the 160 rook blocks (61%) and Balanced Quartiles in 60 (38%). Coverage was between 0.948 and 0.952 for every design except Checkerboard, whose coverage was 0.162 (Figure 17 in Appendix A5). With SRS as a seventh member, the Friedman test rejected equal ranks ($\chi^2 = 795.77$, df $= 6$, 160 blocks, $p < 2.2 \times 10^{-16}$). Holm-adjusted Wilcoxon tests separated every pair except $2 \times 2$ Blocking against Isolation Buffer, which were close and traded places at some values of $\tau$, and Balanced Quartiles against SRS. Nemenyi comparisons also left Incidence-Guided Saturation, Balanced Quartiles and SRS unseparated from one another. Incidence-Guided Saturation nevertheless had the lower MSE in 48 of the 50 independent configuration-by-surface units against Balanced Quartiles (Appendix A3), and its paired comparisons with SRS within each regime appear under SRS benchmark and allocation-specific risk.

Checkerboard under rook contiguity is a different case: $\tau$ is not identified, and the coefficient on

$Z$ estimates $\tau - \gamma$ (Methods). At $\tau = 1$, Checkerboard's mean bias was $-0.502$, $-0.600$, $-0.704$, and $-0.802$ at $\gamma = 0.5$, 0.6, 0.7, and 0.8, while its mean standard deviation stayed between 0.20 and 0.21; squared bias, averaged over scenarios, accounted for 0.438 of its MSE of 0.480 (Figure 18 in Appendix A5). Its coverage fell from 0.337 at $\gamma = 0.5$ to 0.031 at $\gamma = 0.8$, and was between 0.146 and 0.171 at every level of $\rho$, against 0.949 to 0.952 under queen contiguity (Table 15 in Appendix A4). Because $WZ = 1 - Z$, the two spillover regimes define the same outcome model; the observed MSEs, 0.477 under the both-arms regime and 0.483 under the control-only regime, differ only by Monte Carlo error. Rook Checkerboard estimates were precise but centered on the wrong quantity, the opposite of its imprecise but valid queen estimates. We keep these estimates in every ranking and flag them.

## Non-oracle sensitivity analysis

The non-oracle model, which omits the spillover term, was biased for every design (Table 17 in Appendix A6 gives both models' MSE, bias, and coverage for each design). At $\tau = 1$, and setting aside Checkerboard under rook contiguity, its bias ranged from $-0.12$ to $-0.40$ and its coverage from 0.54 to 0.91 across designs and neighbor types; for Checkerboard under rook contiguity the two models coincide, because once the aliased spillover column is dropped they are the same. Omitting the spillover term also removes a column that can be nearly collinear with $Z$, and the non-oracle estimates were accordingly less variable for some designs. Under queen contiguity, the non-oracle MSE was lower than the oracle MSE for every design, most of all for Checkerboard (oracle 1.087, non-oracle 0.108) and $2 \times 2$ Blocking (oracle 0.319, non-oracle 0.121); under rook contiguity it was higher for every design except $2 \times 2$ Blocking (0.128 under both models) and Checkerboard (identical). Where a design's non-oracle MSE was lower, however, its estimate was biased and its intervals under-covered, so the lower MSE does not support valid inference. These results do not change the recommendation: Incidence-Guided Saturation also had the lowest non-oracle MSE under both neighbor types (0.087 under queen contiguity and 0.086 under rook

contiguity).

### Stability across treatment effect sizes

Under queen contiguity, each of the two design orders was the same at every $\tau \in \{0.8, 1.0, 1.5, 2.0, 3.0\}$: the order by average within-block rank did not change across these values, and neither did the order by mean MSE, although the two orders differ from each other in the bottom three designs (see Design performance under queen contiguity; Figure 3a shows mean MSE). With SRS included, the order by average rank placed SRS second at every value of $\tau$, and the Friedman statistic was 564.09, 560.33, 540.92, 526.55, and 497.55 at these five values ($p < 2.2 \times 10^{-16}$ at each). Under rook contiguity the order was also stable (Figure 3b). By average rank among the six designs and SRS, it was the same at every value of $\tau$, with SRS third behind Incidence-Guided Saturation and Balanced Quartiles. By mean MSE, the close pair of $2 \times 2$ Blocking and Isolation Buffer traded places, with Isolation Buffer ahead only at $\tau = 3$. The five values of $\tau$ share their assignments and noise, so these five comparisons are not independent confirmations of one another; they show that, under queen contiguity, the order did not change across the five values of $\tau$ we tested, given the same draws.

Within that stable order, the margins moved. Under queen contiguity, the gap in MSE between Incidence-Guided Saturation and Balanced Quartiles stayed between 0.037 and 0.041, and Incidence-Guided Saturation had the lower MSE of the two in 101 to 103 of the 160 blocks at every value of $\tau$. Isolation Buffer closed the gap instead: its MSE stayed at 0.160 at every value of $\tau$, while that of Incidence-Guided Saturation rose from 0.088 to 0.115 and that of Balanced Quartiles from 0.130 to 0.152. Isolation Buffer's gain came under the control-only regime, where the mean MSE of Incidence-Guided Saturation rose from 0.131 at $\tau = 0.8$ to 0.182 at $\tau = 3$, while that of Isolation Buffer stayed between 0.159 and 0.160. At $\tau = 2$ the two were level (0.1596 for Isolation Buffer against 0.1604), and at $\tau = 3$ Isolation Buffer had the lower control-only MSE (0.160 against 0.182). At $\tau = 2$ and $\tau = 3$, Isolation Buffer also





Figure 3: Mean squared error by design across the five values of the treatment effect, $\tau \in \{0.8, 1.0, 1.5, 2.0, 3.0\}$, under (a) queen contiguity (primary) and (b) rook contiguity (sensitivity). Each point averages the 160 scenarios of one design at one value of $\tau$, pooled over the five incidence configurations. Shaded bands show $\pm 1$ times the average of the scenario-level Monte Carlo standard errors of MSE; they describe the precision of a single scenario's MSE, not of the plotted average, whose standard error is smaller (Table 2). The shared legend lists the designs in order of pooled mean MSE under queen contiguity at $\tau = 1$. The vertical scales of the two panels differ. The gray dashed line marks simple random sampling (SRS). Under rook contiguity, $\tau$ is not identified for Checkerboard; its estimates are kept and flagged. The five values of $\tau$ share their assignments and noise.

had the lower worst case across all 160 blocks (0.207 against 0.210, and 0.208 against 0.238). Incidence-Guided Saturation remained second under the control-only regime at those two values, second to Balanced Quartiles under the both-arms regime at every value of $\tau$, and lowest in pooled MSE at every value of $\tau$. The rise in its MSE was mostly variance: its mean bias grew from 0.029 at $\tau = 0.8$ to 0.047 at $\tau = 3$, but squared bias stayed at or below 3.0% of its MSE. Appendix A7 traces both rises to a term of the estimation error that grows with $\tau$ when treated clusters have treated neighbors, and gives the block-level detail.

Under rook contiguity, Incidence-Guided Saturation kept the lowest control-only MSE at every value of $\tau$, although its margin over Isolation Buffer narrowed, from 0.095 against 0.134 at $\tau = 0.8$ to 0.131 against 0.136 at $\tau = 3$.

Except for Checkerboard under rook contiguity, coverage stayed close to 0.95 at every value of $\tau$:

between 0.946 and 0.950 for every design under queen contiguity, and between 0.947 and 0.952 for every other design under rook contiguity. The coverage of rook Checkerboard, for which $\tau$ is not identified, rose from 0.150 at $\tau = 0.8$ to 0.464 at $\tau = 3$, because its intervals widened around the wrong quantity (Appendix A7). Appendix A3 shows coverage across $\tau$ for each design.

## Robustness across blocks

Table 5 gives the distribution of MSE across the 160 queen blocks at $\tau = 1$. Incidence-Guided Saturation had the lowest median (0.080) and the lowest worst-case MSE of any design (0.169). Isolation Buffer had the narrowest range (0.128 to 0.206), because its MSE does not depend on the spillover regime, but at a higher level. Balanced Quartiles had a low median (0.115) and a worst case of 0.290. The distributions of $2 \times 2$ Blocking and Checkerboard reflected their dependence on the spillover regime: both had low first quartiles (0.062 and 0.063) and high upper quartiles (0.580 and 2.093). Checkerboard had the highest MSE in all 80 control-only blocks; in the 80 both-arms blocks, the highest MSE belonged to High Incidence Focus in 42 and to Isolation Buffer in 38. Under rook contiguity, Incidence-Guided Saturation also had the lowest worst-case MSE (0.138). These worst cases summarize variation across parameter settings; they are distinct from the conditional risk across assignments within one setting, examined next.

Table 5: Distribution of block-level mean squared error by design across the 160 blocks under queen contiguity at $\tau = 1$, pooled over the five incidence configurations (32 blocks in each). At a fixed value of $\tau$, each block contributes one scenario per design. Rows are sorted by median, which here coincides with the order of pooled mean MSE under queen contiguity (Table 2).

| Design | Best | Q25 | Median | Q75 | Worst |
|---|---|---|---|---|---|
| Incidence-Guided Saturation | 0.037 | 0.045 | 0.080 | 0.135 | 0.169 |
| Balanced Quartiles | 0.034 | 0.042 | 0.115 | 0.221 | 0.290 |
| Isolation Buffer | 0.128 | 0.150 | 0.159 | 0.169 | 0.206 |
| High Incidence Focus | 0.139 | 0.160 | 0.234 | 0.322 | 0.424 |
| 2×2 Blocking | 0.048 | 0.062 | 0.271 | 0.580 | 0.719 |
| Checkerboard | 0.051 | 0.063 | 0.899 | 2.093 | 2.843 |

## SRS benchmark and allocation-specific risk

At $\tau = 1$ under queen contiguity, pooled over the five incidence configurations and all spatial/spillover settings, Incidence-Guided Saturation has mean MSE 0.0907 against SRS 0.1285; Saturation Quadrants has 0.0900. Table 6 separates the regimes and includes all eight strategies, and Figure 5 shows the six detailed designs and SRS with the five incidence configurations kept separate: within each regime the configurations lie close together for every design, whereas the regime changes how each design compares with SRS. Incidence-Guided Saturation's control-only ratio to SRS is 0.631, whereas its both-arms ratio is 1.083. SRS, Balanced Quartiles and Balanced Halves have similar both-arms accuracy. Small mean differences should not be interpreted as equivalence, nor should pooling the regimes obscure the difference in design guidance.

Figure 4 tests each design against SRS within each regime, over the 50 independent configuration-by-surface units. Under control-only spillover, Incidence-Guided Saturation had 36.9% lower MSE than SRS (95% interval 34.5% to 39.2% lower), Saturation Quadrants 36.7% lower and Isolation Buffer 25.7% lower, each in all 50 units (Holm-adjusted $p = 6.2 \times 10^{-9}$). Under both-arms spillover, Incidence-Guided Saturation had 8.3% higher MSE than SRS (5.6% to 11.0% higher; $p = 6.1 \times 10^{-6}$) and Saturation Quadrants 4.3% higher ($p = 0.017$). Balanced Quartiles and Balanced Halves did not differ significantly from SRS under either regime, and the remaining designs had significantly higher MSE than SRS under both-arms spillover, as did High Incidence Focus, $2 \times 2$ Blocking and Checkerboard under control-only spillover. The advantage of the saturation designs over SRS is therefore specific to control-only spillover, and under queen contiguity their small both-arms disadvantage is statistically detectable. Under rook contiguity the saturation designs had 23% to 24% lower control-only MSE than SRS and 3% to 5% higher both-arms MSE, significant for Incidence-Guided Saturation ($p = 0.0075$) but not for Saturation Quadrants ($p = 0.15$), and Isolation Buffer had 5.8% higher control-only MSE than SRS. The mean is only part of the comparison, because a trial realizes a single allocation. Under

control-only spillover, the worst 10% of SRS allocations in the grid pilot had mean conditional MSE 60% above that of the average SRS allocation (0.3486 against 0.2172), and the saturation designs' worst-decile MSE was 0.53 to 0.56 times SRS's in the grid pilot and 0.64 to 0.68 times in NC. Under both-arms spillover, their worst-decile MSE was 1.05 to 1.07 times SRS's in the grid pilot and 0.93 to 0.94 times in NC (Table 9), so the small mean disadvantage there comes with no worse downside in NC.





Figure 4: Each design's mean squared error (MSE) compared with simple random sampling (SRS) at $\tau = 1$ under queen contiguity, within each spillover regime. Each point is one plus the mean paired difference in MSE over the 50 independent configuration-by-surface units divided by SRS's mean MSE in that regime, so that 1 marks equal error and values below 1 mark lower error than SRS, with its $t_{49}$ 95% interval. Filled points are significant after Holm's adjustment over the eight designs compared with SRS within the regime (Wilcoxon signed-rank test). The horizontal axis is logarithmic, ratios above 2 are printed, and rows are sorted by the control-only ratio.

To assess allocation risk, we additionally conducted a focused grid pilot with queen weights, $\tau = 1$, two fixed surfaces from each incidence configuration and the extreme combinations of $\rho$ and $\gamma$, $\rho \in \{0, 0.5\}$ and $\gamma \in \{0.5, 0.8\}$. For assignment $a$, its risk is the conditional MSE $m(a) = E_\epsilon[(\hat{\tau} - \tau)^2 \mid a, X]$. We estimated it by simulating repeated outcomes for each sampled assignment and then compared its distribution across assignments. This is different from the distribution of squared errors in a single allocation or MSE across parameter scenarios. The





Figure 5: Grid mean MSE at $\tau = 1$ with queen weights, for the six designs and simple random sampling (SRS), under each spillover regime. Points keep the five incidence configurations separate, each averaging the 16 combinations of outcome spatial dependence $\rho$ and spillover magnitude $\gamma$ within that configuration and regime; parentheses in the legend give incidence dependence $\rho_X$. Both panels use the same logarithmic scale. Table 6 gives the values pooled over configurations for all nine strategies.

Table 6: Full grid benchmark at $\tau = 1$, queen contiguity. Each regime-specific entry averages 80 scenarios (five incidence configurations, four $\rho$ and four $\gamma$ values). MSE is the mean squared error of the estimate of $\tau$; coverage is the proportion of 95% $t$-based confidence intervals, with a degrees-of-freedom-corrected standard error, that contain $\tau$. Both use the oracle fit, the spatial lag model that includes the true spillover term. Simple random sampling is complete randomization of 50 clusters. No value pools queen and rook.

| | Both arms | | Control only | |
|---|---|---|---|---|
| Design | MSE | Coverage | MSE | Coverage |
| Checkerboard | 0.0624 | 0.948 | 2.1114 | 0.951 |
| High Incidence Focus | 0.1617 | 0.950 | 0.3292 | 0.945 |
| Saturation Quadrants | 0.0442 | 0.952 | 0.1359 | 0.940 |
| Isolation Buffer | 0.1608 | 0.948 | 0.1595 | 0.950 |
| $2 \times 2$ Blocking | 0.0623 | 0.947 | 0.5761 | 0.950 |
| Balanced Quartiles | 0.0421 | 0.949 | 0.2195 | 0.942 |
| Balanced Halves | 0.0420 | 0.949 | 0.2179 | 0.943 |
| Incidence-Guided Saturation | 0.0459 | 0.949 | 0.1355 | 0.945 |
| Simple Random Sampling | 0.0424 | 0.950 | 0.2146 | 0.946 |

pilot used 100 assignment draws for each randomized design and 100 simulated outcomes per distinct assignment, and selected settings were refined to 400 outcomes on the same assignments; a design with only one possible assignment received its own outcome replication.

Averaged over the 40 units per regime in the pilot (fixed surfaces crossed with the extreme combinations of $\rho$ and $\gamma$), Incidence-Guided Saturation's control-only mean MSE is 0.1409 against SRS 0.2172, the estimated 90th percentile of allocation-specific MSE is 0.1747 against 0.2980, and the estimated worst-decile mean is 0.1936 against 0.3486. Under both arms, the corresponding mean MSE is 0.0458 against 0.0428 and worst-decile mean 0.0582 against 0.0544. Saturation Quadrants also performs favorably under control-only spillover; Table 9 in the application section compares every design with SRS on both criteria. These selected-unit results support a qualified downside argument for saturation; they are not the full-study grid estimates. The focused refinement preserves the control-only direction but reveals substantial outcome-noise contributions to estimated allocation variation, especially under both arms. Quantiles and worst-decile membership estimated from a finite number of outcomes remain uncertain. We therefore use the completed NC application below as the next setting-specific assessment rather than extrapolate exact tail protection from this pilot.

# Application: Observed NC SUD Incidence for Education-Pilot Planning

## Purpose and observed inputs

The application asks which allocation designs estimate a known education-intervention effect accurately on this geography, when some designs use historical SUD incidence to direct treatment. It supports planning an education intervention for healthcare professionals involved in SUD prevention. There are no observed intervention outcomes and no estimated relationship between local SUD incidence and education ability. Any eventual effect on SUD incidence requires a separate clinical evaluation. A real pilot might realize only one allocation per planning year, making both average estimation error and poor-allocation downside relevant.

The assignment units are 58 community college service-area clusters that partition North

Carolina's 100 counties under the study mapping (Figure 6). Northampton is assigned to Halifax Community College, Bertie to Martin Community College, and Hertford alone to Roanoke-Chowan Community College; these are analysis conventions, not exclusive service commitments. Observed county-year deaths and population estimates for ages 18–64 from the Surveillance, Epidemiology, and End Results program were aggregated to the same named clusters for each year, 2018–2021. SUD deaths were identified from death certificates with the case-adjudication algorithm of Gan and colleagues [29]. The corrected numerator supplied by Habib includes heart-failure deaths formerly excluded as presumed non-sudden. It totals 23,523 deaths over 25,594,321 person-years. The earlier numerator reproduces the totals behind Habib's unpublished report [30]; the corrected numerator is the application input. We do not infer undocumented upstream exclusion rules or zip-code allocation from the received county panel.

Annual incidence is $100,000 D_{iy}/P_{iy}$, and pooled incidence is $100,000 \sum_y D_{iy} / \sum_y P_{iy}$, with the latter population sum interpreted as person-years. All 58 clusters are present in each year, and counts and populations sum back to statewide totals. We hold these observed annual surfaces fixed, generate no synthetic incidence surface and report years separately (Figure 7). The county death-certificate source data are restricted and not publicly available; only 58-cluster summaries are reported. The data were obtained under University of North Carolina at Chapel Hill Institutional Review Board protocol 14-2036, "Sudden Unexpected Death in North Carolina" (principal investigator Ross J. Simpson, Jr., Department of Medicine).

## Geographic adaptations and treatment budgets

Queen contiguity between service areas, computed from legal county boundaries, defines primary adjacency, and rook contiguity is a sensitivity analysis. Shared legal boundaries across water can create adjacency; this is a prespecified geographic exposure proxy, not a measured professional communication network.

All eight designs and SRS are evaluated under the names used on the grid, adapted to the





Figure 6: The assignment of North Carolina's 100 counties to the 58 community college service areas used as clusters in the planned application. Each county is colored by its primary serving college, and each service area carries a single number, keyed to the legend. Hatching marks the two counties that also lie within Roanoke-Chowan Community College's broader service network: Northampton County, assigned to Halifax Community College (24), and Bertie County, assigned to Martin Community College (30). Roanoke-Chowan Community College (41) serves Hertford County alone in this analysis. The map shows county boundaries and the county-to-college assignment only; it does not depend on the SUD data.

irregular map; Appendix A8 gives the rules in full and maps the fixed regions and example assignments. Checkerboard becomes a deterministic greedy graph-coloring assignment, an interspersion analog rather than a literal rectangular checkerboard or an exact bipartite coloring. High Incidence Focus treats the 29 highest annual-rate clusters, Isolation Buffer draws a greedy random maximal independent set on the NC adjacency graph, SRS treats a random 29 of 58 clusters, and Balanced Quartiles and Balanced Halves stratify annual rate ranks and treat 29 overall. The two saturation designs use one fixed four-region partition for all years, chosen for geographic compactness and balance without consulting outcomes. Saturation Quadrants randomly assigns 20/40/60/80% to these regions each draw; Incidence-Guided Saturation ranks the regions by the mean rank of their clusters' annual per-capita rates and assigns 80/60/40/20%





Figure 7: Observed annual SUD incidence per 100,000 adults aged 18–64 in the 58 service-area clusters. These four fixed planning inputs direct incidence-aware allocation; they are not simulated outcomes or measures of education ability.

from highest to lowest; mean raw rates and pooled regional rates serve as prespecified alternative regional summaries. On the NC map, $2 \times 2$ Blocking uses spatial blocks of nearby clusters, 14 irregular groups formed once per year, and treats half of each group, rounded, at random. Treatment budgets (numbers of treated clusters) therefore differ across designs; we report them rather than modify the designs to force equal budgets (Table 7).

## Outcome model and Monte Carlo evaluation

For the primary education outcome, we set $\beta = 0$ in Equation 1, use the 58-cluster $W$, and fix $\tau = 1$, $\sigma = 1$:

$$Y = (I - \rho W)^{-1}[\tau Z + S(Z) + \epsilon], \qquad \epsilon \sim N(0, I). \tag{3}$$

Observed incidence affects assignments but neither baseline education nor the constant structural intervention effect. We estimate $\tau$ with the same validated maximum likelihood implementation

Table 7: Primary queen application treatment budgets. Entries are mean treated-cluster counts / percent of annual population aged 18–64. Counts and population shares use the same sampled assignments; population shares are recalculated for each year, including for designs whose assignments do not depend on annual incidence. Shares are geographic reach, not healthcare-professional enrollment.

| Design | 2018 | 2019 | 2020 | 2021 |
|---|---|---|---|---|
| Checkerboard | 27.00 / 50.4 | 27.00 / 50.4 | 27.00 / 50.4 | 27.00 / 50.7 |
| High Incidence Focus | 29.00 / 22.2 | 29.00 / 23.5 | 29.00 / 23.3 | 29.00 / 22.4 |
| Saturation Quadrants | 29.03 / 49.2 | 29.03 / 49.2 | 29.03 / 49.1 | 29.03 / 49.1 |
| Isolation Buffer | 15.89 / 26.7 | 15.89 / 26.7 | 15.89 / 26.7 | 15.89 / 26.7 |
| $2 \times 2$ Blocking | 28.00 / 50.0 | 31.00 / 55.1 | 27.00 / 48.0 | 29.00 / 50.3 |
| Balanced Quartiles | 29.00 / 48.5 | 29.00 / 49.7 | 29.00 / 50.6 | 29.00 / 49.8 |
| Balanced Halves | 29.00 / 50.0 | 29.00 / 50.5 | 29.00 / 49.2 | 29.00 / 49.4 |
| Incidence-Guided Saturation | 29.00 / 53.2 | 29.00 / 45.1 | 29.00 / 47.9 | 29.00 / 51.8 |
| Simple Random Sampling | 29.00 / 49.5 | 29.00 / 49.5 | 29.00 / 49.5 | 29.00 / 49.5 |

as in the grid study, with an intercept, $Z$ and the true regime-specific $S(Z)$, without $X$. As in the grid model, $\tau$ is the coefficient before spatial propagation, not an average total impact after applying $(I - \rho W)^{-1}$. For the main application and for the analyses of partial participation and sample size below, we report $\hat{\tau} \pm t_{0.975,\, n-p}\, \widehat{\mathrm{SE}} \sqrt{n/(n-p)}$, where $n$ is the number of participating colleges and $p$ the number of fitted coefficients plus $\rho$, and we test $\tau = 0$ against the same $t$ distribution. The maximum likelihood variance divides by $n$, and the normal reference distribution ignores the estimated parameters. With 58 or fewer clusters, both make the Wald interval too narrow.

Primary queen settings cross $\rho = 0, 0.2, 0.5$, $\gamma = 0.5, 0.8$, both regimes, four years and nine designs (432 reported settings). A matched hypothetical baseline sensitivity adds $X = (\mathrm{rank}_{\mathrm{average}}(rate) - 0.5)/58$ with $\beta = 1$ to both the outcome baseline and the fitted covariates (432 settings). It changes baseline and adjustment together and is not an empirical incidence–education association. A rook-contiguity sensitivity analysis of the primary model uses the extreme values $\rho = 0, 0.5$ (288 settings), and the two alternative regional summaries add 96 Incidence-Guided Saturation settings. The full application reports 1,248 settings, computed from 936 distinct simulation settings, because reported settings with the same allocations and outcome model share one simulation.

We sampled $J = 100$ assignments and simulated $R = 100$ independent outcomes per distinct assignment; a design whose set of possible assignments contains only one assignment instead received $R = 1,000$ outcomes for that assignment, rather than 100 repeated copies of it counted as separate allocations. A prespecified adaptive schedule extended allocations or outcomes where needed until the Monte Carlo standard error of mean MSE was at most 5% of mean MSE and that of coverage at most 0.01; two single-assignment settings in the matched sensitivity analysis required $R = 2,000$, and all randomized designs met these targets at $J = 100$ and $R = 100$ (Appendix A8). In the primary model, Checkerboard, Saturation Quadrants, Isolation Buffer and SRS reuse the same simulations across years, because annual incidence enters neither their allocation nor the outcome model. These repeated values are not independent annual confirmation.

For each allocation $a$, the repeated outcomes estimate the conditional MSE $m(a) = E_\epsilon[(\hat{\tau} - \tau)^2 \mid a, \text{observed inputs}]$, the expected squared error of the estimate if $a$ were the allocation realized. We report its distribution across sampled allocations, its estimated 90th percentile and the estimated mean among the worst 10% of sampled allocations, alongside unconditional mean MSE, bias and coverage. A separate tail refinement at queen $\rho = 0, 0.5$, $\gamma = 0.8$, both regimes and all years and designs kept the same allocations and extended the randomized designs to $R = 400$ outcomes per allocation, keeping $R = 1,000$ for single-assignment designs; it is not a new allocation sample. Worst-decile assignments were identified with one half of the simulated outcomes and evaluated with the other half, to avoid selection bias. Design-matrix rank, residual treatment information, aliased columns, warnings, invalid estimates or intervals, and boundary estimates of $\rho$ were recorded.

## Partial participation and sample size

All 58 colleges will be invited to take part after the pilot, but not every college will join. We therefore repeated the application for subsets of $N$ participating colleges,

$N \in \{15, 20, 25, 29, 30, 35, 40, 45, 50, 58\}$, under the education outcome model with $\beta = 0$. Under random volunteering, 50 subsets were drawn for each $N$ and shared by every design and year, so designs are compared on the same participants. In a sensitivity analysis at $N = 20$ and $N = 29$, a college's chance of joining rose linearly with its incidence rank, so that the highest-burden college was three times as likely to join as the lowest. Each design was rebuilt on the participants with its own rule, and the four saturation regions were required to contain at least two colleges each. Spatial dependence links participating colleges only, so a participant with no participating neighbor has a zero row in the participants' weights matrix $W_P$. Spillover exposure counts treated participating neighbors over all geographic neighbors, $e_j(Z) = \sum_{k \in \mathcal{N}(j)} Z_k / |\mathcal{N}(j)|$, so a non-participating neighbor counts as untreated. Spillover scales with the effect, $\gamma = \kappa\tau$ with $\kappa \in \{0.5, 0.8\}$, and the effect $\tau$ took nine values from 0 to 2 in units of the college-level outcome standard deviation. Settings crossed these with $\rho \in \{0, 0.5\}$, both spillover regimes, the nine strategies and the four planning years. With fewer than 58 participants, each setting used 20 allocations and 10 outcomes on each of the 50 subsets (10,000 fits), and a design with a single possible allocation on a subset used 200 outcomes instead. With all 58 colleges, each setting used 100 allocations and 100 outcomes, as in the main application, and it reproduced the main application's MSE and coverage within Monte Carlo error. All effect sizes share the same subsets, allocations and noise, so power curves are smooth in $\tau$. For each setting we estimated power with the corrected $t$ test above, the number of colleges needed for 80% power, and the smallest effect detectable with 80% power at each $N$.

The trial outcome is a score measured on each trained professional and averaged within each college. We write a professional's score as a college effect plus individual variation, with total variance 1, so that effects are in individual standard-deviation units. The intraclass correlation coefficient (ICC) is the share of that variance that lies between colleges, so the between-college variance is the ICC and the within-college variance is $1 - \text{ICC}$. Averaging the scores of $m$ professionals leaves the college part unchanged and divides the individual part by $m$, so the

college mean has standard deviation $\sigma_c = \sqrt{\mathrm{ICC} + (1 - \mathrm{ICC})/m}$ [1, 2]. A college-level effect of $\tau$ standard deviations is therefore an individual-level standardized effect $d = \tau\sigma_c$. With $\beta = 0$, multiplying the effect and the noise by the same constant leaves $\hat{\tau}/\widehat{\mathrm{SE}}$ unchanged, so power for any $m$, ICC and $d$ follows from the simulated college-level results. Rerunning one setting with the effect and the noise both halved reproduced its estimates to within $6 \times 10^{-8}$. In a sensitivity analysis, the number of trained professionals grew with college population ($m$ averaging 25 over participants, ICC = 0.05), so the noise variance differed between colleges while the fitted model stayed unweighted, as an analyst unaware of the difference would fit it.

## Further sensitivity analyses

We compared the nine strategies with the Friedman, Nemenyi and Holm-adjusted Wilcoxon tests used on the grid, treating the 24 combinations of year, $\rho$ and $\gamma$ as blocks, separately for each spillover regime and each value of $\beta$. The four years share one map and the strategies whose allocations ignore annual incidence share their simulations across years, so these $p$-values summarize consistency rather than independent evidence.

To check that the design comparison does not depend on the spatial model, we generated data at $N = 58$ with $\beta = 0$ from the spatial lag model and fitted them by a conditional autoregressive (CAR) model [31, 32] as well as by the spatial lag model. In the reverse direction, we generated data from a CAR model with the same mean and fitted them by both models. We also fitted two Bayesian models to the spatial lag data, a CAR model with the prior of Leroux and colleagues [33, 34] and a Bayesian spatial lag model [9]. Appendix A9 gives the four models, their priors, the Markov chain Monte Carlo settings and the convergence checks. Finally, we replaced the proportional spillover exposure by a binary indicator of any treated neighbor and by a count of treated neighbors scaled by the mean number of neighbors, with the same form in the outcome model and the fit.

## Completed results: accuracy, inference and reach

The main run generated 7,598,000 independent outcome fits. Every setting is complete and meets its prespecified precision targets for mean MSE and coverage: the largest relative Monte Carlo standard error of mean MSE is 0.04871 and the largest Monte Carlo standard error of coverage is 0.00892. There are no warnings, aliased columns, estimates of $\rho$ at the boundary of its parameter space or estimation failures. The tail refinement adds 2,280,000 independent outcomes; counting the outcomes reused from the main run only once gives 9,878,000 distinct outcomes across the two stages. Monte Carlo precision describes uncertainty in simulated performance; it does not certify interval calibration.

Figure 8 compares the eight designs with SRS by year and regime. Under control-only spillover, Saturation Quadrants has descriptive mean MSE 0.22329 against SRS 0.30761, a 27.4% reduction. Incidence-Guided Saturation reduces mean MSE by 21.1–29.9% across the four observed years (Table 8). Both saturation designs have lower mean MSE than SRS in every primary parameter setting, and approximate Monte Carlo intervals for each setting-specific difference excluded zero. Neither is uniquely best: as on the grid, the two performed similarly, and their advantage over SRS comes from the saturation structure both designs share. High Incidence Focus is year-sensitive under control-only spillover and cannot be recommended uniformly.

Under both-arms spillover, SRS mean MSE is 0.07638, Saturation Quadrants 0.07518, and Incidence-Guided Saturation ranges from 0.07428 to 0.07682 across years. SRS remains competitive with balancing, blocking and saturation. Small point differences do not establish equivalence or universal optimality. High Incidence Focus has low both-arms MSE in the primary model, but its allocation is deterministic for these fixed rates; this is conditional model-based accuracy, not evidence of randomization-based causal validity.

Mean coverage of the 95% intervals across the four years was between 94.1% and 94.9% for every design and regime, and between 94.1% and 95.1% in single years. The Wald interval covered

only 92.6% to 93.6% (Table 24). Meeting the Monte Carlo precision targets did not repair that finite-sample undercoverage, but the corrected $t$ interval described under Outcome model and Monte Carlo evaluation did (Appendix A9). The full year/design/regime bias and coverage table is in Appendix A8. Checkerboard's treatment effect is identified on this irregular graph, but weak treatment–spillover separation makes its estimates imprecise; this differs from exact rook non-identification on the rectangular grid.

Population shares contextualize performance (Table 7). High Incidence Focus treats 29 clusters but only about 22–24% of working-age population, while Isolation Buffer treats a mean of 15.89 clusters and about 27%. These population denominators measure geographic reach, not the number of healthcare professionals educated, intervention cost or participant-level precision.

Incidence-Guided Saturation sends more treatment to high-incidence regions when incidence differs between regions. On the NC map it differs little, because the four regions' mean incidence ranks lie between 24 and 34 of 58 in every year. On average, Incidence-Guided Saturation treats colleges holding 51.1% of the summed college incidence rates, against 50.4% for Saturation Quadrants and 62.2% for High Incidence Focus. Shares of deaths run the other way (49.2%, 49.6% and 35.4%), because the highest-rate colleges serve small populations. On the simulation grid, where regional incidence differed more, incidence guidance raised the treated share of incidence by 2.1 to 3.1 percentage points over Saturation Quadrants, and across surfaces the gain rose with the spread of the regions' mean incidence ranks (correlation 0.84 to 0.99; Figure 23 in Appendix A9).

Table 8: Primary application yearly mean MSE, queen contiguity; equal weights over the six $\rho/\gamma$ pairs. Saturation Quadrants and SRS reuse the same simulations across years.

| | Both arms | | Control only | | |
|---|---|---|---|---|---|
| Year | SRS | Incidence-Guided Saturation | SRS | Saturation Quadrants | Incidence-Guided Saturation |
| 2018 | 0.07638 | 0.07428 | 0.30761 | 0.22329 | 0.24285 |
| 2019 | 0.07638 | 0.07628 | 0.30761 | 0.22329 | 0.21565 |
| 2020 | 0.07638 | 0.07682 | 0.30761 | 0.22329 | 0.22029 |
| 2021 | 0.07638 | 0.07450 | 0.30761 | 0.22329 | 0.23732 |





Figure 8: Completed primary application: yearly mean MSE divided by year- and regime-matched SRS MSE, for the eight other designs with queen weights and education outcomes. Each cell averages six $\rho/\gamma$ settings equally before taking the ratio. Blue indicates lower error than SRS, orange higher error; colors use a logarithmic ratio scale and cells print the ratios. SRS mean MSE is 0.07638 under both arms and 0.30761 control-only. Years that share the same simulations are not independent replications. Absolute MSE, bias, coverage, budgets and setting-specific comparisons are in Appendix A8.

## Allocation downside and sensitivity

At the two refined queen settings, $\rho = 0$ and $\rho = 0.5$ with $\gamma = 0.8$, under control-only spillover, Saturation Quadrants' estimated 90th percentile of allocation-specific MSE is 31.8–32.9% below SRS and its estimated worst-decile mean 34.6–37.8% below. Incidence-Guided Saturation's corresponding reductions are 20.8–38.6% and 20.7–43.4%. The pattern persists under the split-half evaluation described above. Figure 22 in Appendix A8 shows the $\rho = 0.5$ setting. This supports a descriptive downside benefit alongside lower average error, conditional on the studied model and sampled assignments.

Table 9 compares every design with SRS on both criteria, mean conditional MSE and the mean of the worst 10% of sampled allocations, in the grid pilot and at the refined NC settings. Under control-only spillover, both saturation designs had lower mean and worst-decile MSE than SRS in both settings. Isolation Buffer also had a lower worst decile than SRS under control-only

spillover (0.62 of SRS in the grid pilot and 0.91 in NC), but under both-arms spillover its mean was 3.79 and 3.69 times that of SRS, and it treated fewer clusters. High Incidence Focus has a single allocation in NC. That allocation's MSE was below the SRS worst-decile mean under both regimes (0.76 under both arms and 0.64 under control-only spillover), with mean MSE close to SRS (0.93 and 1.03). In the grid pilot, however, its both-arms mean was 3.91 times that of SRS, and its NC result depends on the incidence model (next paragraph). Balanced Quartiles and Balanced Halves matched SRS on both criteria. Checkerboard and $2 \times 2$ Blocking did not improve on SRS on either criterion in any setting.

Table 9: Mean conditional MSE and worst-decile mean conditional MSE of each design relative to SRS: each entry is the design's average divided by SRS's average in the same setting and spillover regime (below 1 is lower error than SRS). Grid: focused pilot, queen contiguity, $\tau = 1$, averaged over 40 units, each a fixed incidence surface with one of the extreme combinations of $\rho$ and $\gamma$. NC: refined queen settings $\rho \in \{0, 0.5\}$, $\gamma = 0.8$, averaged with equal weight over 2018–2021 and both values of $\rho$; NC designs are the map adaptations (Checkerboard as a greedy graph-coloring assignment, $2 \times 2$ Blocking on spatial blocks of nearby clusters, and both saturation designs on four fixed regions). A design with one allocation has worst-decile mean equal to its mean.

| | Grid pilot | | | | NC application | | | |
|---|---|---|---|---|---|---|---|---|
| | Both arms | | Control only | | Both arms | | Control only | |
| Design | Mean | Worst 10% | Mean | Worst 10% | Mean | Worst 10% | Mean | Worst 10% |
| Checkerboard | 1.41 | 1.10 | 9.80 | 6.11 | 2.68 | 2.20 | 3.02 | 1.88 |
| High Incidence Focus | 3.91 | 3.11 | 1.38 | 0.87 | 0.93 | 0.76 | 1.03 | 0.64 |
| Saturation Quadrants | 1.06 | 1.05 | 0.62 | 0.53 | 0.99 | 0.94 | 0.73 | 0.64 |
| Isolation Buffer | 3.79 | 3.93 | 0.75 | 0.62 | 3.69 | 4.75 | 0.93 | 0.91 |
| $2 \times 2$ Blocking | 1.44 | 1.57 | 2.68 | 2.63 | 1.00 | 1.02 | 1.15 | 1.18 |
| Balanced Quartiles | 0.99 | 1.00 | 1.00 | 1.00 | 0.98 | 0.96 | 0.95 | 1.01 |
| Balanced Halves | 0.99 | 1.00 | 1.00 | 0.98 | 0.98 | 0.96 | 0.97 | 0.99 |
| Incidence-Guided Saturation | 1.07 | 1.07 | 0.65 | 0.56 | 0.98 | 0.93 | 0.75 | 0.68 |
| Simple Random Sampling | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |

Figure 9 shows the full allocation-to-allocation distribution for the six designs and SRS. Under control-only spillover, most Incidence-Guided Saturation allocations had lower MSE than the average SRS allocation in both studies, whereas the SRS distribution extended well above its mean.

Tail uncertainty remains material. With $J = 100$, the worst decile contains only ten sampled draws; extra outcomes reduce noise in $\widehat{m}(a)$ but do not enlarge the allocation sample. All 112 reported settings in the tail refinement for designs with more than one possible assignment





Figure 9: Distribution of allocation-specific MSE for the six designs and simple random sampling (SRS), relative to the mean MSE of SRS in the same setting (queen weights). Simulation study: focused grid pilot at $\tau = 1$, 40 fixed surface/parameter settings per spillover regime. Application study: refined NC settings ($\rho = 0, 0.5$; $\gamma = 0.8$) in each year 2018–2021. For each allocation, MSE is estimated from repeated simulated outcomes (100 in the simulation study, at least 400 in the application study). Thin lines span the 5th to 95th percentiles of allocations and thick bars the 25th to 75th; circles mark the mean. Percentiles are computed within each setting and then averaged, so bars show allocation-to-allocation spread; a design with one allocation per setting appears as a circle only. Outcome Monte Carlo noise in the per-allocation estimates widens the bars slightly.

flag uncertain worst-decile membership. Under both arms, the overlap between the worst deciles identified by the two outcome halves (the Jaccard index: allocations in both divided by allocations in either) was 0–0.25 for Incidence-Guided Saturation, and approximately 61–86% of the raw variance of estimated risk across allocations was attributable to outcome Monte Carlo noise. Saturation Quadrants' worst-decile membership was similarly unstable. Small both-arms tail differences therefore do not establish superior downside protection. Checkerboard and High Incidence Focus each have only one possible assignment for these inputs; their 90th percentile and worst-decile mean equal their conditional mean MSE, which does not imply low error or absence of outcome uncertainty.

In the matched hypothetical incidence-baseline/X-adjusted sensitivity, High Incidence Focus MSE rises to roughly 3.68–4.44 times its primary value under both arms and 1.42–2.52 times under control-only spillover. Treatment–incidence alignment leaves less residual treatment information after adjustment; this sensitivity changes baseline and adjustment jointly and does not imply that SUD incidence predicts education ability. Rook and queen comparisons matched at the same extreme combinations of $\rho$ and $\gamma$ preserve broad regime-specific conclusions. Alternative regional summaries change the regional ordering in some years; where an alternative summary gives the same ordering and ties, it gives the same set of possible assignments and so the same results. We retain the prespecified mean-rank rule rather than select a summary retrospectively. Appendix A8 reports the matched sensitivity table and regional ordering.

## Planning for realistic participation

Under both-arms spillover, the design hardly affected the number of colleges a trial needs. Every design except Checkerboard and Isolation Buffer needed 35 to 37 colleges for 80% power to detect a college-level effect of one standard deviation, and about 19 colleges for 1.5 standard deviations (Figure 10, Table 21). Checkerboard and Isolation Buffer did not reach 80% power at $\tau = 1$ even with all 58 colleges. Under control-only spillover, no design reached 80% power at $\tau = 1$ with all 58 colleges. At $\tau = 1.5$ the two saturation designs needed 28 colleges, against 29 to 32 for SRS and the rank-based designs, while $2 \times 2$ Blocking and Isolation Buffer failed to reach 80% power with 58 colleges in one of the four planning years. Power under control-only spillover rose slowly beyond about 40 colleges (Figure 11). When nearly every college participates, nearly every control has a treated neighbor, so spillover exposure varies little and is hard to separate from treatment. Non-participating neighbors restore some of that variation, and so do the saturation designs. With all 58 colleges, the smallest effect detectable with 80% power was 0.76 to 0.78 college-level standard deviations under both-arms spillover for every design except Checkerboard (1.32) and Isolation Buffer (1.50), and 1.24 to 1.25 for the two saturation designs

under control-only spillover, against 1.45 to 1.57 for SRS and the rank-based designs.





Figure 10: Number of participating colleges needed for 80% power with the corrected $t$ test, by design, for a college-level effect of $\tau = 1$ standard deviation under both-arms spillover and $\tau = 1.5$ under control-only spillover. Random volunteering, $\rho = 0.5$ and spillover $\gamma = 0.8\tau$. Dark bars show the mean over the 2018–2021 planning years and whiskers the range. Light bars mark designs that did not reach 80% power with all 58 colleges in the stated number of years, with the smallest number needed in the other years.

For a trial with $m = 25$ trained professionals per college and an ICC of 0.05, so that $\sigma_c = 0.30$, an individual-level effect of $d = 0.3$ gives power 0.71 to 0.72 with 29 colleges and 0.96 with 58 under both-arms spillover, for SRS and for both saturation designs. Under control-only spillover the same effect gives power 0.49 and 0.53 with SRS, and 0.51 and 0.64 with Incidence-Guided Saturation (Table 22 in Appendix A9). Letting the number of professionals grow with college population, at the same average of 25, reduced power by about 0.1 for every design and changed no design's relative standing.

The Wald test rejected a true null hypothesis in 11% to 13% of simulated trials with 15 colleges and in 6% to 7% with 58. With the corrected $t$ test the rejection rate was 4.4% to 5.6%, and the coverage of the corrected interval at $\tau = 1$ was between 94.0% and 95.6% for every design and regime at every number of colleges (Table 23 in Appendix A9). The colleges-needed numbers above therefore come from a test with the nominal size.





Figure 11: Power of the corrected $t$ test against the number of participating colleges for simple random sampling (SRS), the two saturation designs and Checkerboard, by spillover regime (columns) and college-level effect (rows). Random volunteering, $\rho = 0.5$ and spillover $\gamma = 0.8\tau$. Lines show the mean over the 2018–2021 planning years and bands the range, which is narrower than the lines except near 58 colleges, and the dashed line marks 80% power. The two saturation designs nearly coincide. Each number of colleges uses its own 50 random participant subsets, so the small drop from 29 to 30 colleges reflects which subsets were drawn.

The regime-specific guidance held with fewer participants, but the size of the saturation advantage depended on participation (Table 25 in Appendix A9). Checkerboard and Isolation Buffer remained worse than SRS under both-arms spillover at every number of colleges, and the rank-based designs remained within a few percent of SRS. Under control-only spillover, the saturation designs' mean MSE was 22% below that of SRS with 58 colleges, 9% to 10% below with 40, 4% to 5% below with 29 and about 1% below with 20. With few participants, non-participating neighbors already create the exposure variation that saturation otherwise supplies. When the colleges with higher incidence were more likely to volunteer, the saturation designs' advantage over SRS was 2% or less at 20 and 29 colleges. Isolation Buffer went from matching SRS under

control-only spillover with 58 colleges to 2.3 times SRS's MSE with 29 colleges and 6.2 times with 15.

The design comparison did not depend on the spatial model used to generate or fit the data, with one exception (Appendix A9). Fitting a CAR model, generating the data from a CAR model, or both, left the saturation designs with 0.76 to 0.82 times SRS's MSE under control-only spillover, and Checkerboard and Isolation Buffer the worst designs under both-arms spillover. A Bayesian spatial lag model reproduced the maximum likelihood results, with posterior means correlated 0.999 with the maximum likelihood estimates, credible-interval coverage of 94.6% to 95.3% and the same design ordering. The exception is the Bayesian CAR model with strong spatial dependence ($\rho = 0.5$). Its estimates were biased by 0.14 to 0.22 even when its chains converged, its coverage was 88% to 90%, and it did not reproduce the saturation designs' control-only advantage. That model assumes a different dependence structure from the one that generated the data, and the correctly specified Bayesian model does not share the problem. Under a binary spillover exposure Isolation Buffer was never identified, and under a count exposure the saturation designs remained the best under control-only spillover. Formal tests over the 24 combinations of year, $\rho$ and $\gamma$ rejected equal ranks for every regime and value of $\beta$ (Friedman $\chi^2$ from 135 to 180 on 8 degrees of freedom), and under control-only spillover the two saturation designs had the two best average ranks.

The application supports considering either saturation strategy when control-only spillover is plausible, and SRS alongside other randomized strategies when both-arm exposure is expected. A trial team should consider likely spillover, recruitment, cluster and participant budgets, achievable measurement precision and interval calibration before selecting one realized allocation. The findings do not establish intervention effectiveness or a final trial protocol.

# Discussion

## Summary and relevance

We compared six treatment assignment designs in the detailed grid ranking, plus two related variants and SRS, for a spatial cluster randomized trial on a grid of 100 clusters, under three mechanisms of heterogeneous baseline incidence, two spillover regimes, and a range of values for spatial dependence, spillover magnitude, and the treatment effect. Some findings held across the incidence configurations and the values of $\rho$, $\gamma$, and $\tau$ under queen contiguity. Others depended on the spillover regime, which a trial team may not know in advance.

We judged each design on two criteria: its average MSE, and the spread of MSE across the allocations it can produce. A trial realizes one allocation, so a design with a low average MSE can still give a poor estimate if some of its allocations perform badly. Chapter 2 compared simple random and block stratified sampling on the same two criteria. The spread matters most for SRS under control-only spillover: in the grid pilot, the worst 10% of SRS allocations had mean conditional MSE 0.3486, against 0.2172 for SRS allocations overall.

Under queen contiguity, Incidence-Guided Saturation had the lowest mean squared error (0.091) and Balanced Quartiles the second lowest (0.131), and the same two designs led under rook contiguity (0.072 and 0.084). Under queen contiguity, the order of the six designs was the same in each of the five incidence configurations and at every value of $\tau$, and neither the strength of spatial dependence in the outcome nor the spillover magnitude changed it; the mechanism that generated the incidence surface changed each design's MSE modestly (by under 10%, except High Incidence Focus). Coverage of the 95% intervals was close to 0.95 for every design under both neighbor types, except Checkerboard under rook contiguity, so the designs differed in precision and coverage did not separate them.

The spillover regime was the one factor that changed the queen ranking. Under queen contiguity

at $\tau = 1$, Checkerboard and $2 \times 2$ Blocking were close to the best designs when spillover reached both arms and were the two worst when it reached only control clusters (MSE 0.062 and 2.111 for Checkerboard, 0.062 and 0.576 for $2 \times 2$ Blocking), and Balanced Quartiles also lost ground under the control-only regime (0.042 and 0.219), while Incidence-Guided Saturation was first or second among the six detailed designs under both regimes at every value of $\tau$, with a both-arms MSE 8% above that of SRS. Its control-only MSE did rise with $\tau$, and Isolation Buffer, whose MSE did not, matched or passed it under that regime at $\tau = 2$ and passed it at $\tau = 3$. A design whose performance depends on the regime carries a risk that its average MSE does not show.

Checkerboard, the strict allocation of Chapter 2, failed for different reasons under the two neighbor types. Under queen contiguity its estimates stayed centered on $\tau$ with close to nominal coverage but were imprecise, because under the control-only regime only the boundary clusters separate the spillover effect from the treatment effect; under rook contiguity $\tau$ is not identified, and its estimates were centered on $\tau - \gamma$. Checkerboard intersperses treated and control clusters as finely as the grid allows, and both failures come from the dependence this pattern creates between $Z$ and the spillover covariate (Methods).

Together, the grid benchmark, the allocation-risk results (Table 9) and the NC application give guidance by scenario. When spillover is expected to reach mainly control clusters, Incidence-Guided Saturation and Saturation Quadrants had the lowest mean MSE and among the lowest worst-decile MSE, so they are the designs we recommend over SRS. Isolation Buffer also limited downside in that regime, but it should be considered only when both-arms spillover is implausible and a smaller treated budget is acceptable. When spillover is expected to reach both arms, the spread of MSE across allocations was small for SRS and the balancing and saturation designs. SRS, Balanced Quartiles and Balanced Halves performed about equally, and the saturation designs had mean MSE 4% to 8% above SRS on the grid and within 3% of it in NC, with worst-decile MSE within 7% of SRS's in both, so SRS and the saturation designs are both

reasonable choices. The number of colleges a trial needs depends far more on the spillover regime than on the design: 35 to 37 colleges detect a one-standard-deviation college-level effect under both-arms spillover with any design except Checkerboard and Isolation Buffer, whereas under control-only spillover even all 58 colleges do not, and the saturation designs' advantage over SRS shrinks as fewer colleges join. High Incidence Focus gave one fixed allocation whose MSE in NC was below the SRS worst-decile mean under both regimes. Its accuracy is model-based rather than randomization-based, however: it was about four times worse than SRS under both arms in the grid pilot, and its MSE rose 1.4–4.4-fold when baseline outcomes were related to incidence. It is a candidate only when historical incidence can be assumed unrelated to the outcome. Checkerboard and $2 \times 2$ Blocking did not improve on SRS on either criterion. The NC model assesses education outcomes rather than assuming that historical SUD incidence predicts education ability or a heterogeneous intervention effect.

Saturation Quadrants, which assigns the same saturations without reference to incidence, performed similarly to Incidence-Guided Saturation (see Treatment assignment designs), so their accuracy advantage over SRS under control-only spillover comes from the shared saturation structure, and incidence guidance lets a trial direct its highest treatment saturations to the highest-incidence regions with little or no loss of estimation accuracy. How much treatment it redirects depends on how much incidence differs between regions, a few percentage points of incidence share on the grid and less than one on the NC map, whose regions have similar incidence.

These are design-stage results, and they complement analysis-stage modeling rather than replace it. Every design was analyzed with a spatial lag model that included the spillover term, and, in the grid study, for every design whose $\tau$ was identified the estimates were close to unbiased: at $\tau = 1$, the absolute bias of each design under each regime was at most 0.048 under queen contiguity and 0.027 under rook contiguity. Given that model, the choice of design determined

how precisely $\tau$ was estimated.

## Relation to Chapter 2

Chapter 2's practical argument considered reasonably good estimation together with protection against poor allocation in its studied small-grid settings. We preserve both criteria while extending the designs, geography and incidence conditions. Our findings concern these new models and settings; they do not directly compare numerical results across chapters. The rectangular Checkerboard and its graph adaptation illustrate why a restricted allocation's low assignment variation must be interpreted together with its level of estimation error. The application also separates incidence-guided assignment from assumptions about education outcomes. No direct cross-chapter result comparison is needed to motivate these extensions.

## Limitations

These conclusions have several limitations. First, the primary estimator is an oracle. It includes the exact spillover exposure term, so its results are a best case for each design. We fit a non-oracle model that omits the spillover term as a sensitivity analysis; it was biased for every design and its intervals under-covered, but Incidence-Guided Saturation still had the lowest MSE under both neighbor types. The non-oracle model is only one departure from the oracle. We did not study an analyst who includes a spillover term of the wrong form, such as one built on the wrong neighbor definition or a distance decay.

Second, in the synthetic grid study, the designs and the fitted model used the incidence surface that generated the outcome (the matched-surface assumption in Methods). In practice, planning incidence is estimated from an earlier period and measured with error. The designs that assign treatment by incidence rank, and the covariate adjustment, would then use a noisy surface, and we did not study how that changes the comparison.

Third, in the Poisson mechanism every cluster had the same population of 100,000. Real clusters,

including the community college service areas in the Application, differ in population, so their observed rates differ in precision, and unequal populations may change how the designs that use incidence perform. In the application, letting the number of trained professionals grow with college population reduced power by about 0.1 for every design and changed no design's relative standing.

Fourth, the full synthetic comparison uses one regular $10 \times 10$ grid, with $\beta$ and $\sigma$ fixed at 1. The application adds one irregular 58-cluster geography and unequal observed populations, but does not constitute a systematic sweep over graph sizes, structures or participant budgets. Some grid results depend on its boundary geometry, while application design adaptations also change assignment support.

Fifth, the simulation shares random draws by design. Blocks within an incidence configuration share its ten incidence surfaces, so the block-level tests treat dependent blocks as independent, which is why we also compared adjacent designs over the 50 independent configuration-by-surface units. The five values of $\tau$ also share their draws, so the stability of the design order across $\tau$ is not an independent replication at each value (see Stability across treatment effect sizes).

Sixth, the simulation's base rate of 35 per 100,000 is not the rate of the county data described in the Application (see Heterogeneous baseline incidence); we kept it deliberately, because the simulation is a general design study rather than a calibration to one data set. In the Poisson mechanism, incidence enters the designs and the fitted model only through the ranks of the observed rates, so the base rate affects the simulation only through the spatial pattern of those ranks and the number of tied rates.

Seventh, application results are conditional on a continuous education-outcome model with known spillover form and constant structural effect, not an observed education intervention or demonstrated reduction in SUD. Working-age population is a geographic denominator rather than a sample of healthcare professionals. Historical rates are held fixed, so uncertainty in

their measurement and changes between planning and implementation are not propagated. The matched baseline sensitivity is hypothetical.

Eighth, the 95% Wald intervals under-covered in both the grid and the application, and the Wald test was anti-conservative with few colleges. A small-sample correction, a $t$ reference distribution with a degrees-of-freedom-corrected standard error, restored coverage of 94% to 96% for every design in the application at every number of participating colleges (Appendix A9) and of 0.946 to 0.952 for every identified design on the grid, so we report it in both studies. The finite-outcome allocation-tail estimates do not remove noise from individual risks or establish population worst cases. Settings and years that share the same simulations cannot be treated as independent confirmation. Budgets also differ; these are evaluations of retained strategies, not an equal-cost optimization.

Ninth, the participation analysis assumes that colleges volunteer at random or with probability rising with incidence, and that non-participating colleges neither transmit nor receive spillover.

## Future work

The next trial-design steps are to specify the education endpoint, eligible professionals, implementation budget and plausible spillover network, then assess interval calibration for that protocol before randomization. Additional methodological work could study noisy planning incidence, effect heterogeneity, exposure networks beyond contiguity and a broader set of graph geometries. The trial endpoint here is a measured education score, an intermediate outcome. Designing for a later reduction in SUD incidence would need a count outcome model and is left for future work. A larger allocation sample could sharpen downside estimates if that precision is needed for a final choice. These are extensions of the completed application, not missing analyses required to characterize the prespecified settings reported here.

# References


[1] Allan Donner and Neil Klar. *Design and analysis of cluster randomization trials in health research*. Arnold, 2000.

[2] Richard J. Hayes and Lawrence H. Moulton. *Cluster Randomised Trials, Second Edition*. Chapman and Hall/CRC, 2017.

[3] Donald B. Rubin. Statistics and causal inference: Comment: Which ifs have causal answers. *Journal of the American Statistical Association*, 81(396):961–962, 1986.

[4] Michael G Hudgens and M. Elizabeth Halloran. Toward Causal Inference With Interference. *Journal of the American Statistical Association*, 103(482):832–842, 2008.

[5] W. R. Tobler. A Computer Movie Simulating Urban Growth in the Detroit Region. *Economic Geography*, 46:234, 1970.

[6] F. N. Binka, F. Indome, and T. Smith. Impact of spatial distribution of permethrin-impregnated bed nets on child mortality in rural northern Ghana. *The American Journal of Tropical Medicine and Hygiene*, 59(1):80–85, 1998.

[7] Edward Miguel and Michael Kremer. Worms: Identifying Impacts on Education and Health in the Presence of Treatment Externalities. *Econometrica*, 72(1):159–217, 2004.

[8] P. A. P. Moran. The Interpretation of Statistical Maps. *Journal of the Royal Statistical Society Series B: Statistical Methodology*, 10(2):243–251, 1948.

[9] James LeSage and Robert Kelley Pace. *Introduction to Spatial Econometrics*. Chapman and Hall/CRC, 2009.

[10] Keith Ord. Estimation Methods for Models of Spatial Interaction. *Journal of the American Statistical Association*, 70(349):120–126, 1975.

[11] Roger Bivand. R Packages for Analyzing Spatial Data: A Comparative Case Study with Areal Data. *Geographical Analysis*, 54(3):488–518, 2022.

[12] Christopher Jarvis, Gian Luca Di Tanna, Daniel Lewis, Neal Alexander, and W. John Edmunds. Spatial analysis of cluster randomised trials: a systematic review of analysis methods. *Emerging Themes in Epidemiology*, 14(1):12, 2017.

[13] Gillian M. Raab and Izzy Butcher. Balance in cluster randomized trials. *Statistics in Medicine*, 20(3):351–365, 2001.

[14] Lawrence H. Moulton. Covariate-based constrained randomization of group-randomized trials. *Clinical Trials*, 1(3):297–305, 2004.

[15] Amy M Crisp, M Elizabeth Halloran, Ira M Longini, Gonzalo Vazquez-Prokopec, and Natalie E Dean. Covariate-constrained randomization with cluster selection and substitution. *Clinical Trials*, 20(3):284–292, 2023.

[16] Sarah Baird, J. Aislinn Bohren, Craig McIntosh, and Berk Özler. Optimal design of experiments in the presence of interference. *The Review of Economics and Statistics*, 100(5):844–860, 2018.

[17] Robert S. McCann, Henk van den Berg, Willem Takken, Andrew G. Chetwynd, Emanuele Giorgi, Dianne J. Terlouw, and Peter J. Diggle. Reducing contamination risk in cluster-randomized infectious disease-intervention trials. *International Journal of Epidemiology*, 47(6):2015–2024, 2018.

[18] Michael P. Leung. Rate-optimal cluster-randomized designs for spatial interference. *The Annals of Statistics*, 50(5):3064–3087, 2022.

[19] Chencheng Cai, Xu Zhang, and Edoardo M. Airoldi. Independent-set design of experiments for estimating treatment and spillover effects under network interference. In *Proceedings*

*of the 12th International Conference on Learning Representations (ICLR 2024)*, Vienna, Austria, 2024.

[20] Michael P. Leung. Cluster-randomized trials with cross-cluster interference. *Journal of the American Statistical Association*, pages 1361–1371, 2025.

[21] Samuel I. Watson and Thomas A. Smith. Design and Analysis of Randomized Trials to Estimate Spatio-Temporally Heterogeneous Treatment Effects. *Journal of the American Statistical Association*, 121(553):502–512, 2026.

[22] Mojtaba Mirzaei, Golsa Joodi, Brittany Bogle, Sarah Chen, and Ross J. Simpson. Years of Life and Productivity Loss Because of Adult Sudden Unexpected Death in the United States. *Medical Care*, 57(7):498–502, 2019.

[23] Roger Bivand and Gianfranco Piras. Comparing Implementations of Estimation Methods for Spatial Econometrics. *Journal of Statistical Software*, 63(18), 2015.

[24] Milton Friedman. The use of ranks to avoid the assumption of normality implicit in the analysis of variance. *Journal of the American Statistical Association*, 32(200):675–701, 1937.

[25] Peter Bjorn Nemenyi. *Distribution-Free Multiple Comparisons*. PhD thesis, Princeton University, Princeton, NJ, 1963.

[26] Janez Demšar. Statistical comparisons of classifiers over multiple data sets. *Journal of Machine Learning Research*, 7:1–30, 2006.

[27] Frank Wilcoxon. Individual comparisons by ranking methods. *Biometrics Bulletin*, 1(6):80–83, 1945.

[28] Sture Holm. A simple sequentially rejective multiple test procedure. *Scandinavian Journal of Statistics*, 6(2):65–70, 1979.

[29] Zoe Su Wen Gan, Wansuk Choi, Feng-Chang Lin, Rebecca Tippett, Golsa Joodi, Irion

Pursell, and Ross Joseph Simpson. Factors Underlying Increased Incidence of Sudden Unexpected Death in Rural Counties in North Carolina. *Journal of General Internal Medicine*, 34(6):815–817, 2019.

[30] Ashkan Habib. Temporal trends and social determinants of sudden death mortality in North Carolina. Master's paper, Department of Biostatistics, University of North Carolina at Chapel Hill, Chapel Hill, NC, April 2026. Unpublished.

[31] Julian Besag. Spatial Interaction and the Statistical Analysis of Lattice Systems. *Journal of the Royal Statistical Society: Series B (Methodological)*, 36(2):192–225, 1974.

[32] Noel A. C. Cressie. *Statistics for Spatial Data*. Wiley, 1993.

[33] Brian G. Leroux, Xingye Lei, and Norman E. Breslow. Estimation of Disease Rates in Small Areas: A New Mixed Model for Spatial Dependence. In M. Elizabeth Halloran and Donald Berry, editors, *Statistical Models in Epidemiology, the Environment, and Clinical Trials*, volume 116 of *The IMA Volumes in Mathematics and its Applications*, pages 179–191. Springer, New York, NY, 2000.

[34] Duncan Lee. CARBayes: An R Package for Bayesian Spatial Modeling with Conditional Autoregressive Priors. *Journal of Statistical Software*, 55(13):1–24, 2013.

[35] John Geweke. Evaluating the Accuracy of Sampling-Based Approaches to the Calculation of Posterior Moments. In José M. Bernardo, James O. Berger, A. Philip Dawid, and Adrian F. M. Smith, editors, *Bayesian Statistics 4*, pages 169–193. Oxford University Press, Oxford, 1992.

# Appendix

## A1. The eight-design comparison

Table 10 defines the two related variants excluded from the detailed six-design grid ranking but included in the main-text nine-design benchmark and application, in the format of Table 1, and Table 11 reports the comparison of all eight designs and SRS at the primary scenario, $\tau = 1$.

Table 10: The two related variants outside the detailed six-design grid ranking, in the format of Table 1. Saturation Quadrants shares its mechanism with Incidence-Guided Saturation, and Balanced Halves with Balanced Quartiles (see Treatment assignment designs). A cluster's incidence rank is its rank by the baseline incidence surface $X_k$, with ties broken at random in every draw. Clusters treated is the number of clusters treated per assignment.

| Design | Assignment rule | Clusters treated | Deterministic |
|---|---|---|---|
| Saturation Quadrants | The grid is divided into its four $5 \times 5$ coordinate quadrants, which are given saturations of 20%, 40%, 60%, and 80% in an order drawn at random for each assignment, without reference to incidence; within each quadrant, that share of its 25 clusters is treated at random | 50 | No |
| Balanced Halves | Clusters are divided by incidence rank into two strata of 50; 25 clusters are treated at random in each stratum | 50 | No |

Each excluded design was compared with its retained counterpart by the Nemenyi and Holm-adjusted Wilcoxon signed-rank tests described under Simulation design, resampling, and metrics, applied here to all eight designs and SRS. Saturation Quadrants' mean squared error was 0.0900, against 0.0907 for Incidence-Guided Saturation, under queen contiguity (Nemenyi $p = 0.99$; Holm-adjusted Wilcoxon signed-rank $p = 0.62$), and 0.0708 against 0.0717 under rook contiguity (Nemenyi $p = 1.00$; Wilcoxon $p = 1.00$). Saturation Quadrants had the marginally lower mean under both neighbor types and the better average rank in this comparison (2.394 against 2.700 under queen contiguity and 2.587 against 2.650 under rook contiguity), so retaining Incidence-Guided Saturation as the representative of the saturation mechanism does not rest on performance. Balanced Halves had a mean squared error of 0.1299, against 0.1308 for Balanced Quartiles, under queen contiguity (Nemenyi $p = 1.00$; Wilcoxon $p = 1.00$), and 0.0842 against

0.0837 under rook contiguity (Nemenyi $p = 1.00$; Wilcoxon $p = 1.00$). The two designs differ only in how finely they stratify on incidence, and we retain the finer, four-stratum version. Balanced Halves had the marginally lower mean and the better average rank under queen contiguity (3.831 against 3.906), and Balanced Quartiles had both under rook contiguity (3.369 against 3.569). Under both neighbor types, each excluded design is adjacent to its retained counterpart in mean MSE (Table 11). The MSEs and coverages of the six retained designs are those of Table 2, given here to four and three decimal places.

Table 11: Performance of all eight designs and SRS at the primary scenario, $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity), pooled over the five incidence configurations. Each entry averages the 160 scenarios of one design and neighbor type (5 incidence configurations $\times$ 4 values of $\rho$ $\times$ 4 values of $\gamma$ $\times$ 2 spillover regimes), each summarizing 250 fits of the oracle model. Rows in both panels are in order of mean squared error (MSE) under queen contiguity. Retained marks the six designs compared in the body of this chapter, and SRS is the benchmark. Average rank is the mean of each design's within-block MSE rank among the eight designs and SRS over the 160 blocks (1 = lowest MSE), so it differs from the average rank in Table 2. Under rook contiguity, $\tau$ is not identified for Checkerboard; its estimates are kept and flagged.

| Design | Retained | MSE | Coverage | Average rank |
|---|---|---|---|---|
| *Queen contiguity (primary)* | | | | |
| Saturation Quadrants | No | 0.0900 | 0.946 | 2.394 |
| Incidence-Guided Saturation | Yes | 0.0907 | 0.947 | 2.700 |
| Simple Random Sampling | Benchmark | 0.1285 | 0.948 | 3.788 |
| Balanced Halves | No | 0.1299 | 0.946 | 3.831 |
| Balanced Quartiles | Yes | 0.1308 | 0.946 | 3.906 |
| Isolation Buffer | Yes | 0.1602 | 0.949 | 5.638 |
| High Incidence Focus | Yes | 0.2455 | 0.948 | 7.763 |
| 2×2 Blocking | Yes | 0.3192 | 0.948 | 7.244 |
| Checkerboard | Yes | 1.0869 | 0.950 | 7.737 |
| *Rook contiguity (sensitivity)* | | | | |
| Saturation Quadrants | No | 0.0708 | 0.949 | 2.587 |
| Incidence-Guided Saturation | Yes | 0.0717 | 0.952 | 2.650 |
| Simple Random Sampling | Benchmark | 0.0850 | 0.947 | 3.612 |
| Balanced Halves | No | 0.0842 | 0.949 | 3.569 |
| Balanced Quartiles | Yes | 0.0837 | 0.948 | 3.369 |
| Isolation Buffer | Yes | 0.1329 | 0.950 | 6.050 |
| High Incidence Focus | Yes | 0.2062 | 0.948 | 7.969 |
| 2×2 Blocking | Yes | 0.1281 | 0.948 | 6.206 |
| Checkerboard (flagged) | Yes | 0.4799 | 0.162 | 8.988 |

## A2. Simulation mechanics

This section gives the mechanical details behind Simulation design, resampling, and metrics (Methods): the parameter grid, the random-number streams, the Monte Carlo structure, and the exact formulas for the metrics and their Monte Carlo standard errors.

**Parameter grid.** Table 12 lists the parameters that were crossed to form the 12,800 scenarios and the settings that were held fixed.

Table 12: Parameter grid of the original eight-design simulation. The crossed parameters form $5 \times 5 \times 2 \times 4 \times 4 \times 2 \times 8 = 12{,}800$ scenarios, 9,600 of them for the six designs compared in the body of this chapter; the settings in the lower panel are the same in every scenario.

| Parameter | Values | Levels |
|---|---|---|
| *Crossed* | | |
| Treatment effect $\tau$ | 0.8, 1.0 (primary), 1.5, 2.0, 3.0 | 5 |
| Incidence configuration | iid; spatially autocorrelated, $\rho_X \in \{0.20, 0.50\}$; Poisson, $\rho_X \in \{0.20, 0.50\}$ | 5 |
| Neighbor type | Queen (primary), rook (sensitivity) | 2 |
| Outcome spatial dependence $\rho$ | 0, 0.01, 0.20, 0.50 | 4 |
| Spillover magnitude $\gamma$ | 0.5, 0.6, 0.7, 0.8 | 4 |
| Spillover regime | Both arms, control only (Equation 2) | 2 |
| Design | The six designs of Table 1 and the two of Table 10 | 8 |
| *Fixed* | | |
| Grid | Regular $10 \times 10$ grid, $N = 100$ clusters | |
| Outcome model (Equation 1) | $\beta = 1$, $\sigma = 1$ | |
| Poisson mechanism | Base rate 35 per 100,000; $P = 100{,}000$ per cluster | |
| Incidence surfaces per configuration | $K = 10$ | |
| Assignments per surface | $J = 25$ (Checkerboard: one assignment, used in every draw) | |
| Fits per scenario and estimator | $KJ = 250$, each with its own noise vector | |
| Estimators | Oracle (primary) and non-oracle (sensitivity), both fit to every simulated outcome | |

**Random-number streams.** Every random draw in the simulation has its own seed, computed by hashing a key that names the draw. The key lists the draw's type (incidence surface, assignments, or noise) and the parameters that identify it, with numeric values written to a fixed number of decimal places so that equal values always give the same key. The random-number generator and its methods for normal and discrete draws are also fixed explicitly, so the streams do not depend on software defaults. Table 13 lists the three kinds of draw, the parameters in their keys, and the scenarios that therefore share them. The consequences of this scheme,

independence from the order of execution and common random numbers, are described in Methods.

Table 13: Seed keys. Each key names the kind of draw and the parameters listed here; the incidence mechanism is iid, spatial, or Poisson, and the iid configuration, which has no $\rho_X$, uses 0 in its place. $k$ indexes the incidence surface and $d$ the design. A draw is shared by every scenario whose key parameters match its own.

| Draw | Key parameters | Shared by |
|---|---|---|
| Incidence surface $X_k$ | Incidence mechanism, $\rho_X$, $k$ | Every block, design, and value of $\tau$ of the configuration |
| The $J = 25$ assignments of design $d$ on surface $k$ | Incidence mechanism, $\rho_X$, neighbor type, $\rho$, $\gamma$, spillover regime, $k$, $d$ | All five values of $\tau$ and both estimators |
| The 250 noise vectors of a block | Incidence mechanism, $\rho_X$, neighbor type, $\rho$, $\gamma$, spillover regime | All eight designs, all five values of $\tau$, and both estimators |

**Monte Carlo structure and checkpoints.** Within a scenario, fit $(k, j)$, with $k = 1, \dots, 10$ and $j = 1, \dots, 25$, uses surface $X_k$, assignment $Z_{kj}$, and noise vector $\epsilon_{kj}$, the $(k, j)$ column of the block's $100 \times 250$ noise matrix (see Simulation design, resampling, and metrics). The unit of computation is a combination of incidence configuration, neighbor type, and $\rho$: 40 units, each covering 4 values of $\gamma$, 2 spillover regimes, 8 designs, 5 values of $\tau$, 250 fits, and 2 estimators. The units ran in parallel, and the run stops if any unit fails. Each unit's results are saved together with a record of the parameter settings, the simulation code, and the software versions that produced them, and saved results are reused only if all of these match the current run, so results from different code or settings are never combined.

**Scenario metrics.** For one scenario and estimator, let $f = 1, \dots, n$ index the valid fits, those with a finite estimate and standard error (here every fit was valid, so $n = 250$). Let $L_f, U_f = \hat{\tau}_f \mp t_{0.975,\, N-p}\, \widehat{\mathrm{SE}}_f \sqrt{N/(N-p)}$, with $N = 100$ clusters and $p$ as defined in Methods (the Wald limits replace the multiplier by $z_{0.975} = \Phi^{-1}(0.975) \approx 1.96$), and let $\bar{\hat{\tau}} = n^{-1} \sum_f \hat{\tau}_f$. Then

$$\mathrm{Bias} = \frac{1}{n} \sum_{f=1}^{n} (\hat{\tau}_f - \tau), \qquad \mathrm{SD} = \left\{ \frac{1}{n-1} \sum_{f=1}^{n} \left( \hat{\tau}_f - \bar{\hat{\tau}} \right)^2 \right\}^{1/2}, \qquad \mathrm{MSE} = \frac{1}{n} \sum_{f=1}^{n} (\hat{\tau}_f - \tau)^2,$$

$$\text{Coverage} = \frac{1}{n}\sum_{f=1}^{n} \mathbf{1}\{L_f \le \tau \le U_f\}, \qquad \text{Power} = \frac{1}{n}\sum_{f=1}^{n} \mathbf{1}\{L_f > 0\},$$

so that $\text{MSE} = \text{Bias}^2 + (n-1)\,\text{SD}^2/n$.

**Surface-level standard errors.** For $m \in \{\text{Bias}, \text{MSE}, \text{Coverage}, \text{Power}\}$, let $m_k$ be the same formula applied to the valid fits from surface $k$ (here all 25). With $K = 10$ and $s(a_1, \dots, a_K) = \{(K-1)^{-1}\sum_k (a_k - \bar{a})^2\}^{1/2}$ the sample standard deviation,

$$\text{SE}(m) = \frac{s(m_1, \dots, m_K)}{\sqrt{K}}, \qquad m \pm t_{0.975,\,K-1}\,\text{SE}(m).$$

Because every fit was valid, each surface contributes 25 fits and $m = K^{-1}\sum_k m_k$. For two designs $d$ and $d'$ in the same block at the same $\tau$, the difference is paired at the surface level: with $\Delta_k = m_{d,k} - m_{d',k}$,

$$\text{SE}(m_d - m_{d'}) = \frac{s(\Delta_1, \dots, \Delta_K)}{\sqrt{K}},$$

with the same $t_{0.975,\,K-1}$ interval.

**Standard errors pooled over configurations.** For one design, neighbor type, and value of $\tau$, let $\mathcal{B}_c$ be the 32 blocks of configuration $c$ and $m_{b,k}$ the surface-$k$ metric in block $b$. The configuration-by-surface means and the pooled metric are

$$\bar{m}_{c,k} = \frac{1}{32}\sum_{b \in \mathcal{B}_c} m_{b,k}, \qquad \bar{m} = \frac{1}{50}\sum_{c=1}^{5}\sum_{k=1}^{10} \bar{m}_{c,k},$$

where $\bar{m}$ equals the mean of the metric over the 160 scenarios, and

$$\text{SE}(\bar{m}) = \frac{s(\{\bar{m}_{c,k}\})}{\sqrt{50}},$$

with $s$ taken over the 50 values $\bar{m}_{c,k}$. These are the standard errors in Table 2. For two designs $d$ and $d'$ adjacent in the mean-MSE order (Design performance under queen contiguity), let $D_{c,k} =$

$\bar{m}_{d,c,k} - \bar{m}_{d',c,k}$ for $m$ = MSE. The interval for the mean difference is $\bar{D} \pm t_{0.975,\,49}\, s(\{D_{c,k}\})/\sqrt{50}$, and the Wilcoxon signed-rank test, with the normal approximation, is applied to the 50 values $D_{c,k}$.


## A3. Supplementary statistical comparisons

This section gives the pairwise test results and two figures behind results stated in the body of this chapter.


**Pairwise tests under queen contiguity.** With SRS as a seventh member, the four pairs that Nemenyi comparisons did not separate were Balanced Quartiles against SRS ($p = 1.00$), $2 \times 2$ Blocking against High Incidence Focus ($p = 0.32$) and Checkerboard ($p = 0.39$), and Checkerboard against High Incidence Focus ($p = 1.00$). Over the 50 independent configuration-by-surface units, the mean paired differences in MSE between designs adjacent in the six-design mean-MSE order, with $t_{49}$ 95% intervals, were $-0.0401$ ($-0.0431$, $-0.0372$) for Incidence-Guided Saturation against Balanced Quartiles, $-0.0293$ ($-0.0332$, $-0.0255$) for Balanced Quartiles against Isolation Buffer, $-0.0853$ ($-0.0954$, $-0.0752$) for Isolation Buffer against High Incidence Focus, $-0.0738$ ($-0.0858$, $-0.0617$) for High Incidence Focus against $2 \times 2$ Blocking, and $-0.7677$ ($-0.7893$, $-0.7460$) for $2 \times 2$ Blocking against Checkerboard, with Wilcoxon $p \leq 4.9 \times 10^{-9}$ in every case. The better design of each pair had the lower MSE in all 50 units, except High Incidence Focus against $2 \times 2$ Blocking, where it did so in 48 (96%). This test follows the mean-MSE order. It separated High Incidence Focus from $2 \times 2$ Blocking, which the Nemenyi comparison of within-block ranks did not, because each unit's MSE averages over both spillover regimes, and there the control-only losses of $2 \times 2$ Blocking outweigh its both-arms wins.

**Pairwise tests under rook contiguity.** With SRS as a seventh member, Nemenyi comparisons separated 17 of 21 pairs; the four they did not separate were Incidence-Guided Saturation against Balanced Quartiles ($p = 0.66$) and SRS ($p = 0.14$), Balanced Quartiles against SRS ($p = 0.97$), and $2 \times 2$ Blocking against Isolation Buffer ($p = 1.00$). Holm-adjusted Wilcoxon tests separated

every pair except $2 \times 2$ Blocking against Isolation Buffer and Balanced Quartiles against SRS (both $p = 0.21$). In the surface-level comparison, Incidence-Guided Saturation had a lower MSE than Balanced Quartiles in 48 of the 50 units (mean difference $-0.0121$; $-0.0139$, $-0.0102$; Wilcoxon $p = 9.9 \times 10^{-10}$). $2 \times 2$ Blocking and Isolation Buffer were close: $2 \times 2$ Blocking had the lower MSE in 36 of the 50 units (72%; mean difference $-0.0048$; $-0.0078$, $-0.0017$; Wilcoxon $p = 0.0027$), but Isolation Buffer had the slightly better average rank (4.21 against 4.33), and the two designs traded places in mean MSE at $\tau = 3$. Every other adjacent pair differed in all 50 units. Within single incidence configurations, rook coverage was between 0.935 and 0.946 for every design except Checkerboard, whose coverage was between 0.14 and 0.15.





(a) Queen contiguity (primary)





(b) Rook contiguity (sensitivity)

Figure 12: Nemenyi critical-difference diagrams for the six designs and simple random sampling (SRS) at $\tau = 1$, pooled over the five incidence configurations. Designs are placed at their average within-block MSE rank, given in parentheses (1 = lowest MSE); gray bars join designs that the Nemenyi comparisons did not separate.

Figure 12 gives the Nemenyi critical-difference diagrams for the comparison of the six designs and SRS at $\tau = 1$, whose results are reported under Design performance under queen contiguity and Rook contiguity in the Results. Each design is placed at its average within-block MSE rank among the six designs and SRS over the 160 blocks of its neighbor type. The red arrow shows the critical difference, 0.712 at $\alpha = 0.05$, and a gray bar joins designs whose pairwise Nemenyi comparisons were all not significant. Under queen contiguity, the bars join Balanced Quartiles with SRS, and $2 \times 2$ Blocking with Checkerboard and High Incidence Focus. Under rook contiguity, they join Incidence-Guided Saturation, Balanced Quartiles and SRS, and Isolation Buffer with $2 \times 2$ Blocking. Under rook contiguity, $\tau$ is not identified for Checkerboard; its estimates are kept and flagged.




(a) Queen contiguity (primary)




(b) Rook contiguity (sensitivity)

Figure 13: Coverage of the 95% confidence intervals by design across $\tau \in \{0.8, 1.0, 1.5, 2.0, 3.0\}$, pooled over the five incidence configurations. Each point averages the 160 scenarios of one design at one value of $\tau$. The dashed red line marks the nominal 0.95 level, and the gray dashed line marks the mean coverage of simple random sampling.

Figure 13 gives the coverage of each design across the five values of $\tau$, summarized under

Stability across treatment effect sizes. The shaded bands show $\pm 1$ times the average of the scenario-level Monte Carlo standard errors of coverage; they describe the precision of a single scenario's coverage, not of the plotted average. The legend lists the designs in order of pooled mean MSE at $\tau = 1$ for the neighbor type of the panel (Table 2). The vertical axis runs from 0 to 1, so lines close to 0.95 overlap: all six under queen contiguity, between 0.946 and 0.950, and all but Checkerboard under rook contiguity, between 0.947 and 0.952. The lowest line under rook contiguity, which the legend does not mark, is Checkerboard, for which $\tau$ is not identified; its estimates are kept and flagged. The five values of $\tau$ share their assignments and noise.

## A4. Additional sensitivity tables

This section gives three tables summarized in the Results: mean squared error by level of outcome spatial dependence $\rho$ (Table 14), Checkerboard's coverage by level of $\rho$ under each neighbor type (Table 15), and mean squared error by level of spillover magnitude $\gamma$ (Table 16). The first and third are discussed under Sensitivity to spatial dependence, spillover magnitude, and spillover regime, and the second under Rook contiguity.

Table 14: Mean squared error by design across the four levels of outcome spatial dependence $\rho$, under queen contiguity at $\tau = 1$, pooled over the five incidence configurations. Each entry averages 40 scenarios (5 incidence configurations $\times$ 4 values of $\gamma$ $\times$ 2 spillover regimes). Rows are ordered by pooled mean MSE under queen contiguity (Table 2).

| Design | $\rho = 0$ | $\rho = 0.01$ | $\rho = 0.20$ | $\rho = 0.50$ |
|---|---|---|---|---|
| Incidence-Guided Saturation | 0.090 | 0.087 | 0.093 | 0.093 |
| Balanced Quartiles | 0.129 | 0.129 | 0.132 | 0.133 |
| Isolation Buffer | 0.161 | 0.157 | 0.158 | 0.165 |
| High Incidence Focus | 0.243 | 0.242 | 0.249 | 0.248 |
| 2×2 Blocking | 0.318 | 0.320 | 0.314 | 0.324 |
| Checkerboard | 1.095 | 1.077 | 1.084 | 1.092 |

Table 15: Checkerboard's 95% confidence interval coverage across the four levels of outcome spatial dependence $\rho$ at $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity), pooled over the five incidence configurations. Each entry averages 40 scenarios (5 incidence configurations $\times$ 4 values of $\gamma$ $\times$ 2 spillover regimes). Under rook contiguity, $\tau$ is not identified for Checkerboard; its estimates are kept and flagged. The nominal level is 0.95.

| Neighbor type | $\rho = 0$ | $\rho = 0.01$ | $\rho = 0.20$ | $\rho = 0.50$ |
|---|---|---|---|---|
| Queen | 0.950 | 0.952 | 0.949 | 0.949 |
| Rook | 0.171 | 0.168 | 0.161 | 0.146 |

Table 16: Mean squared error by design across the four levels of spillover magnitude $\gamma$ at $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity), pooled over the five incidence configurations. Each entry averages 40 scenarios (5 incidence configurations $\times$ 4 values of $\rho$ $\times$ 2 spillover regimes). Rows in both panels are ordered by pooled mean MSE under queen contiguity (Table 2). Under rook contiguity, $\tau$ is not identified for Checkerboard; its estimates are kept and flagged.

| Design | $\gamma = 0.5$ | $\gamma = 0.6$ | $\gamma = 0.7$ | $\gamma = 0.8$ |
|---|---|---|---|---|
| *Queen contiguity* | | | | |
| Incidence-Guided Saturation | 0.092 | 0.089 | 0.092 | 0.089 |
| Balanced Quartiles | 0.132 | 0.128 | 0.132 | 0.131 |
| Isolation Buffer | 0.159 | 0.163 | 0.160 | 0.159 |
| High Incidence Focus | 0.244 | 0.249 | 0.248 | 0.241 |
| 2×2 Blocking | 0.312 | 0.314 | 0.328 | 0.323 |
| Checkerboard | 1.108 | 1.052 | 1.086 | 1.101 |
| *Rook contiguity* | | | | |
| Incidence-Guided Saturation | 0.069 | 0.072 | 0.075 | 0.072 |
| Balanced Quartiles | 0.083 | 0.085 | 0.083 | 0.083 |
| Isolation Buffer | 0.131 | 0.133 | 0.134 | 0.133 |
| High Incidence Focus | 0.207 | 0.209 | 0.205 | 0.203 |
| 2×2 Blocking | 0.129 | 0.129 | 0.127 | 0.128 |
| Checkerboard (flagged) | 0.295 | 0.403 | 0.538 | 0.684 |

## A5. Coverage, bias–variance and rook contiguity figures

This section gives two queen-contiguity figures summarized in the Results, the coverage of each design (Figure 14) and the decomposition of MSE into squared bias and variance for one incidence configuration (Figure 15), followed by the rook-contiguity versions of these two figures and of Figure 2, as described under Rook contiguity in the Results. Each rook figure has the layout of its queen counterpart, but designs are ordered for rook contiguity, so the order differs from that of the queen figure. Under rook contiguity, $\tau$ is not identified for Checkerboard ($WZ = 1 - Z$); its estimates are kept and flagged.

Figure 16 corresponds to Figure 2.





Figure 14: Coverage of the 95% confidence intervals by design at $\tau = 1$, under queen contiguity. Each box summarizes the coverage of the 160 scenarios of one design (5 incidence configurations $\times$ 4 values of $\rho$ $\times$ 4 values of $\gamma$ $\times$ 2 spillover regimes), each estimated from 250 fits. Designs are ordered by median coverage, so the order differs from the MSE order used elsewhere. The dashed red line marks the nominal 0.95 level, and the gray dotted line the median coverage of simple random sampling. Figure 17 shows rook contiguity.





Figure 15: Decomposition of mean squared error into squared bias and variance by design at $\tau = 1$ for one incidence configuration, Poisson with $\rho_X = 0.20$, under queen contiguity. For each design, the two stacked components are the squared bias and the variance ($\mathrm{SD}^2$) of $\hat{\tau}$, each averaged over the 32 scenarios of that configuration (4 values of $\rho$ $\times$ 4 values of $\gamma$ $\times$ 2 spillover regimes). Designs are ordered by pooled mean MSE (Table 2). The gray dashed line marks the MSE of simple random sampling (SRS) in the same configuration. Figure 18 shows rook contiguity.

Figure 17 corresponds to Figure 14. Every design except Checkerboard has coverage close to the nominal level; Checkerboard's coverage, 0.162 pooled over the five incidence configurations (Table 2), is far below it.





Figure 16: Mean squared error of the oracle estimate of $\tau$ by design at $\tau = 1$, under rook contiguity; layout as in Figure 2. Checkerboard is flagged ($\tau$ not identified).





Figure 17: Coverage of the 95% confidence intervals by design at $\tau = 1$, under rook contiguity; layout as in Figure 14. Checkerboard is flagged ($\tau$ not identified).

Figure 18 corresponds to Figure 15. Nearly all of Checkerboard's MSE is squared bias, because its coefficient on $Z$ estimates $\tau - \gamma$ (Methods).





Figure 18: Squared bias and variance of $\hat{\tau}$ by design at $\tau = 1$ for the Poisson configuration with $\rho_X = 0.20$, under rook contiguity; layout as in Figure 15. Checkerboard is flagged ($\tau$ not identified).

## A6. Oracle and non-oracle estimates

Table 17 gives the mean squared error, bias, and coverage of the oracle and non-oracle models for each of the six designs, as summarized under Non-oracle sensitivity analysis in the Results.

Table 17: Oracle and non-oracle estimates of $\tau$ by design at $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity), pooled over the five incidence configurations. Each entry averages the 160 scenarios of one design and neighbor type. The oracle model has the covariates $Z$, Spill, and $X_k$; the non-oracle model omits Spill. Rows in both panels are in order of oracle MSE under queen contiguity. Under rook contiguity, $\tau$ is not identified for Checkerboard ($WZ = 1 - Z$); its estimates are kept and flagged, and the two models coincide.

| | Oracle | | | Non-oracle | | |
|---|---|---|---|---|---|---|
| Design | MSE | Bias | Coverage | MSE | Bias | Coverage |
| *Queen contiguity (primary)* | | | | | | |
| Incidence-Guided Saturation | 0.091 | 0.032 | 0.947 | 0.087 | −0.123 | 0.825 |
| Balanced Quartiles | 0.131 | 0.017 | 0.946 | 0.098 | −0.176 | 0.786 |
| Isolation Buffer | 0.160 | 0.003 | 0.949 | 0.091 | −0.175 | 0.892 |
| High Incidence Focus | 0.245 | 0.031 | 0.948 | 0.219 | −0.180 | 0.907 |
| 2×2 Blocking | 0.319 | 0.010 | 0.948 | 0.121 | −0.244 | 0.727 |
| Checkerboard | 1.087 | 0.001 | 0.950 | 0.108 | −0.206 | 0.758 |
| *Rook contiguity (sensitivity)* | | | | | | |
| Incidence-Guided Saturation | 0.072 | 0.018 | 0.952 | 0.086 | −0.121 | 0.825 |
| Balanced Quartiles | 0.084 | 0.008 | 0.948 | 0.097 | −0.176 | 0.789 |
| Isolation Buffer | 0.133 | 0.003 | 0.950 | 0.211 | −0.400 | 0.536 |
| High Incidence Focus | 0.206 | 0.018 | 0.948 | 0.223 | −0.192 | 0.903 |
| 2×2 Blocking | 0.128 | 0.004 | 0.948 | 0.128 | −0.257 | 0.710 |
| Checkerboard (flagged) | 0.480 | −0.652 | 0.162 | 0.480 | −0.652 | 0.162 |

## A7. Technical notes

This section explains two results reported in the body of this chapter, the growth with $\tau$ of the bias of Incidence-Guided Saturation and the rise with $\tau$ of the coverage of Checkerboard under rook contiguity, and closes with block-level detail for the results across $\tau$. The stored results keep neither $\hat{\rho}$ nor the standard error of each fit, so we re-ran every block for the six designs, both neighbor types, and all five values of $\tau$, 2.4 million fits of the oracle model, recording $\hat{\rho}$ and the standard error, and the re-run reproduced the stored results in all 9,600 scenarios. Numbers below that involve $\hat{\rho}$, the standard error, or the terms of Equation 4 come from this re-run; the others come from the stored results.

### Identification diagnostics

Two combinations of design and neighbor type weaken or remove the information that separates $\tau$ from the spillover term. Under rook contiguity, Checkerboard gives $WZ = 1 - Z$ exactly, because every neighbor of a treated cluster is a control and every neighbor of a control is treated. Both spillover covariates then equal $\gamma(1 - Z)$, a linear combination of the intercept and $Z$, so $\tau$ is not identified: the fitting routine drops the aliased spillover column, and the coefficient on $Z$ estimates $\tau - \gamma$. Chapter 2 noted the same consequence of exact collinearity between treatment and spillover exposure, $\widehat{\beta} \approx \beta - \psi$ in its notation. The non-oracle model has no spillover column to drop, but its Checkerboard estimates under rook contiguity have the same defect. Under queen contiguity, each of the 64 interior clusters has four treated and four control neighbors, so $WZ = 1/2$ at every interior cluster. Under the control-only regime the spillover covariate then equals $(\gamma/2)(1 - Z)$ at those clusters, a linear combination of the intercept and $Z$, and only the 36 clusters on the grid boundary carry information that separates it from the intercept and $Z$; $\tau$ is identified, but imprecisely. Under the both-arms regime it is the constant $\gamma/2$ at interior clusters, confounded with the intercept but not with $Z$. Isolation Buffer under rook contiguity can also, rarely, draw exactly the checkerboard pattern, a maximal independent set that equals

one color class of the grid. This happened in 4 of its 40,000 rook draws and affected one fit in each of 20 scenarios, 4 at each value of $\tau$. We flag every fit in which the fitting routine reports an aliased column and every scenario in which some draw has $\text{rank}([1, Z, WZ]) < 3$. Aliased estimates are kept in all summaries. In the exhibits, we flag Checkerboard under rook contiguity, where every fit is aliased; the Isolation Buffer scenarios, each with one aliased fit among its 250, are noted here and carry no flag in the exhibits.

**Estimation error and its dependence on $\tau$**

For one fit $(k, j)$, write $Y$, $Z$, and $\epsilon$ for $Y_{kj}$, $Z_{kj}$, and $\epsilon_{kj}$ (Simulation design, resampling, and metrics). Let $V = [1, Z, S(Z), X_k]$ be the $100 \times 4$ covariate matrix of the oracle model, so that Equation 1 reads $(I - \rho W)Y = V\theta + \epsilon$ with $\theta = (0, \tau, 1, \beta)^\top$. Let $A = (I - \rho W)^{-1}$ and $V^+ = (V^\top V)^{-1} V^\top$, and for a vector $v$ write $[V^+ v]_Z$ for the coefficient on $Z$ when $v$ is regressed on the columns of $V$ by least squares. Given $\hat{\rho}$, the estimated coefficients are $V^+(I - \hat{\rho} W)Y$ (Estimation). Because $(I - \hat{\rho} W)Y = V\theta + \epsilon + (\rho - \hat{\rho})WY$ and $WY = WA(V\theta + \epsilon)$,

$$\hat{\tau} - \tau = [V^+ \epsilon]_Z + (\rho - \hat{\rho})\, h + \tau(\rho - \hat{\rho})\, g, \tag{4}$$

where

$$g = [V^+ WAZ]_Z, \qquad h = [V^+ WA\{S(Z) + \beta X_k + \epsilon\}]_Z.$$

The first term has mean zero given $Z$ and $X_k$. The last term carries a factor of $\tau$. It is present exactly when $g \neq 0$, where $g$ is the coefficient on $Z$ when the lagged treatment $WAZ = WZ + \rho W^2 Z + \rho^2 W^3 Z + \cdots$ is regressed on the model's own covariates, and its sign and size are set by the error in $\hat{\rho}$. The concentrated likelihood depends on $Y$ only through the residual sum of squares of $(I - \tilde{\rho} W)Y$ on $V$, and the part of that residual that involves $\tau$ is $\tau(\rho - \tilde{\rho})$ times the residual of $WAZ$ on $V$. If $WAZ$ lies in the column space of $V$, that part vanishes for every $\tilde{\rho}$, so $\hat{\rho}$ is the same at every value of $\tau$; if in addition $g = 0$, then $\hat{\tau} - \tau$ is the same at every value of

$\tau$. Equation 4 held on every re-run fit, with a largest residual of $4.2 \times 10^{-13}$; for Checkerboard under rook contiguity it held in the reduced form given below.

Two consequences of Equation 4 explain the results for $\tau$ reported in the body.

First, for designs whose treated clusters have treated neighbors, the last term gives a small positive bias that grows with $\tau$. Under queen contiguity, pooled over the 160 blocks, the bias of Incidence-Guided Saturation rose from 0.029 at $\tau = 0.8$ to 0.047 at $\tau = 3$ (Stability across treatment effect sizes), while that of Isolation Buffer stayed between 0.002 and 0.004. Almost all of the rise is the last term of Equation 4. In our fits, $\hat{\rho}$ was biased downward by about 0.06 on average (for Incidence-Guided Saturation, by 0.071 at $\tau = 0.8$ and 0.054 at $\tau = 3$). We observed this downward bias in these simulations; we did not derive it or check it against a published finite-sample result. With $\rho - \hat{\rho}$ positive on average, the last term is positive and grows with $\tau$ for any design with $g > 0$. For Incidence-Guided Saturation, $g$ averaged 0.371 over the queen fits, and the last term contributed 0.021 of the bias at $\tau = 0.8$ and 0.043 at $\tau = 3$; the first term contributed 0.001 at both values, and the second 0.007 and 0.002. For Isolation Buffer, $g$ averaged 0.020, and the last term contributed 0.001 and 0.004. Most of the difference in $g$ comes from the control-only regime. Under the both-arms regime with $\rho = 0$, the lagged treatment is $WZ = S(Z)/\gamma$, one of the covariates, so $g = 0$ for every design. Under the control-only regime, $WZ = S(Z)/\gamma + Z \circ WZ$, and at $\rho = 0$, $g$ is close to the average share of treated neighbors among treated clusters. That share is 0.57 for Incidence-Guided Saturation, whose treated clusters are concentrated in the high-saturation quadrants, and exactly 0 for Isolation Buffer, whose treated clusters have no treated neighbors. For Isolation Buffer, $Z \circ WZ = 0$, so the two regimes define the same spillover covariate and the same $g$, which is 0 at $\rho = 0$ and about 0.06 at $\rho = 0.5$; at $\rho = 0$, its $\hat{\rho}$ and its estimation error were the same at every value of $\tau$, up to the optimizer's tolerance.

The same term explains why the control-only MSE of Incidence-Guided Saturation rose from

0.131 at $\tau = 0.8$ to 0.182 at $\tau = 3$ while that of Isolation Buffer did not. Under that regime, averaged over the 80 queen blocks, the variance of the last term of Equation 4 rose from 0.008 to 0.061 for Incidence-Guided Saturation, while the variance of the rest of the error changed little (0.119 and 0.115). The variance of the last term grew more slowly than $\tau^2$ because $\hat{\rho}$ became less variable as $\tau$ grew. For Isolation Buffer, the variance of the last term stayed below 0.0002. The rise in bias slowed at larger values of $\tau$ for a related reason: the part of the likelihood that involves $\tau$ sharpens it around the true $\rho$ as $\tau$ grows, so the downward bias of $\hat{\rho}$ shrank.

Second, the decomposition explains why the coverage of Checkerboard under rook contiguity rose with $\tau$. Under rook contiguity, Checkerboard's coverage rose from 0.150 at $\tau = 0.8$ to 0.464 at $\tau = 3$ (Stability across treatment effect sizes), although its coefficient on $Z$ estimates $\tau - \gamma$ at every value of $\tau$. For this design $WZ = 1 - Z$, and because $W$ is row-standardized, $W^2 Z = W(1 - Z) = Z$. The powers of $W$ applied to $Z$ therefore alternate between $1 - Z$ and $Z$, and $WAZ = \{(1 - Z) + \rho Z\}/(1 - \rho^2)$ lies in the span of the intercept and $Z$. The derivation of Equation 4 applies with the aliased spillover column dropped, $V = [1, Z, X_k]$ and $\theta = (\gamma, \tau - \gamma, \beta)^\top$, so that $\tau - \gamma$ takes the place of $\tau$, and $g = -1/(1 + \rho)$. Two consequences follow: $\hat{\rho}$ is the same at every value of $\tau$, and

$$\hat{\tau} - \tau = -\gamma + \delta + (\tau - \gamma)\,\frac{\hat{\rho} - \rho}{1 + \rho},$$

where $\delta$ collects the first two terms of that decomposition and, like $\hat{\rho}$, does not depend on $\tau$. The error in $\hat{\rho}$ is therefore multiplied by $\tau - \gamma$, which grows with $\tau$. The mean standard deviation of $\hat{\tau}$ rose from 0.202 at $\tau = 0.8$ to 0.327 at $\tau = 3$, and the standard error tracked it, rising on average from 0.199 to 0.322. With the bias held near $-\gamma$, wider intervals covered $\tau$ more often. The rise was largest at $\rho = 0$ (coverage 0.157 to 0.562) and smallest at $\rho = 0.5$ (0.142 to 0.284), consistent with the factor $1/(1 + \rho)$. The same term raised the MSE from 0.477 to 0.567. About three quarters of that increase was variance, $(n - 1)\mathrm{SD}^2/n$ averaged over scenarios (Appendix

A2), which rose from 0.041 to 0.109. The other quarter was squared bias, which rose from 0.436 to 0.458 because $\hat{\rho}$ was biased slightly downward, moving the mean bias from $-0.650$ to $-0.667$. The higher coverage at large $\tau$ reflects wider intervals around the wrong quantity, not a recovery of $\tau$.

**Block-level detail.** Under queen contiguity, the average rank of Incidence-Guided Saturation rose from 1.41 at $\tau = 0.8$ to 1.85 at $\tau = 3$, while that of Balanced Quartiles stayed between 2.13 and 2.14 and that of Isolation Buffer fell from 3.71 to 3.31. Incidence-Guided Saturation had the lower MSE of it and Balanced Quartiles in 103, 102, 102, 102, and 101 of the 160 blocks at $\tau = 0.8$, 1, 1.5, 2, and 3, and a lower MSE than Isolation Buffer in 75, 73, 56, 40, and 12 of the 80 control-only blocks. Its worst case across blocks was the lowest of the six designs at $\tau \leq 1.5$, but at $\tau = 2$ and $\tau = 3$ that of Isolation Buffer was lower (0.207 against 0.210, and 0.208 against 0.238). Under rook contiguity, at $\tau = 3$, Incidence-Guided Saturation had the lower MSE in 47 of the 80 control-only blocks, and its worst case across rook blocks was the lowest of the six designs at every value of $\tau$ except $\tau = 3$, where that of Isolation Buffer was lower (0.173 against 0.174). The coverage of rook Checkerboard was 0.150, 0.162, 0.212, 0.286, and 0.464 at $\tau = 0.8$, 1, 1.5, 2, and 3.

## A8. Observed-incidence application detail

The primary application numbers come from the aggregate performance and allocation-risk summaries of the main run and of the separate tail refinement. Annual tables average the six queen parameter pairs equally, without pooled Monte Carlo intervals. Each random draw used a fixed, reproducible seed. An independent check recomputed performance from the stored fits, checked annual treatment budgets and regional orderings, and checked the allocations and outcomes reused from the main run in the tail refinement. The county death-certificate source data are restricted and not publicly available; only 58-cluster summaries are reported.

For randomized designs, the prespecified refinement schedule allowed $J = 100, 200, 400$ and $R =$

100, 200, 400, 1000, 2000, 4000; whichever source of Monte Carlo error, allocations or outcomes, contributed more to the shortfall from the precision targets was extended. All randomized designs met the targets at $J = 100$ and $R = 100$. For designs with a single possible assignment, only outcomes were extended. If an allocation occurs $n_a$ times among $J$ draws, its risk estimate enters the mean with weight $n_a/J$. The variance due to outcome noise therefore involves squared weights $(n_a/J)^2$, not $n_a/J^2$ as if duplicate estimates were independent. Bias and coverage use the same accounting of frequencies and covariances. The overall precision includes both variation across assignments and outcome noise given an assignment; a design whose sampled assignments happened to coincide is distinguished from one with only one possible assignment. Approximate Monte Carlo standard errors of setting-specific differences between designs treat the designs' random draws as independent, whereas averages across settings or models do not assume that shared allocations are independent. Settings with the same set of possible assignments shared their simulations, with annual treatment counts and population shares recalculated.

Estimated risk variance is reported raw and with its outcome Monte Carlo noise contribution subtracted. Signed corrected estimates are retained rather than silently truncated; none is negative in the NC refinement. Quantiles and worst-decile means use noisy estimated conditional risks. To avoid selection bias, worst-decile assignments were identified with one half of the simulated outcomes and evaluated with the other half, and the roles of the two halves were then reversed. The Jaccard overlap of the two worst deciles describes sampled tail membership, not a confidence interval or population tail probability. For a design with only one possible assignment, an overlap of one is uninformative.

**Design adaptations.** Before simulation, we checked the 58-cluster row-standardized contiguity matrix $W$, its binary adjacency and its row order against the boundary geometry. On the NC map, Checkerboard visits clusters by decreasing degree, chooses the arm that conflicts least with assigned neighbors, breaks equal conflicts toward control, and complements the assignment if

more than half are treated. In Balanced Quartiles and Balanced Halves, odd-size strata receive their necessary extra treatments at random; in Balanced Halves, one half receives 14 treatments and the other 15, with the extra-treatment half chosen randomly. The four-region partition used by both saturation designs was selected from 250 candidates generated by a geographic $k$-means procedure, by compactness and balance in reference population, cluster count and county count, without consulting outcomes; reference population is pooled person-years divided by four. Incidence-Guided Saturation first ranks clusters by annual per-capita rates, averages their ranks equally within each region, ranks those four means, and assigns 80/60/40/20% from highest to lowest. Regional ties are broken randomly per allocation, and local treatment counts are rounded under the retained design rules. Per-capita cluster rates already account for population size; regional mean ranks answer an equally weighted cluster question, whereas pooled regional deaths/population weights larger clusters more heavily. Mean raw rates and pooled regional rates are evaluated as prespecified sensitivities rather than chosen by performance. The grid rule averages $X$ directly: mean ranks align with its rank-scaled Poisson cases but are a deliberate adaptation for the application, rather than the exact rule used for continuous grid incidence. The 14 groups used by $2 \times 2$ Blocking are formed once per year by $k$-means on standardized projected coordinates, incidence ranks and log(1+population), then held fixed; half of each group, rounded, is treated at random, and the single-cluster group of each year remains control, because half of one cluster rounds to zero. This is not a set of literal square blocks.

The fixed regional criterion is $C = 3s_P + 1.5s_K + 1.5s_D + c/d_{\max}$, where $s_P$, $s_K$ and $s_D$ are the standard deviations of regional population, cluster and county shares. Here $c$ averages within-region distances to regional centers and $d_{\max}$ is the maximum pairwise distance between the projected cluster coordinates. Candidates use standardized projected coordinates and are selected without outcome performance. The fixed groups used by $2 \times 2$ Blocking contain one to eight clusters; yearly total treatments are 28, 31, 27 and 29. Table 18 documents alternative summaries before performance evaluation.

Table 18: Regional ordering from highest to lowest summary, using the fixed region IDs in Figure 19. Primary mean ranks weight clusters equally; pooled regional rates weight cluster rates by population.

| Year | Mean cluster rank | Mean cluster rate | Pooled regional rate |
|---|---|---|---|
| 2018 | 2,1,3,4 | 2,4,1,3 | 4,3,2,1 |
| 2019 | 4,2,3,1 | 4,2,3,1 | 4,3,1,2 |
| 2020 | 2,4,1,3 | 2,4,1,3 | 4,3,2,1 |
| 2021 | 2,1,4,3 | 2,4,1,3 | 4,3,1,2 |





Figure 19: Fixed four-region partition used by both saturation strategies in all years, chosen from 250 geographic candidates before outcome evaluation.





Figure 20: One illustrative queen assignment from each application strategy using 2018 observed incidence and fixed geography. These sampled assignments illustrate the adaptations; they were not selected by observed performance.





Figure 21: Primary queen setting-specific mean MSE ratios to year-matched SRS. Teal cells have lower MSE than SRS and red cells higher; setting-specific Monte Carlo errors are in the source table. Parameters and spillover regimes are kept separate; this plot does not pool neighbor definitions.

Allocation-risk estimates for the refined setting $\rho = 0.5$, $\gamma = 0.8$ (Figure 22) support the downside comparison in the body.

Table 19 retains MSE, bias and coverage for every design in every year; budgets are in Table 7. More granular setting-specific results, precision components, residual treatment information and warning and failure records are kept as aggregate output tables. The absence of warnings and failures is a verified result, not a sign that diagnostics were skipped.

Table 20 reports Incidence-Guided Saturation's matched annual mean-MSE ratios. Rook means use only the four extreme combinations of $\rho$ and $\gamma$ shared with the primary analysis. Baseline/X-adjusted and regional-summary means use the six queen pairs. These are matched contrasts,





Figure 22: Allocation-specific conditional MSE in the refined primary queen setting $\rho = 0.5, \gamma = 0.8$, by year and spillover regime. Mean MSE, the estimated 90th percentile of allocation-specific MSE and the estimated worst-decile mean summarize the same $J = 100$ sampled assignments, with at least 400 independent outcomes per assignment of a randomized design or 1,000 for designs with a single possible assignment. These tail estimates, based on a finite number of outcomes, are descriptive, with uncertain membership; they are not quantiles of realized errors or a fresh allocation confirmation.

not ratios of unmatched pooled analyses.

## A9. Participation, power and sensitivity analyses for the NC application

This section gives the detail behind Planning for realistic participation and the sensitivity analyses of the application. All numbers come from aggregate summaries of runs that wrote to their own output folders, each with a manifest of parameters, code hashes and package versions.

Table 19: Primary queen application performance by design and planning year. Each entry averages the six $\rho/\gamma$ pairs of one spillover regime with equal weight; MSE, bias and coverage of the corrected $t$ interval are Monte Carlo estimates. Checkerboard, Saturation Quadrants, Isolation Buffer and SRS use the same simulations in every year, because annual incidence enters neither their allocation nor the outcome model, so their rows repeat; repeated values are not independent annual confirmation. Treatment counts and population shares are in Table 7.

| | | Both arms | | | Control only | | |
|---|---|---|---|---|---|---|---|
| Design | Year | MSE | Bias | Coverage | MSE | Bias | Coverage |
| Checkerboard | 2018 | 0.21591 | -0.0074 | 0.949 | 0.92036 | 0.0100 | 0.948 |
| | 2019 | 0.21591 | -0.0074 | 0.949 | 0.92036 | 0.0100 | 0.948 |
| | 2020 | 0.21591 | -0.0074 | 0.949 | 0.92036 | 0.0100 | 0.948 |
| | 2021 | 0.21591 | -0.0074 | 0.949 | 0.92036 | 0.0100 | 0.948 |
| High Incidence Focus | 2018 | 0.07172 | 0.0160 | 0.948 | 0.21426 | 0.0237 | 0.948 |
| | 2019 | 0.07180 | 0.0063 | 0.951 | 0.43019 | 0.0227 | 0.945 |
| | 2020 | 0.07292 | 0.0094 | 0.946 | 0.25918 | 0.0327 | 0.946 |
| | 2021 | 0.07031 | 0.0104 | 0.951 | 0.35318 | 0.0296 | 0.945 |
| Saturation Quadrants | 2018 | 0.07518 | 0.0208 | 0.949 | 0.22329 | 0.0464 | 0.941 |
| | 2019 | 0.07518 | 0.0208 | 0.949 | 0.22329 | 0.0464 | 0.941 |
| | 2020 | 0.07518 | 0.0208 | 0.949 | 0.22329 | 0.0464 | 0.941 |
| | 2021 | 0.07518 | 0.0208 | 0.949 | 0.22329 | 0.0464 | 0.941 |
| Isolation Buffer | 2018 | 0.28591 | 0.0088 | 0.947 | 0.28575 | 0.0106 | 0.947 |
| | 2019 | 0.28591 | 0.0088 | 0.947 | 0.28575 | 0.0106 | 0.947 |
| | 2020 | 0.28591 | 0.0088 | 0.947 | 0.28575 | 0.0106 | 0.947 |
| | 2021 | 0.28591 | 0.0088 | 0.947 | 0.28575 | 0.0106 | 0.947 |
| $2 \times 2$ Blocking | 2018 | 0.07609 | 0.0099 | 0.948 | 0.30622 | 0.0281 | 0.944 |
| | 2019 | 0.07808 | 0.0143 | 0.945 | 0.43630 | 0.0314 | 0.942 |
| | 2020 | 0.07764 | 0.0122 | 0.949 | 0.31848 | 0.0281 | 0.945 |
| | 2021 | 0.07736 | 0.0107 | 0.947 | 0.36168 | 0.0289 | 0.943 |
| Balanced Quartiles | 2018 | 0.07610 | 0.0170 | 0.947 | 0.29352 | 0.0315 | 0.944 |
| | 2019 | 0.07624 | 0.0175 | 0.948 | 0.30616 | 0.0367 | 0.944 |
| | 2020 | 0.07530 | 0.0158 | 0.947 | 0.28932 | 0.0356 | 0.943 |
| | 2021 | 0.07453 | 0.0175 | 0.948 | 0.28439 | 0.0354 | 0.944 |
| Balanced Halves | 2018 | 0.07458 | 0.0158 | 0.948 | 0.29101 | 0.0395 | 0.945 |
| | 2019 | 0.07517 | 0.0167 | 0.949 | 0.29955 | 0.0360 | 0.945 |
| | 2020 | 0.07466 | 0.0150 | 0.948 | 0.30610 | 0.0372 | 0.944 |
| | 2021 | 0.07584 | 0.0160 | 0.946 | 0.29089 | 0.0340 | 0.944 |
| Incidence-Guided Saturation | 2018 | 0.07428 | 0.0174 | 0.949 | 0.24285 | 0.0464 | 0.943 |
| | 2019 | 0.07628 | 0.0233 | 0.949 | 0.21565 | 0.0522 | 0.941 |
| | 2020 | 0.07682 | 0.0209 | 0.947 | 0.22029 | 0.0474 | 0.942 |
| | 2021 | 0.07450 | 0.0197 | 0.950 | 0.23732 | 0.0451 | 0.942 |
| Simple Random Sampling | 2018 | 0.07638 | 0.0135 | 0.947 | 0.30761 | 0.0378 | 0.945 |
| | 2019 | 0.07638 | 0.0135 | 0.947 | 0.30761 | 0.0378 | 0.945 |
| | 2020 | 0.07638 | 0.0135 | 0.947 | 0.30761 | 0.0378 | 0.945 |
| | 2021 | 0.07638 | 0.0135 | 0.947 | 0.30761 | 0.0378 | 0.945 |

The production application files were unchanged. Unless stated otherwise, results use random volunteering, $\beta = 0$, $\kappa = 0.8$ and the corrected $t$ test, and they average the four planning years.

**Colleges needed and smallest detectable effect.** Table 21 gives, for each strategy, the number of colleges needed for 80% power and the smallest college-level effect detectable with

Table 20: Incidence-Guided Saturation sensitivity MSE divided by matched primary MSE, by year and regime. Baseline adds rank-scaled $X$ to both generation and fit; rook uses the matched extreme combinations of $\rho$ and $\gamma$. Regional-summary alternatives preserve fixed regions.

| Sensitivity | Regime | 2018 | 2019 | 2020 | 2021 |
|---|---|---|---|---|---|
| Baseline / adjusted | Both | 1.016 | 1.030 | 1.015 | 1.035 |
| Baseline / adjusted | Control | 1.026 | 1.023 | 1.042 | 1.040 |
| Rook contiguity | Both | 1.005 | 0.998 | 0.985 | 0.998 |
| Rook contiguity | Control | 0.967 | 0.969 | 0.971 | 1.036 |
| Mean regional rate | Both | 1.034 | 1.000 | 1.000 | 1.031 |
| Mean regional rate | Control | 0.907 | 1.000 | 1.000 | 0.928 |
| Pooled regional rate | Both | 1.015 | 0.979 | 0.981 | 1.003 |
| Pooled regional rate | Control | 0.962 | 1.133 | 1.061 | 1.030 |

80% power at 29 and 58 colleges. The number of colleges needed is interpolated monotonically between the simulated values of $N$ within each year, averaged over years and rounded up to a whole college. Results at $\rho = 0$ differed from those at $\rho = 0.5$ by about two colleges or fewer. Power curves are not perfectly monotone in $N$ within Monte Carlo error, because the participant subsets differ between values of $N$, and we report the dips rather than smooth them.

Table 21: Colleges needed for 80% power and smallest effect detectable with 80% power (MDE, college-level standard deviations), corrected $t$ test, random volunteering, $\rho = 0.5$, spillover $\gamma = 0.8\tau$, mean over the 2018–2021 planning years. $> 58$: 80% power not reached with all 58 colleges in at least one year. $> 2$: 80% power not reached at the largest simulated effect, $\tau = 2$.

| | Colleges needed | | MDE, 29 colleges | | MDE, 58 colleges | |
|---|---|---|---|---|---|---|
| Design | Both arms $\tau = 1$ | Control only $\tau = 1.5$ | Both | Control | Both | Control |
| Checkerboard | $> 58$ | $> 58$ | 1.70 | 1.86 | 1.32 | $> 2$ |
| High Incidence Focus | 35 | 30 | 1.13 | 1.51 | 0.76 | 1.57 |
| Saturation Quadrants | 36 | 28 | 1.14 | 1.47 | 0.76 | 1.24 |
| Isolation Buffer | $> 58$ | $> 58$ | $> 2$ | $> 2$ | 1.50 | 1.50 |
| $2 \times 2$ Blocking | 37 | $> 58$ | 1.15 | 1.63 | 0.78 | 1.60 |
| Balanced Quartiles | 36 | 31 | 1.14 | 1.50 | 0.77 | 1.46 |
| Balanced Halves | 36 | 29 | 1.13 | 1.49 | 0.77 | 1.46 |
| Incidence-Guided Saturation | 36 | 28 | 1.13 | 1.46 | 0.76 | 1.25 |
| Simple Random Sampling | 36 | 32 | 1.14 | 1.50 | 0.77 | 1.45 |

**Interval calibration.** We tried several corrections before adopting one, with the rule that a method is adopted only if its coverage lies between 94.0% and 96.0% for every design and regime. On the stored fits of the main application ($\beta = 0$), the Wald interval covered 92.6% to 93.6% by design and regime. A $t$ reference distribution alone gave 93.2% to 94.1%, a degrees-of-freedom-corrected standard error alone 93.5% to 94.4%, and the two together 94.1% to 94.9%.

Table 22: Power of the corrected $t$ test for an individual-level standardized effect $d$ with simple random sampling, by the number of trained professionals per college ($m$) and the intraclass correlation coefficient (ICC), with $\sigma_c = \sqrt{\text{ICC} + (1 - \text{ICC})/m}$ and $\tau = d/\sigma_c$. Random volunteering, $\rho = 0.5$, spillover $\gamma = 0.8\tau$, mean over the four planning years.

| | | | Both arms | | | | Control only | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | 29 colleges | | 58 colleges | | 29 colleges | | 58 colleges | |
| $m$ | ICC | $\sigma_c$ | $d = 0.2$ | $d = 0.3$ | $d = 0.2$ | $d = 0.3$ | $d = 0.2$ | $d = 0.3$ | $d = 0.2$ | $d = 0.3$ |
| 10 | 0.01 | 0.330 | 0.33 | 0.62 | 0.61 | 0.90 | 0.22 | 0.41 | 0.24 | 0.45 |
| 10 | 0.05 | 0.381 | 0.27 | 0.51 | 0.50 | 0.82 | 0.18 | 0.33 | 0.20 | 0.36 |
| 10 | 0.10 | 0.436 | 0.22 | 0.41 | 0.40 | 0.71 | 0.15 | 0.27 | 0.17 | 0.30 |
| 25 | 0.01 | 0.223 | 0.61 | 0.91 | 0.90 | 1.00 | 0.41 | 0.71 | 0.44 | 0.74 |
| 25 | 0.05 | 0.297 | 0.40 | 0.71 | 0.69 | 0.96 | 0.26 | 0.49 | 0.29 | 0.53 |
| 25 | 0.10 | 0.369 | 0.28 | 0.53 | 0.52 | 0.85 | 0.19 | 0.35 | 0.21 | 0.38 |
| 50 | 0.01 | 0.173 | 0.81 | 0.98 | 0.98 | 1.00 | 0.59 | 0.87 | 0.63 | 0.89 |
| 50 | 0.05 | 0.263 | 0.48 | 0.80 | 0.79 | 0.98 | 0.31 | 0.58 | 0.34 | 0.62 |
| 50 | 0.10 | 0.344 | 0.31 | 0.59 | 0.58 | 0.88 | 0.21 | 0.39 | 0.23 | 0.42 |

In a separate run of 500 fits per setting at 58 colleges, parametric percentile bootstrap intervals with 499 replicates covered 90.1% to 93.6%, parametric bootstrap-$t$ intervals 93.2% to 95.8% and profile-likelihood intervals 91.8% to 94.7%. Only the $t$ interval with the corrected standard error met the rule on the stored fits. In the separate 500-fit run it covered 92.8% to 95.8%, narrowly missing the rule there, as every other method did. Table 23 shows its size and coverage at each number of participating colleges. Table 24 compares the Wald and corrected intervals for each design in the grid study and the main application.

Table 23: Size and coverage of the Wald and corrected $t$ tests by the number of participating colleges, random volunteering, $\beta = 0$, all designs, regimes, values of $\rho$ and $\kappa$, and years. Size is the rejection rate of a true null hypothesis $\tau = 0$ (range over designs). Coverage is at $\tau = 1$, with the range over design-by-regime means in parentheses. All entries are percentages.

| Colleges | Wald size | Corrected $t$ size | Wald coverage | Corrected $t$ coverage |
|---|---|---|---|---|
| 15 | 11.1–12.8 | 4.4–5.4 | 87.7 | 94.9 (94.5–95.6) |
| 20 | 9.5–10.4 | 4.7–5.4 | 89.8 | 94.8 (94.4–95.3) |
| 25 | 8.4–9.5 | 4.7–5.5 | 90.9 | 94.8 (94.4–95.2) |
| 29 | 8.3–8.8 | 5.0–5.5 | 91.6 | 94.8 (94.4–95.1) |
| 30 | 7.9–8.6 | 5.0–5.5 | 91.7 | 94.7 (94.4–95.0) |
| 35 | 7.6–8.1 | 5.1–5.5 | 92.2 | 94.7 (94.2–95.1) |
| 40 | 7.4–7.7 | 5.2–5.5 | 92.5 | 94.7 (94.2–94.9) |
| 45 | 6.9–7.5 | 5.0–5.6 | 92.7 | 94.7 (94.3–95.2) |
| 50 | 7.0–7.3 | 5.2–5.6 | 92.9 | 94.6 (94.2–95.1) |
| 58 | 6.3–7.0 | 5.0–5.5 | 93.2 | 94.6 (94.0–95.1) |

**Guidance under partial participation.** Table 25 gives each strategy's mean MSE relative to

Table 24: Coverage of the 95% Wald interval and the corrected $t$ interval ($t$ reference distribution with a degrees-of-freedom-corrected standard error), the interval reported throughout, for the six designs and SRS. Grid: oracle model at $\tau = 1$, pooled over the five incidence configurations and both spillover regimes (160 scenarios per entry). Application: queen weights, $\beta = 0$, averaged over the four planning years and the six $\rho/\gamma$ pairs of each regime. Both intervals were computed from the same fits. [a]Under rook contiguity on the grid, $\tau$ is not identified for Checkerboard.

| | Grid, queen | | Grid, rook | | NC, both arms | | NC, control only | |
|---|---|---|---|---|---|---|---|---|
| Design | Wald | $t$ | Wald | $t$ | Wald | $t$ | Wald | $t$ |
| Incidence-Guided Saturation | 0.937 | 0.947 | 0.942 | 0.952 | 0.935 | 0.949 | 0.927 | 0.942 |
| Balanced Quartiles | 0.936 | 0.946 | 0.940 | 0.948 | 0.933 | 0.948 | 0.929 | 0.944 |
| Isolation Buffer | 0.939 | 0.949 | 0.939 | 0.950 | 0.932 | 0.947 | 0.931 | 0.947 |
| High Incidence Focus | 0.938 | 0.948 | 0.939 | 0.948 | 0.934 | 0.949 | 0.931 | 0.946 |
| 2×2 Blocking | 0.939 | 0.948 | 0.938 | 0.948 | 0.932 | 0.947 | 0.929 | 0.944 |
| Checkerboard[a] | 0.941 | 0.950 | 0.150 | 0.162 | 0.936 | 0.949 | 0.933 | 0.948 |
| Simple Random Sampling | 0.938 | 0.948 | 0.938 | 0.947 | 0.932 | 0.947 | 0.929 | 0.945 |

SRS at $\tau = 1$ for 20, 29, 40 and 58 participating colleges. When colleges with higher incidence were more likely to volunteer, the ratios at 20 and 29 colleges were within 0.02 of 1 for both saturation designs and Balanced Quartiles under either regime, and within 0.03 for Balanced Halves, and Checkerboard and Isolation Buffer remained the worst designs. Rebuilding the four saturation regions on the participants left at least two colleges in every region by construction. Before that requirement was imposed, a region with fewer than two colleges occurred in 1 of the 50 random subsets at 15 colleges and in one incidence-weighted subset at 20 colleges. Imposing it changed the regions of only two distinct participant subsets and changed no ratio in Table 25 by more than 0.01.

**Targeting.** With all 58 colleges, Incidence-Guided Saturation's mean share of the summed college incidence rates in treated colleges was 51.1%, against 50.4% for Saturation Quadrants, 50.0% for SRS and 62.2% for High Incidence Focus. Its mean share of deaths was 49.2%, against 49.6%, 49.7% and 35.4%. On the grid, the gain of Incidence-Guided Saturation over Saturation Quadrants in treated incidence share averaged 2.1 to 3.1 percentage points across the five incidence configurations, while High Incidence Focus reached 0.75 to 0.77 by giving up randomization over the whole map. Grid clusters have equal populations, so rate share and

Table 25: Mean MSE relative to simple random sampling (SRS) at $\tau = 1$ by the number of participating colleges, random volunteering, mean over 16 blocks (year $\times$ $\rho$ $\times$ $\kappa$). Below 1 is lower error than SRS.

| | Both arms | | | | Control only | | | |
|---|---|---|---|---|---|---|---|---|
| Design | 20 | 29 | 40 | 58 | 20 | 29 | 40 | 58 |
| Checkerboard | 1.88 | 2.18 | 2.23 | 2.82 | 1.18 | 1.38 | 1.80 | 3.10 |
| High Incidence Focus | 0.98 | 0.97 | 0.96 | 0.92 | 0.99 | 1.00 | 0.99 | 1.06 |
| Saturation Quadrants | 1.00 | 0.98 | 1.00 | 1.00 | 0.99 | 0.96 | 0.90 | 0.78 |
| Isolation Buffer | 5.92 | 4.21 | 3.74 | 3.87 | 3.61 | 2.25 | 1.51 | 0.99 |
| $2 \times 2$ Blocking | 1.03 | 1.01 | 1.02 | 1.03 | 1.08 | 1.11 | 1.11 | 1.18 |
| Balanced Quartiles | 1.00 | 0.99 | 0.99 | 1.01 | 1.00 | 0.99 | 0.99 | 1.02 |
| Balanced Halves | 0.99 | 0.98 | 0.98 | 1.00 | 0.99 | 0.97 | 1.01 | 1.01 |
| Incidence-Guided Saturation | 0.99 | 0.97 | 1.00 | 1.00 | 0.99 | 0.95 | 0.91 | 0.78 |
| Simple Random Sampling | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |

death share coincide there. Figure 23 shows that the gain rose almost linearly with the spread of the regions' mean incidence ranks, and that the NC regions lie at the low end of that spread.





Figure 23: Gain in treated incidence share from incidence guidance, Incidence-Guided Saturation minus Saturation Quadrants, against the spread of the regions' mean incidence ranks, (largest minus smallest regional mean rank) divided by the number of clusters. Filled symbols are the 50 grid surfaces (queen, production allocations) by incidence configuration, with a least-squares line fitted to the grid surfaces only. Open triangles are the four fixed NC regions in each planning year, whose spread divides by 58 clusters rather than 100.

**Formal tests on the NC results.** Friedman tests over the 24 combinations of year, $\rho$ and $\gamma$ rejected equal ranks of the nine strategies in all four combinations of regime and $\beta$ ($\chi^2 = 135.3$, 153.8, 150.7 and 179.8 on 8 degrees of freedom, $p \leq 2.3 \times 10^{-25}$; Nemenyi critical difference

2.45). Under control-only spillover, Saturation Quadrants and Incidence-Guided Saturation had the two best average ranks (1.67 and 1.79 with $\beta = 0$; 1.29 and 1.71 with $\beta = 1$), and SRS ranked seventh with $\beta = 0$ and sixth with $\beta = 1$. Under both-arms spillover with $\beta = 0$, High Incidence Focus ranked first (1.88) and SRS sixth (5.17), with the balancing and saturation designs between them. These tests treat the 24 blocks as independent, although the years share one map and some strategies share their simulations across years, so they describe the consistency of the ordering rather than independent evidence.

**Unequal numbers of trained professionals.** With $m$ proportional to college population and averaging 25, and ICC = 0.05, power fell by 0.097 on average across designs, settings and effect sizes. For $d = 0.3$ under both-arms spillover, the mean power over the nine strategies fell from 0.59 to 0.46 with 20 colleges and from 0.88 to 0.77 with 58. MSE rose by a factor of 1.24 to 1.84 across designs and settings, and no design gained relative to the others.

**Estimation models.** Every model in the sensitivity analysis has the mean $\mu = \alpha\mathbf{1} + \tau Z + \text{Spill}$ with the proportional spillover covariate of the main analysis, and uses the 58-college queen geography. The spatial lag model of the main analysis is $Y = \rho WY + \mu + \epsilon$, $\epsilon \sim N(0, \sigma^2 I)$. The CAR model is $Y = \mu + u$, $u \sim N\{0, \sigma^2(I - \lambda S)^{-1}\}$, where $S$ is the symmetric matrix similar to the row-standardized $W$ [10], fitted by maximum likelihood with the `spautolm` function of the R package `spatialreg` [11]. For the reverse comparison, data were generated as $Y = \mu + L\epsilon$ with $LL^\top = (I - \rho S)^{-1}$ and the same values of $\rho$ as the spatial lag data. These runs used four years, $\rho \in \{0, 0.2, 0.5\}$, $\gamma \in \{0.5, 0.8\}$, both regimes and the nine strategies, with 500 fits per setting.

The Bayesian CAR model [33] is $Y_j = \mu_j + \phi_j + e_j$, $e_j \sim N(0, \nu^2)$, with

$$\phi_j \mid \phi_{-j} \sim N\left(\frac{\lambda \sum_k a_{jk}\phi_k}{\lambda \sum_k a_{jk} + 1 - \lambda},\ \frac{\sigma_\phi^2}{\lambda \sum_k a_{jk} + 1 - \lambda}\right),$$

where $a_{jk}$ is the binary queen adjacency. We used the defaults of the `S.CARleroux` function

of the R package `CARBayes` [34], version 6.1.1: independent $N(0, 10^5)$ priors for the regression coefficients, inverse-gamma(1, 0.01) priors for $\nu^2$ and $\sigma^2_\phi$, and a uniform(0, 1) prior for $\lambda$. Each chain ran 25,000 iterations, of which the first 5,000 were discarded, thinned by 5. At $\rho = 0.5$, where fewer than half the chains converged, we reran the same data with 100,000 iterations, 20,000 discarded and thinning by 20. The Bayesian spatial lag model [9] has the same form as the maximum likelihood model, with the defaults of the `spBreg_lag` function of `spatialreg`, version 1.4.3: a $N(0, 10^{12}I)$ prior for the regression coefficients, the prior $p(\sigma^2) \propto 1/\sigma^2$, a Beta(1.01, 1.01) prior for $\rho$ rescaled to its feasible interval, and 10,000 draws of which the first 2,000 were discarded. Both Bayesian models used four years, $\rho \in \{0, 0.5\}$, $\gamma = 0.8$, both regimes and the nine strategies, with 100 fits per setting (14,400 fits per model), and both were fitted to the same data as the maximum likelihood model. We report the posterior mean of $\tau$ and the 95% equal-tailed credible interval. A chain was counted as converged when the effective sample size of $\tau$ was at least 400 and the absolute Geweke $z$ statistic [35] was below 1.96.

With the longer chains, 83.1% of the Bayesian CAR chains at $\rho = 0.5$ converged, against 46.2% for the shorter chains, but 12.5% still had an absolute Geweke $z$ of at least 1.96, against about 5% expected by chance. Among converged chains, the Bayesian CAR estimate was biased by +0.14 under both-arms spillover and +0.22 under control-only spillover, with credible-interval coverage of 90.4% and 87.7%, against biases of +0.02 and +0.03 and Wald coverage of 93.5% and 93.2% for maximum likelihood on the same data. Of the Bayesian spatial lag chains, 94.9% converged. The median effective sample size of $\tau$ was 8,000 (minimum 5,897) and 5.1% had an absolute Geweke $z$ of at least 1.96. Its posterior means correlated 0.999 with the maximum likelihood estimates (mean absolute difference 0.017), its bias was at most 0.04 in absolute value in every combination of $\rho$ and regime, and its credible intervals covered 94.6% to 95.3% over all chains (94.5% to 95.3% over converged chains). The Spearman correlation of its design ordering with that of maximum likelihood averaged 0.96 to 1.00 across the four combinations of $\rho$ and regime (0.83 in the lowest single block), and the best design agreed in every block. Tables 26

and 27 give each strategy's MSE relative to SRS under each model.

Table 26: Mean MSE relative to simple random sampling (SRS) under four combinations of data-generating model and fitted model: spatial lag (SAR) or conditional autoregressive (CAR). 58 colleges, $\beta = 0$, mean over 24 blocks (year $\times$ $\rho$ $\times$ $\gamma$). Below 1 is lower error than SRS.

| | Both arms | | | | Control only | | | |
|---|---|---|---|---|---|---|---|---|
| Data | SAR | SAR | CAR | CAR | SAR | SAR | CAR | CAR |
| Fit | SAR | CAR | SAR | CAR | SAR | CAR | SAR | CAR |
| Checkerboard | 2.88 | 2.83 | 2.93 | 3.09 | 2.99 | 2.64 | 3.01 | 3.00 |
| High Incidence Focus | 1.06 | 1.02 | 1.07 | 1.07 | 1.08 | 1.03 | 1.10 | 1.09 |
| Saturation Quadrants | 1.04 | 1.02 | 1.04 | 1.03 | 0.79 | 0.81 | 0.81 | 0.78 |
| Isolation Buffer | 4.11 | 4.13 | 4.16 | 4.45 | 1.03 | 0.95 | 1.03 | 1.05 |
| $2 \times 2$ Blocking | 0.98 | 0.99 | 1.00 | 1.02 | 1.21 | 1.17 | 1.22 | 1.22 |
| Balanced Quartiles | 1.04 | 1.05 | 1.04 | 1.06 | 1.03 | 1.00 | 1.03 | 1.02 |
| Balanced Halves | 1.04 | 1.03 | 1.05 | 1.04 | 1.02 | 0.98 | 1.03 | 0.99 |
| Incidence-Guided Saturation | 1.03 | 1.04 | 1.04 | 1.03 | 0.81 | 0.82 | 0.81 | 0.76 |
| Simple Random Sampling | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |

Table 27: Mean MSE relative to simple random sampling (SRS) at $\rho = 0.5$ for maximum likelihood (ML), the Bayesian spatial lag model (Bayes SAR) and the Bayesian CAR model with converged chains only (Bayes CAR), all fitted to the same spatial lag data. 58 colleges, $\beta = 0$, $\gamma = 0.8$, mean over the four planning years.

| | Both arms | | | Control only | | |
|---|---|---|---|---|---|---|
| Design | ML | Bayes SAR | Bayes CAR | ML | Bayes SAR | Bayes CAR |
| Checkerboard | 3.14 | 3.18 | 2.90 | 3.16 | 3.16 | 2.31 |
| High Incidence Focus | 0.96 | 0.96 | 0.83 | 1.19 | 1.19 | 1.04 |
| Saturation Quadrants | 1.12 | 1.10 | 1.11 | 0.86 | 0.86 | 1.05 |
| Isolation Buffer | 3.89 | 3.94 | 3.80 | 1.01 | 1.02 | 0.87 |
| $2 \times 2$ Blocking | 1.14 | 1.14 | 1.11 | 1.48 | 1.48 | 1.34 |
| Balanced Quartiles | 1.00 | 1.00 | 1.05 | 1.10 | 1.10 | 1.15 |
| Balanced Halves | 0.97 | 0.97 | 0.99 | 1.05 | 1.06 | 1.01 |
| Incidence-Guided Saturation | 1.12 | 1.10 | 1.13 | 0.81 | 0.81 | 0.95 |
| Simple Random Sampling | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |

**Spillover form.** Under the binary form, $S(Z) = \gamma\,\mathbf{1}\{\text{any treated queen neighbor}\}$, times $1 - Z$ under control-only spillover. Under the count form, $S(Z) = (\gamma/\bar{d})\times$ (number of treated queen neighbors), where $\bar{d} = 4.93$ is the mean number of queen neighbors, so a college of average degree with every neighbor treated receives $\gamma$, as under the proportional form. Table 28 compares the three forms. Under the binary form, Isolation Buffer is never identified, because every control has a treated neighbor, and under control-only spillover no strategy was identified in every fit. The saturation designs were identified most often there (in 89.7% and 91.7% of fits) and, among identified fits, had MSE 0.70 to 0.71 times that of SRS.

Table 28: Mean MSE relative to simple random sampling (SRS) under three spillover forms, 58 colleges, $\beta = 0$, mean over 16 blocks (year $\times$ $\rho$ $\times$ $\gamma$). n.i.: not identified in every fit (the spillover covariate is aliased with the intercept and treatment in some or all allocations).

| | Both arms | | | Control only | | |
|---|---|---|---|---|---|---|
| Design | Proportional | Count | Binary | Proportional | Count | Binary |
| Checkerboard | 2.97 | 1.78 | 1.07 | 3.09 | 1.41 | n.i. |
| High Incidence Focus | 0.91 | 0.92 | 0.96 | 1.03 | 1.04 | n.i. |
| Saturation Quadrants | 1.01 | 1.02 | 1.03 | 0.76 | 0.81 | n.i. |
| Isolation Buffer | 3.82 | 3.84 | n.i. | 0.95 | 1.16 | n.i. |
| $2 \times 2$ Blocking | 1.04 | 1.03 | 1.00 | 1.17 | 1.07 | n.i. |
| Balanced Quartiles | 1.01 | 1.01 | 1.00 | 0.99 | 0.99 | n.i. |
| Balanced Halves | 1.02 | 1.02 | 1.02 | 0.98 | 0.99 | n.i. |
| Incidence-Guided Saturation | 1.01 | 1.03 | 1.04 | 0.75 | 0.79 | n.i. |
| Simple Random Sampling | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | n.i. |