Sampling Design for Spatial Cluster Randomized Trials Under Heterogeneous Incidence

Andrew Walther[1], Ashkan Habib[2], Ross Joseph Simpson, Jr.[3], and Feng-Chang Lin[1]

[1]Department of Biostatistics, University of North Carolina at Chapel Hill, Chapel Hill, NC, USA
[2]Department of Epidemiology, University of North Carolina at Chapel Hill, Chapel Hill, NC, USA
[3]Division of Cardiology, University of North Carolina School of Medicine, Chapel Hill, NC, USA
*Corresponding author: Feng-Chang Lin, flin33@email.unc.edu

1 Introduction

Cluster randomized trials (CRTs) randomize intact groups, such as clinics, schools, or geographic areas, rather than individuals. They are the standard design when an intervention is delivered at the group level or when individual randomization would create unacceptable contamination between arms [1, 2]. Standard CRT analysis relies on the no-interference component of the stable unit treatment value assumption (SUTVA): a cluster's outcome must not depend on which other clusters were assigned to treatment [3]. This assumption comes from the theory of individually randomized trials. It can fail once clusters are spatially arranged, as can the weaker assumption of partial interference, under which outcomes may depend on assignments within prespecified groups but not across them [4]. Tobler's first law of geography states that "everything is related to everything else, but near things are more related than distant things" [5]. By this principle, an intervention delivered in one location can plausibly influence outcomes in adjacent locations through shared populations, service networks, information diffusion, or environmental pathways. Documented examples of spatial spillover come from public health and development economics. In a trial of insecticide-treated bed nets in northern Ghana, child

mortality was lower in control villages close to treated villages than in control villages farther away [6]. A school-based deworming trial in Kenya found health and attendance benefits among untreated children near treated schools [7]. When control clusters benefit from nearby treatment, an unadjusted comparison of treated and control clusters may understate the direct effect. How much contamination occurs can depend on the spatial arrangement of the two arms, not only on the number of clusters allocated to each.

1.1 The Design-Stage Gap in the Spatial Interference Literature

Methods for spatial interference in CRTs have concentrated on correction at the analysis stage (Chapter 1). Spatial autocorrelation statistics such as Moran's I [8] detect residual spatial dependence once outcomes have been observed. Spatial regression models, such as the spatial lag model [9] estimated by maximum likelihood [10] and implemented in software [11], allow an analyst to separate a direct treatment effect from a spillover effect after the fact. In their systematic review of spatial analysis methods for cluster randomized trials, Jarvis and colleagues placed trials that used spatial separation or buffers outside the primary review of statistical methods [12]. The literature therefore offers much more guidance on analyzing spatial effects than on how the choice of treatment assignment itself, made before any data are collected, might reduce the problem.

Design-stage tools do exist, but they were largely developed for a different purpose. Restricted and covariate-constrained randomization address the baseline imbalance that a limited number of clusters can produce [13, 14]. Crisp and colleagues noted that their extension, which selects clusters from a larger eligible set, also increases spatial dispersion among the selected clusters [15]. Their dispersion criterion concerns which clusters are selected, not how they are assigned to arms. Balancing a covariate across arms also does not by itself determine whether treated and control clusters are spatially interspersed in a way that induces contamination. Other work addresses the problem studied here more directly. Randomized saturation designs assign different fractions

of units treated to different groups so that direct and spillover effects can be jointly identified [16]. Another approach selects whole clusters for inclusion or exclusion in place of a "fried-egg" design that omits each cluster's outer area from analysis [17]. Recent theoretical work develops designs under spatial, network and cross-cluster interference and spatio-temporal heterogeneity [18, 19, 20, 21]. This chapter complements that work with a simulation comparison of concrete assignment strategies that a trial team could implement, under heterogeneous baseline incidence and a range of spatial dependence and spillover conditions.

1.2 Extending Chapter 2

Chapter 2 examined block-stratified allocation as a practical way to obtain reasonably good estimation while limiting poor-allocation risk in the settings it studied. This chapter evaluates both criteria across a broader set of designs under heterogeneous incidence. We retain Chapter 2's simple random assignment benchmark and strict alternating allocation, called Checkerboard here, while adding incidence balancing, targeting, saturation and isolation strategies. The grid comparison increases the number of clusters from 8–12 to 100, considers queen as well as rook neighbors, and includes heterogeneous baseline incidence in the outcome model. These changes extend the design question, so the results are not a direct numerical replication of Chapter 2. In Chapter 2, β denotes the intervention effect. Here that effect is τ, and β denotes the coefficient of the incidence covariate. The observed-incidence application later in the chapter uses the North Carolina (NC) community college geography and a continuous education outcome, without assuming that historical sudden unexpected death (SUD) incidence predicts baseline education performance.

1.3 Aims and Outline

This chapter has three aims: (1) compare assignment designs by mean squared error (MSE), bias and confidence interval coverage, (2) assess how conclusions depend on incidence heterogeneity,

spatial dependence, spillover regime and treatment-effect magnitude, and (3) assess both average accuracy and allocation-specific downside for planning a SUD-prevention education pilot on an observed North Carolina geography. The detailed grid results present six designs, and the appendix documents the two related variants. A main-text benchmark includes all eight strategies and simple random sampling (SRS). The completed application evaluates all nine strategies separately for each observed planning year. The application simulates outcomes and assignments and does not report outcomes from an implemented intervention.

The Methods set out the outcome model, the baseline incidence mechanisms used on the grid, the treatment assignment designs, and the estimator and performance criteria, and then describe the grid simulation. The Results compare the designs on the 100-cluster grid, overall and by incidence configuration, spatial dependence and spillover regime, and then compare each design with SRS. Later subsections report how the comparison changes with the treatment effect, across parameter settings and across allocations, and the last two give sensitivity analyses for rook contiguity and for a model without the spillover term. The application then evaluates the same designs on the observed NC geography, including participation and power. The Discussion draws out implications for trial design and for the SUD education pilot.

2 Methods

2.1 Spatial Structure, Outcome Model and Estimand

The grid study uses a 10×10 regular grid of 100 clusters, and the application uses 58 community college service areas in North Carolina. In both, clusters are linked under one of two definitions of adjacency. Under queen contiguity, two clusters are neighbors if they share an edge or a corner. Under rook contiguity, they must share an edge. Queen contiguity is the primary analysis in this chapter. Rook contiguity is a sensitivity analysis and the case that continues Chapter 2, whose grids used rook neighbors. For each definition, the binary adjacency matrix

was row-standardized to form the spatial weights matrix $\mathbf{W}$. The product $\mathbf{WZ}$ then gives, for each cluster, the proportion of its neighbors that are treated, and $\mathbf{WY}$ gives the average outcome among its neighbors. Row-standardization expresses each cluster's spillover exposure as an average over its own neighborhood rather than a raw sum, which would otherwise depend on how many neighbors the cluster has. Within a scenario, the same neighbor type defines $\mathbf{W}$ in the outcome model, in the Isolation Buffer design, and in the fitted model.

Cluster-level outcomes $\mathbf{Y}$ were generated from a spatial lag model with a spillover term,

$$\mathbf{Y} = (\mathbf{I} - \rho\mathbf{W})^{-1} \left[\tau\mathbf{Z} + \mathbf{S}(\mathbf{Z}) + \beta\mathbf{X} + \varepsilon\right], \qquad \varepsilon \sim N(\mathbf{0}, \sigma^2\mathbf{I}), \tag{1}$$

where $\mathbf{Z} \in \{0,1\}^N$ is the treatment assignment of the N clusters produced by the design under evaluation, τ is the direct treatment effect of interest, $\mathbf{S}(\mathbf{Z})$ is the spillover term defined in Equation 2, ρ is the spatial autoregressive coefficient governing dependence in the outcome beyond that induced by treatment and spillover, $\mathbf{X}$ is the baseline incidence covariate with coefficient $\beta = 1$, and $\sigma = 1$. The spatial multiplier $(\mathbf{I} - \rho\mathbf{W})^{-1}$ propagates each cluster's shocks through the network of neighbors. The effect τ is the coefficient of a cluster's own treatment before spatial propagation, not an average total effect after applying $(\mathbf{I} - \rho\mathbf{W})^{-1}$. When $\rho = 0$ the multiplier is the identity and the model is a linear regression with independent errors, $\mathbf{Y} = \tau\mathbf{Z} + \mathbf{S}(\mathbf{Z}) + \beta\mathbf{X} + \varepsilon$, in which spatial structure enters only through the spillover term. Larger values of ρ induce progressively stronger spatial clustering in the outcome. Setting $\beta = 1$ makes incidence prognostic, so higher-incidence clusters have higher baseline outcomes. This is the harder case for designs that use incidence, because treatment can then line up with baseline risk. Investigators can choose β to suit their own outcome. The application's education outcome is not expected to depend on SUD incidence, so its primary analysis uses $\beta = 0$.

We evaluated two spillover regimes,

$$\mathbf{S}(\mathbf{Z}) = \gamma\,\mathbf{WZ} \quad \text{(both arms)}, \qquad \mathbf{S}(\mathbf{Z}) = \gamma\,\mathbf{WZ} \circ (\mathbf{1} - \mathbf{Z}) \quad \text{(control only)}, \tag{2}$$

where $\circ$ denotes the elementwise product. Under the control-only regime, only untreated clusters respond to the treatment status of their neighbors. This is classical contamination: an untreated cluster's outcome rises with the share of its neighbors that are treated. Under the both-arms regime, every cluster responds to its neighbors' treatment regardless of its own assignment, so neighboring treatment adds to a treated cluster's own effect.

2.2 Heterogeneous Baseline Incidence

Chapter 2 assumed a spatially uniform baseline outcome risk. Cluster-level health outcomes typically vary across space, and the designs studied here differ in whether and how they use that variation. We generated the baseline incidence covariate $\mathbf{X}$, with values in $(0, 1)$, under three mechanisms. Under the independent (iid) mechanism, each X_i is drawn from a Uniform$(0, 1)$ distribution, with no spatial structure. The spatially autocorrelated mechanism sets $\mathbf{X} = \Phi\{(\mathbf{I} - \rho_X \mathbf{W}_Q)^{-1}\mathbf{u}\}$, where $\mathbf{u} \sim N(\mathbf{0}, \mathbf{I})$, Φ is the standard normal distribution function applied elementwise, $\mathbf{W}_Q$ is the queen weights matrix, and $\rho_X \in \{0.20, 0.50\}$. Under the Poisson mechanism, a spatially autocorrelated log-rate surface, $\log\lambda = \log(35/100{,}000) + (\mathbf{I} - \rho_X \mathbf{W}_Q)^{-1}\mathbf{u}$ with $\rho_X \in \{0.20, 0.50\}$, generates cluster death counts $C_i \sim \text{Poisson}(\lambda_i P)$, with an equal population of $P = 100{,}000$ in every cluster, so that a cluster at the base rate expects 35 deaths. The observed rates C_i/P are then rank-normalized to $X_i = (r_i - 0.5)/N$, where r_i is the rank of cluster i's rate among the $N = 100$ clusters and tied rates share their average rank. Ties remain at this population size: the Poisson surfaces used here have between 60 and 76 distinct values among the 100 clusters. The base rate of 35 per 100,000 was chosen to represent published SUD incidence. It lies between the SUD incidence rates that Mirzaei and colleagues estimated for US

men (49.3 per 100,000) and women (21.7 per 100,000) aged 20–64, close to their average [22]. It is not the observed rate of the county data described in Section 4, which come from a different source, age range, period, and case definition. The incidence filters always use the queen weights $\mathbf{W}_Q$, whichever neighbor type the scenario uses, so the incidence surfaces are identical under rook and queen contiguity. The iid mechanism and the two strengths of each of the other two mechanisms give five incidence configurations.

For each configuration we generated $K = 10$ incidence surfaces, $\mathbf{X}_1, \ldots, \mathbf{X}_{10}$, each from its own seed. The same ten surfaces are used by every scenario in that configuration, across neighbor types, outcome-model parameters, designs, and values of τ. The design draws and the outcome noise are shared more selectively, as described in Section 2.5. Each design is applied to the surface that generates the outcome: assignments for surface k are drawn from $\mathbf{X}_k$, and the outcome and the fitted model for those assignments use $\mathbf{X}_k$ as well. We call this the matched-surface assumption: the incidence observed when a trial is planned is the incidence that drives its outcome. The target of each scenario is performance averaged over incidence surfaces. For example, $\text{MSE} = E_{\mathbf{X}} E_{\mathbf{Z}|\mathbf{X}} E_{\varepsilon}[(\hat{\tau} - \tau)^2]$, with $\mathbf{X}$ drawn from the configuration's generator, $\mathbf{Z}$ from the design given $\mathbf{X}$, and $\varepsilon \sim N(\mathbf{0}, \mathbf{I})$. Bias, coverage, and power are defined in the same way.

2.3 Treatment Assignment Designs

We implemented eight treatment assignment designs and present six of them as the primary comparison set in this chapter. The other two, Saturation Quadrants and Balanced Halves, each share the mechanism of a retained design. In a comparison of the eight designs and SRS at $\tau = 1$, neither could be distinguished from its counterpart under either neighbor type (Appendix A1). Saturation Quadrants assigns the saturations 20%, 40%, 60%, and 80% to the four 5×5 quadrants of the grid in random order, without reference to incidence. Its retained counterpart, Incidence-Guided Saturation, assigns the higher saturations to the quadrants with higher mean incidence (Table 1). On the NC map, both designs use four fixed geographic regions in place of

the quadrants. Balanced Halves divides clusters into two halves by incidence rank and treats 25 at random in each. Its retained counterpart, Balanced Quartiles, uses four strata. In each pair the excluded design had the marginally lower mean squared error or average rank under at least one neighbor type, so the choice of representative does not rest on performance. The two saturation designs performed similarly, so incidence guidance matches the accuracy of Saturation Quadrants while directing the highest treatment saturations to the quadrants or regions with the highest incidence. The accuracy advantage of both designs over SRS, which arises under control-only spillover (see Section 3.4), comes from the saturation structure they share. Both variants are included in the full benchmark with SRS and in the application.

Table 1 describes the six retained designs, and Figure 1 shows one assignment from each, and from SRS, on a single illustrative incidence surface. Checkerboard is the strict block-stratified allocation of Chapter 2, in which no two rook neighbors share an arm. Chapter 2's Block Stratified Sampling design also admitted relaxed allocations on its 3×3 grid, where the arms cannot be balanced. On its 2×4 and 3×4 grids, as on the 10×10 grid here, the strict allocations are the two checkerboard patterns. We use the two names interchangeably for this allocation and use Checkerboard in the rest of this chapter. Checkerboard is the only deterministic design: it gives the same assignment in every draw, although each of its fits still receives its own outcome noise. Every other design was drawn independently 25 times for each incidence surface. Designs that rank clusters by incidence break ties at random, afresh for each draw. High Incidence Focus is random only through that tie-breaking. Under the iid and spatial mechanisms, incidence values are distinct, so it gives the same assignment in all 25 draws on a surface, and that assignment changes only from one surface to the next. Isolation Buffer builds its assignment from the neighbor type of the scenario, and it treats 38 clusters on average under rook contiguity and 21 under queen contiguity. Every other design treats exactly 50.

Table 1: The six treatment assignment designs compared in this chapter, ordered by mean squared error under queen contiguity at $\tau = 1$, pooled over the five incidence configurations (Table 2). A cluster's incidence rank is its rank by the baseline incidence surface $\mathbf{X}_k$, with ties broken at random in every draw. Clusters treated is the number of clusters treated per assignment. For Isolation Buffer, which depends on the neighbor type, it is the mean over its assignments under each neighbor type.

Design	Assignment rule	Clusters treated	Deterministic
Incidence-Guided Saturation	The grid is divided into its four 5×5 coordinate quadrants. Quadrants are ranked by mean incidence and given saturations of 80%, 60%, 40%, and 20% from highest to lowest mean; within each quadrant, that share of its 25 clusters is treated at random	50	No
Balanced Quartiles	Clusters are divided by incidence rank into four strata of 25. Twelve clusters are treated at random in each stratum, and one more in each of two randomly chosen strata	50	No
Isolation Buffer	Clusters are treated one at a time, each chosen at random from those that are neither treated nor adjacent to a treated cluster, until none remain (a greedy random maximal independent set); no two treated clusters are neighbors	38 rook, 21 queen (mean)	No
High Incidence Focus	The 50 clusters with the highest incidence rank are treated	50	No
2×2 Blocking	The grid is divided into 25 non-overlapping 2×2 blocks; two of the four clusters in each block are treated at random	50	No
Checkerboard (strict Block Stratified Sampling allocation in Chapter 2)	Clusters whose grid coordinates (x, y) have an odd sum $x + y$ are treated, so treatment alternates from cluster to cluster; under rook contiguity every neighbor of a treated cluster is a control, and every neighbor of a control is treated	50	Yes

2.4 Estimation and Performance Criteria

We estimated τ with two maximum likelihood spatial lag models, both fit to every simulated outcome and both including an intercept. The primary, oracle model has the spatial lag $\rho\mathbf{WY}$ and the covariates $\mathbf{Z}$, Spill $= \mathbf{S}(\mathbf{Z})$, and $\mathbf{X}_k$, so it matches the outcome model in Equation 1, including the true regime-specific spillover covariate from Equation 2. The oracle model assumes that the analyst knows the form of the spillover mechanism and has the exact exposure term, so its results are a best case for each design. We return to this assumption as a limitation. The non-oracle model, a sensitivity analysis, has the covariates $\mathbf{Z}$ and $\mathbf{X}_k$ only and omits the spillover




Figure 1: One example assignment from each of the six designs and SRS on the 10×10 grid, in the order of Table 1, all on the illustrative incidence surface in the first panel (darker is higher). That surface is spatially autocorrelated with $\rho_X = 0.5$ and was generated with a fixed seed. It is not one of the simulation's incidence surfaces. Blue clusters are treated and white clusters are controls. Lines mark the 2×2 blocks and the quadrants, numbers in the Balanced Quartiles panel give incidence quartiles, and percentages in the Incidence-Guided Saturation panel give treated shares. Isolation Buffer is shown under queen contiguity.

term. Both models are fit to the same outcomes.

We fit both models with our own implementation of the maximum likelihood estimator of the spatial lag model [23], the same estimator that the `lagsarlm` function of the R package `spatialreg` computes with `method = "eigen"`. It maximizes the concentrated log-likelihood over ρ, computing the log-determinant from the eigenvalues of $\mathbf{W}$ [10], estimates the remaining coefficients by least squares given $\hat{\rho}$, and computes standard errors from the analytic information matrix. On 5,120 validation fits it agreed with `lagsarlm` to within 9.7×10^{-8} in $\hat{\tau}$ and to a relative difference of 1.1×10^{-8} in its standard error, at roughly 1% of the computing time. As a further check, we refit a 1% sample of the full simulation with `lagsarlm` itself. Confidence intervals are 95% intervals with a t reference distribution and a degrees-of-freedom-corrected standard error, $\hat{\tau} \pm t_{0.975,\, N-p}\, \widehat{\mathrm{SE}} \sqrt{N/(N-p)}$. Here $\widehat{\mathrm{SE}}$ is the estimated standard error, $N = 100$

is the number of clusters and p is the number of regression coefficients plus ρ: 5 for the oracle model, and 4 for the non-oracle model and for rook Checkerboard, whose aliased spillover column is dropped. The application uses the same interval. The 95% Wald interval, $\hat{\tau} \pm 1.96\,\widehat{\mathrm{SE}}$, covered about one percentage point less for every design.

For Checkerboard, strict interspersion makes treatment and spillover hard or impossible to separate. Under rook contiguity on the rectangular grid, $\mathbf{WZ} = \mathbf{1} - \mathbf{Z}$, so treatment and spillover cannot be separately identified, and the fitted coefficient on treatment estimates $\tau - \gamma$. Under queen contiguity, treatment is identified but control-only spillover is weakly separated from treatment. We retain Checkerboard in the main design comparison and flag aliased estimates. Exact matrix identities, boundary information and the rare Isolation Buffer aliases are detailed in Appendix A7. These diagnostics apply only to the two models fitted here.

Because a trial realizes only one allocation, we judge each design on two criteria: the error of the estimate averaged over the allocations the design can produce, and how that error varies from one allocation to another. The risk of assignment a is the conditional MSE $m(a) = E_{\varepsilon}[(\hat{\tau} - \tau)^2 \mid a, \mathbf{X}]$. We estimated it by simulating repeated outcomes for each sampled assignment and then compared its distribution across assignments. This distribution across assignments differs from the distribution of squared errors in a single allocation and from MSE across parameter scenarios.

A design's MSE is the average of $m(a)$ over its assignments and, in the grid study, over incidence surfaces. Bias, coverage of the 95% interval and power are averaged over assignments and outcome noise in the same way. We summarize the variation across assignments by the estimated 90th percentile of $m(a)$ among sampled assignments and by the worst-decile mean, the mean of $m(a)$ over the worst 10% of sampled assignments.

2.5 Simulation Design, Resampling, and Metrics

We tested four values of the outcome spatial dependence, $\rho \in \{0, 0.01, 0.20, 0.50\}$, four spillover magnitudes, $\gamma \in \{0.5, 0.6, 0.7, 0.8\}$, and five magnitudes of the direct effect, $\tau \in \{0.8, 1.0, 1.5, 2.0, 3.0\}$, with $\tau = 1$ as the primary scenario throughout. The full simulation crossed five values of τ, five incidence configurations, two neighbor types, four values of ρ, four values of γ, two spillover regimes, and eight designs, for $5 \times 5 \times 2 \times 4 \times 4 \times 2 \times 8 = 12{,}800$ scenarios, of which the six designs reported in this chapter account for 9,600. We call a combination of incidence configuration, neighbor type, ρ, γ, and spillover regime a block. This gives $5 \times 2 \times 4 \times 4 \times 2 = 320$ blocks, 160 for each neighbor type. At the primary scenario, $\tau = 1$, the six designs give 1,920 scenarios, and every block contains all six.

Within each scenario, we drew $J = 25$ assignments from each of the $K = 10$ incidence surfaces, for 250 fits per scenario. Every fit had its own noise vector, so that fit (k, j) has outcome $\mathbf{Y}_{kj} = (\mathbf{I} - \rho\mathbf{W})^{-1}[\tau\mathbf{Z}_{kj} + \mathbf{S}(\mathbf{Z}_{kj}) + \beta\mathbf{X}_k + \varepsilon_{kj}]$. Checkerboard's 250 fits share one assignment but have 250 distinct noise vectors. The ten surfaces are independent, so the surface is the primary sampling unit. Each estimator was fit 3.2 million times. SRS assigns exactly 50 of the 100 clusters to treatment by complete randomization, ignoring incidence and geography. We ran it afterward with the same matched surfaces, noise keys and 250-fit structure, which brought the complete benchmark to 14,400 scenarios and 3.6 million fits per estimator. Adding SRS left the original eight-design results unchanged.

Every random draw was seeded from a key that names the draw, so the results do not depend on the order in which scenarios are run. The keys also give common random numbers. Within a block, all designs share the same noise vectors and incidence surfaces, the five values of τ reuse the same assignments and noise, and the oracle and non-oracle models are fit to the same outcomes. Blocks within an incidence configuration share its ten surfaces.

For each scenario and estimator, we computed bias, the standard deviation (SD) of $\hat{\tau}$, MSE,

coverage of the 95% interval, and power, the fraction of fits whose interval lies above zero (a one-sided test of $\tau = 0$ at level 0.025). For both estimators, every one of the 250 fits in every scenario was valid, with a finite estimate and standard error, and the fitting routine raised no warning other than the aliasing flags described above. Each metric is estimated from a finite number of simulated datasets, so it carries Monte Carlo error. Its Monte Carlo standard error measures this uncertainty and shrinks as more datasets are simulated [24]. Monte Carlo standard errors come from the surface-level metrics: with m_k a metric computed on the 25 fits from surface k, $\mathrm{SE}(m) = \mathrm{sd}(m_1, \ldots, m_{10})/\sqrt{10}$, and, for metrics pooled over the five incidence configurations, from the 50 independent configuration-by-surface means. Appendix A2 gives the parameter grid, the seed keys, and the exact formulas for the metrics, their standard errors, and paired differences between designs.

We compared designs within each neighbor type with a Friedman rank-sum test on scenario MSE [25], treating the 160 blocks as repeated measures across the six designs and SRS. SRS is the usual default for a cluster randomized trial, so it enters every test as a seventh member and each design is compared with it as well as with the other designs. At $\tau = 1$ we followed the Friedman test with Nemenyi post-hoc comparisons [26, 27] and paired Wilcoxon signed-rank tests [28] with Holm's adjustment for multiple comparisons [29] for all 21 pairs. We repeated the Friedman test at each other value of τ. Blocks within an incidence configuration share their surfaces, so these tests treat dependent blocks as independent, which overstates the information about variation from surface to surface. We therefore also ran paired Wilcoxon signed-rank tests, with t_{49} intervals for the mean difference, over 50 independent units, the 5 configurations times 10 surfaces. Each unit's MSE was averaged over that surface's blocks. These tests compared each pair of designs adjacent in the mean-MSE order, and each design with SRS within each spillover regime, with Holm's adjustment over the eight designs compared with SRS.

We also ran an allocation-risk study with queen weights, $\tau = 1$, all ten surfaces from each

incidence configuration and the extreme combinations of ρ and γ, $\rho \in \{0, 0.5\}$ and $\gamma \in \{0.5, 0.8\}$. The study used 100 assignment draws for each randomized design and 100 simulated outcomes per distinct assignment. As a precision check, one setting (surface 1, $\rho = 0.5$, $\gamma = 0.8$) was refined to 400 outcomes on the same assignments. A design with only one possible assignment received its own outcome replication.

We report results separately for each neighbor type, with queen contiguity primary, and never average a number over the two. Unless stated otherwise, every number in the Results is pooled over the five incidence configurations, and every table and figure caption states whether it pools the configurations or shows them separately. We report the ranking within each configuration separately and show the split wherever a conclusion changes.

3 Results

3.1 Design Performance Under Queen Contiguity

At the primary scenario, $\tau = 1$, under queen contiguity and pooled over the five incidence configurations, Incidence-Guided Saturation had the lowest mean squared error (MSE = 0.091), followed by Balanced Quartiles (0.131), Isolation Buffer (0.160), High Incidence Focus (0.245), 2×2 Blocking (0.319), and Checkerboard (1.087) (Table 2, Figure 2). Coverage of the 95% intervals was between 0.946 and 0.950 for all six designs (Figure 14 in Appendix A5). Power to reject $\tau = 0$ was 0.921 for Incidence-Guided Saturation, 0.814 for Balanced Quartiles, 0.706 for Isolation Buffer, 0.629 for 2×2 Blocking, 0.582 for High Incidence Focus, and 0.538 for Checkerboard.

Incidence-Guided Saturation also led block by block. Of the 160 queen blocks at $\tau = 1$, Incidence-Guided Saturation had the lowest MSE of the six designs in 95 (59%), Balanced Quartiles in 58 (36%), and Isolation Buffer in 7 (4%). No other design had the lowest MSE in any block.

The Friedman test rejected equal MSE ranks across the six designs and SRS under queen

Table 2: Performance of the six designs at the primary scenario, $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity), pooled over the five incidence configurations. Each entry averages the 160 scenarios of one design and neighbor type (5 incidence configurations $\times$ 4 values of ρ $\times$ 4 values of γ $\times$ 2 spillover regimes), each summarizing 250 fits of the oracle model. Rows in both panels are in order of mean squared error (MSE) under queen contiguity. Monte Carlo standard errors of MSE, multiplied by 100 in the third column, are computed from the 50 configuration-by-surface means (Section 2). Those of bias, coverage, and power are all below 0.007. Average rank is the mean of each design's within-block MSE rank among the six designs and SRS over the 160 blocks (1 = lowest MSE). SRS's average rank is 2.600 under queen contiguity and 2.450 under rook contiguity. Clusters treated is the mean number of clusters treated per assignment. Under rook contiguity, τ is not identified for Checkerboard ($\mathbf{WZ} = \mathbf{1} - \mathbf{Z}$). Its estimates are kept and flagged, and its coefficient on $\mathbf{Z}$ estimates $\tau - \gamma$.

Design	MSE	SE of MSE ($\times$100)	Bias	Coverage	Power	Average rank	Clusters treated
Queen contiguity (primary)							
Incidence-Guided Saturation	0.091	0.082	0.032	0.947	0.921	1.775	50
Balanced Quartiles	0.131	0.115	0.017	0.946	0.814	2.688	50
Isolation Buffer	0.160	0.112	0.003	0.949	0.706	4.194	21.4
High Incidence Focus	0.245	0.466	0.031	0.948	0.582	5.763	50
2×2 Blocking	0.319	0.319	0.010	0.948	0.629	5.244	50
Checkerboard	1.087	1.011	0.001	0.950	0.538	5.737	50
Rook contiguity (sensitivity)							
Incidence-Guided Saturation	0.072	0.056	0.018	0.952	0.956	1.831	50
Balanced Quartiles	0.084	0.064	0.008	0.948	0.907	2.225	50
Isolation Buffer	0.133	0.091	0.003	0.950	0.784	4.206	38.2
High Incidence Focus	0.206	0.301	0.018	0.948	0.617	5.969	50
2×2 Blocking	0.128	0.124	0.004	0.948	0.803	4.331	50
Checkerboard (flagged)	0.480	0.145	−0.652	0.162	0.390	6.987	50

contiguity at $\tau = 1$ ($\chi^2 = 560.33$, df = 6, 160 blocks, $p < 2.2 \times 10^{-16}$). Nemenyi comparisons (critical difference 0.712) separated 17 of the 21 pairs. Incidence-Guided Saturation ranked significantly better than every other design and than SRS ($p = 0.011$). SRS and Balanced Quartiles, whose average ranks were 2.60 and 2.69, could not be distinguished from each other ($p = 1.00$), and both ranked significantly better than the remaining four designs. The other three pairs not separated all lay among the bottom three designs. Holm-adjusted Wilcoxon signed-rank tests separated 20 of the 21 pairs, all except Balanced Quartiles against SRS ($p = 0.15$). We also compared each pair of designs adjacent in the mean-MSE order over the 50 independent configuration-by-surface units. Every adjacent pair differed significantly (Wilcoxon $p \leq 4.9 \times 10^{-9}$), and the better design had the lower MSE in all 50 units for every pair except




Figure 2: Mean squared error (MSE) of the oracle estimate of τ by design at $\tau = 1$, under queen contiguity, with designs in the order of Table 2. Columns of panels are the four levels of outcome spatial dependence ρ, rows the both-arms (top) and control-only (bottom) spillover regimes, and bar colors the values of the spillover magnitude γ. Each bar's height is the largest of the five incidence-configuration MSEs for that combination of design, ρ, γ, and regime, and the horizontal lines within it mark the other four. The gray dashed line in each panel marks simple random sampling (SRS), the largest of its five configuration MSEs averaged over the four values of γ. The vertical scale is set separately for each row. Figure 16 in Appendix A5 shows rook contiguity.

High Incidence Focus against 2×2 Blocking (48 of 50). Appendix A3 gives the pairwise results and the critical-difference diagrams.

The bottom three designs were ordered differently by average rank and by mean MSE: by mean MSE, High Incidence Focus (0.245), 2×2 Blocking (0.319), and Checkerboard (1.087). By

average rank, the order was 2×2 Blocking (5.24), Checkerboard (5.74), and High Incidence Focus (5.76). Both reversals arise because the MSEs of 2×2 Blocking and Checkerboard depended strongly on the spillover regime. Each had a lower MSE than High Incidence Focus in all 80 both-arms blocks (mean MSE 0.062 for each, against 0.162) and a higher MSE in all 80 control-only blocks (0.576 and 2.111, against 0.329). Average rank counts each block once, so their wins under the both-arms regime offset their losses under the control-only regime. Mean MSE weights those losses by their size. The surface-level comparison, which averages each unit over both regimes, also separated High Incidence Focus from 2×2 Blocking.

3.2 Incidence Configuration, Spatial Dependence and Spillover Magnitude

Table 3 gives each design's MSE within each of the five incidence configurations. Under queen contiguity, the mean-MSE order within every configuration was the same as the pooled order: Incidence-Guided Saturation, Balanced Quartiles, Isolation Buffer, High Incidence Focus, 2×2 Blocking, and Checkerboard. The configuration changed each design's MSE only slightly. In this order, each design's highest MSE across the five configurations was lower than the next design's lowest. Incidence-Guided Saturation had the lowest MSE in 18 to 21 of the 32 blocks in each configuration. Coverage did not depend on the configuration either: within each configuration, every design's coverage, averaged over its 32 scenarios, was between 0.941 and 0.952. High Incidence Focus, the design that uses the incidence ranks most directly, also had no higher MSE under the two Poisson configurations than under the iid and spatial configurations.

Under queen contiguity, neither the strength of spatial dependence in the outcome nor the spillover magnitude changed the ranking. Across $\rho \in \{0, 0.01, 0.20, 0.50\}$, no design's MSE changed by more than 0.02. Across $\gamma \in \{0.5, 0.6, 0.7, 0.8\}$, the MSE of every design except Checkerboard also varied by less than 0.02, and Checkerboard's varied between 1.052 and 1.108 with no trend in γ (Tables 14 and 16 in Appendix A4). Under rook contiguity, γ mattered for Checkerboard alone, for the reason given in the rook results below.

Table 3: Mean squared error by design within each of the five incidence configurations at $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity). Each entry averages the 32 scenarios of one design, neighbor type, and configuration (4 values of $\rho \times 4$ values of $\gamma \times 2$ spillover regimes), each summarizing 250 fits of the oracle model. The spatially autocorrelated and Poisson configurations are labeled by the strength of dependence in the incidence surface, ρ_X. Rows in both panels are ordered by pooled mean MSE under queen contiguity (Table 2). Under rook contiguity, τ is not identified for Checkerboard. Its estimates are kept and flagged.

		Spatial		Poisson	
Design	iid	$\rho_X = 0.20$	$\rho_X = 0.50$	$\rho_X = 0.20$	$\rho_X = 0.50$
Queen contiguity					
Incidence-Guided Saturation	0.093	0.087	0.092	0.090	0.092
Balanced Quartiles	0.130	0.130	0.131	0.128	0.135
Isolation Buffer	0.160	0.159	0.159	0.162	0.161
High Incidence Focus	0.245	0.267	0.245	0.232	0.238
2×2 Blocking	0.311	0.315	0.323	0.326	0.320
Checkerboard	1.091	1.068	1.086	1.112	1.077
Rook contiguity					
Incidence-Guided Saturation	0.072	0.072	0.073	0.073	0.069
Balanced Quartiles	0.081	0.084	0.084	0.084	0.085
Isolation Buffer	0.131	0.131	0.132	0.136	0.134
High Incidence Focus	0.205	0.213	0.200	0.202	0.211
2×2 Blocking	0.129	0.125	0.129	0.130	0.129
Checkerboard (flagged)	0.480	0.482	0.474	0.481	0.482

3.3 Spillover Regime

The spillover regime was the one factor that changed the queen ranking (Table 4, Figure 2). Under the both-arms regime, Balanced Quartiles had the lowest MSE (0.042), followed by Incidence-Guided Saturation (0.046), 2×2 Blocking (0.062), Checkerboard (0.062), Isolation Buffer (0.161), and High Incidence Focus (0.162). Under the control-only regime, the order was Incidence-Guided Saturation (0.135), Isolation Buffer (0.159), Balanced Quartiles (0.219), High Incidence Focus (0.329), 2×2 Blocking (0.576), and Checkerboard (2.111). At larger values of τ, Isolation Buffer matched or passed Incidence-Guided Saturation under this regime (see Section 3.5). For Isolation Buffer, no treated cluster has a treated neighbor, so $\mathbf{WZ} = 0$ at every treated cluster and $\mathbf{WZ} \circ (\mathbf{1} - \mathbf{Z}) = \mathbf{WZ}$. The two regimes in Equation 2 therefore define the same outcome model, and so the same expected MSE. The observed values, 0.161 and 0.159, differ only by Monte Carlo error because the two regimes use separate draws. Every other design had a higher MSE under the control-only regime. The increase was largest for Checkerboard

and 2×2 Blocking, which went from close to the best designs under the both-arms regime to the two worst under the control-only regime. Among the six detailed designs, Incidence-Guided Saturation was first or second under both regimes, at this and every other value of τ. In the full benchmark that includes SRS (Table 5), however, its both-arms MSE was 8% above that of SRS, a small but statistically detectable difference (Figure 3).

Table 4: Mean squared error by design under each spillover regime at $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity), pooled over the five incidence configurations. Each entry averages 80 scenarios (5 incidence configurations $\times$ 4 values of ρ $\times$ 4 values of γ). Rows are ordered by pooled mean MSE under queen contiguity (Table 2). Under rook contiguity, τ is not identified for Checkerboard. Its estimates are kept and flagged.

	Queen		Rook	
Design	Both arms	Control only	Both arms	Control only
Incidence-Guided Saturation	0.046	0.135	0.045	0.098
Balanced Quartiles	0.042	0.219	0.042	0.125
Isolation Buffer	0.161	0.159	0.131	0.134
High Incidence Focus	0.162	0.329	0.164	0.249
2×2 Blocking	0.062	0.576	0.051	0.206
Checkerboard (flagged under rook)	0.062	2.111	0.477	0.483

The increase under the control-only regime was variance, not bias. The oracle model includes the true regime-specific spillover covariate, so it has no omitted-variable bias. At $\tau = 1$, in every combination of design and regime under queen contiguity, the absolute bias was at most 0.048 and squared bias, averaged over scenarios, was at most 2.2% of MSE. Checkerboard showed the mechanism most clearly: under the control-only regime its spillover covariate is a linear combination of the intercept and $\mathbf{Z}$ at every interior cluster, so only the boundary clusters separate the spillover effect from the treatment effect (Section 2). Checkerboard's MSE rose from 0.062 under the both-arms regime to 2.111 under the control-only regime, while its bias stayed near zero (0.004) and its coverage stayed at 0.951, because its intervals widened with its variance. Its pooled MSE of 1.087 was almost entirely variance, and squared bias, averaged over scenarios, was 0.004, less than 0.5% of MSE. Figure 15 in Appendix A5 shows the decomposition for the Poisson configuration with $\rho_X = 0.20$. 2×2 Blocking showed the same pattern on a smaller scale, with MSE rising from 0.062 to 0.576 and a bias of 0.016 under the control-only

regime.

3.4 Comparison with Simple Random Sampling

At $\tau = 1$ under queen contiguity, pooled over the five incidence configurations and all spatial and spillover settings, Incidence-Guided Saturation had mean MSE 0.091 against 0.128 for SRS, and Saturation Quadrants had 0.090. Table 5 separates the regimes and includes all eight strategies. Figure 4 shows the six detailed designs and SRS with the five incidence configurations kept separate. Within each regime the configurations lie close together for every design, whereas the regime changes how each design compares with SRS. Incidence-Guided Saturation's MSE was 0.631 times that of SRS under control-only spillover and 1.083 times under both arms. SRS, Balanced Quartiles and Balanced Halves had similar both-arms accuracy. Small mean differences do not establish equivalence. Pooling over the regimes also hides how the design guidance differs between them.

Figure 3 tests each design against SRS within each regime, over the 50 independent configuration-by-surface units. Under control-only spillover, Incidence-Guided Saturation had 36.9% lower MSE than SRS (95% interval 34.5% to 39.2% lower), Saturation Quadrants 36.7% lower and Isolation Buffer 25.7% lower, each in all 50 units (Holm-adjusted $p = 6.2 \times 10^{-9}$). Under both-arms spillover, Incidence-Guided Saturation had 8.3% higher MSE than SRS (5.6% to 11.0% higher; $p = 6.1 \times 10^{-6}$) and Saturation Quadrants 4.3% higher ($p = 0.017$). Balanced Quartiles and Balanced Halves did not differ significantly from SRS under either regime. The remaining designs had significantly higher MSE than SRS under both-arms spillover, as did High Incidence Focus, 2×2 Blocking and Checkerboard under control-only spillover.

Under rook contiguity the saturation designs had 23% to 24% lower control-only MSE than SRS and 3% to 5% higher both-arms MSE, significant for Incidence-Guided Saturation ($p = 0.0075$) but not for Saturation Quadrants ($p = 0.15$). Isolation Buffer's control-only MSE under rook contiguity was 5.8% higher than that of SRS.




Figure 3: Each design's mean squared error (MSE) compared with simple random sampling (SRS) at $\tau = 1$ under queen contiguity, within each spillover regime. Each point is one plus the mean paired difference in MSE over the 50 independent configuration-by-surface units divided by SRS's mean MSE in that regime, so that 1 marks equal error and values below 1 mark lower error than SRS. The t_{49} 95% interval is shown for each point. Filled points are significant after Holm's adjustment over the eight designs compared with SRS within the regime (Wilcoxon signed-rank test). The horizontal axis is logarithmic, ratios above 2 are printed, and rows are sorted by the control-only ratio.

Table 5: Full grid benchmark at $\tau = 1$, queen contiguity. Each regime-specific entry averages 80 scenarios (five incidence configurations, four ρ and four γ values). MSE and coverage both use the oracle fit, the spatial lag model that includes the true spillover term, and coverage is that of 95% t-based confidence intervals with a degrees-of-freedom-corrected standard error. Simple random sampling treats 50 of the 100 clusters at random. No value pools queen and rook.

	Both arms		Control only	
Design	MSE	Coverage	MSE	Coverage
Checkerboard	0.062	0.948	2.111	0.951
High Incidence Focus	0.162	0.950	0.329	0.945
Saturation Quadrants	0.044	0.952	0.136	0.940
Isolation Buffer	0.161	0.948	0.159	0.950
2×2 Blocking	0.062	0.947	0.576	0.950
Balanced Quartiles	0.042	0.949	0.219	0.942
Balanced Halves	0.042	0.949	0.218	0.943
Incidence-Guided Saturation	0.046	0.949	0.135	0.945
Simple Random Sampling	0.042	0.950	0.215	0.946




Figure 4: Grid mean MSE at $\tau = 1$ with queen weights, for the six designs and simple random sampling (SRS), under each spillover regime. Points keep the five incidence configurations separate, each averaging the 16 combinations of outcome spatial dependence ρ and spillover magnitude γ within that configuration and regime. Parentheses in the legend give incidence dependence ρ_X. Horizontal lines are 95% Monte Carlo intervals over the ten simulated incidence surfaces and are often narrower than the symbols. Designs share surfaces and outcome noise, so Figure 3 gives the paired comparison of each design with SRS. Table 5 gives the values pooled over configurations for all nine strategies.

3.5 Stability Across Treatment Effect Sizes

Under queen contiguity, the order by average within-block rank and the order by mean MSE were each the same at every $\tau \in \{0.8, 1.0, 1.5, 2.0, 3.0\}$. The two orders differ from each other in the bottom three designs (see Section 3.1; Figure 5a shows mean MSE). With SRS included, the order by average rank placed SRS second at every value of τ, and the Friedman statistic was 564.09, 560.33, 540.92, 526.55, and 497.55 at these five values ($p < 2.2 \times 10^{-16}$ at each). Under rook contiguity the order was also stable (Figure 5b). By average rank among the six designs and SRS, it was the same at every value of τ, with SRS third behind Incidence-Guided Saturation and Balanced Quartiles. By mean MSE, the close pair of 2×2 Blocking and Isolation Buffer traded places, with Isolation Buffer ahead only at $\tau = 3$. The five values of τ share their assignments and noise, so these five comparisons are not independent confirmations of one

another. They show only that, under queen contiguity, the order did not change across the five values of τ we tested, given the same draws.




Figure 5: Mean squared error by design across the five values of the treatment effect, $\tau \in \{0.8, 1.0, 1.5, 2.0, 3.0\}$, under (a) queen contiguity (primary) and (b) rook contiguity (sensitivity). Each point averages the 160 scenarios of one design at one value of τ, pooled over the five incidence configurations. Shaded bands show ± 1 times the average of the scenario-level Monte Carlo standard errors of MSE. They describe the precision of a single scenario's MSE, not of the plotted average, whose standard error is smaller (Table 2). The shared legend lists the designs in order of pooled mean MSE under queen contiguity at $\tau = 1$. The vertical scales of the two panels differ. The gray dashed line marks simple random sampling (SRS). Under rook contiguity, τ is not identified for Checkerboard. Its estimates are kept and flagged. The five values of τ share their assignments and noise.

Within that stable order, the gap in MSE between Incidence-Guided Saturation and Balanced Quartiles under queen contiguity stayed between 0.037 and 0.041, and Incidence-Guided Saturation had the lower MSE of the two in 101 to 103 of the 160 blocks at every value of τ. Isolation Buffer closed the gap instead: its MSE stayed at 0.160 at every value of τ, while that of Incidence-Guided Saturation rose from 0.088 to 0.115 and that of Balanced Quartiles from 0.130 to 0.152. Isolation Buffer's gain came under the control-only regime, where the mean MSE of Incidence-Guided Saturation rose from 0.131 at $\tau = 0.8$ to 0.182 at $\tau = 3$, while that of Isolation Buffer stayed between 0.159 and 0.160. At $\tau = 2$ the two were level (0.160 for Isolation

Buffer against 0.160), and at $\tau = 3$ Isolation Buffer had the lower control-only MSE (0.160 against 0.182). At $\tau = 2$ and $\tau = 3$, Isolation Buffer also had the lower worst case across all 160 blocks (0.207 against 0.210, and 0.208 against 0.238). Incidence-Guided Saturation remained second under the control-only regime at those two values, second to Balanced Quartiles under the both-arms regime at every value of τ, and lowest in pooled MSE at every value of τ. The rise in its MSE was mostly variance: its mean bias grew from 0.029 at $\tau = 0.8$ to 0.047 at $\tau = 3$, but squared bias stayed at or below 3.0% of its MSE. Appendix A7 traces both rises to a term of the estimation error that grows with τ when treated clusters have treated neighbors, and gives the block-level detail.

Under rook contiguity, Incidence-Guided Saturation kept the lowest control-only MSE at every value of τ, although its margin over Isolation Buffer narrowed, from 0.095 against 0.134 at $\tau = 0.8$ to 0.131 against 0.136 at $\tau = 3$.

Except for Checkerboard under rook contiguity, coverage stayed close to 0.95 at every value of τ: between 0.946 and 0.950 for every design under queen contiguity, and between 0.947 and 0.952 for every other design under rook contiguity. The coverage of rook Checkerboard, for which τ is not identified, rose from 0.150 at $\tau = 0.8$ to 0.464 at $\tau = 3$, because its intervals widened around the wrong quantity (Appendix A7). Appendix A3 shows coverage across τ for each design.

3.6 Variation Across Parameter Settings

Table 6 gives the distribution of MSE across the 160 queen blocks at $\tau = 1$. Incidence-Guided Saturation had the lowest median (0.080) and the lowest worst-case MSE of any design (0.169). Isolation Buffer had the narrowest range (0.128 to 0.206), because its MSE does not depend on the spillover regime, but at a higher median than the two leading designs. Balanced Quartiles had a low median (0.115) and a worst case of 0.290. The distributions of 2×2 Blocking and Checkerboard reflected their dependence on the spillover regime: both had low first quartiles (0.062 and 0.063) and high upper quartiles (0.580 and 2.093). Checkerboard had the highest

MSE in all 80 control-only blocks. In the 80 both-arms blocks, the highest MSE belonged to High Incidence Focus in 42 and to Isolation Buffer in 38. Under rook contiguity, Incidence-Guided Saturation also had the lowest worst-case MSE (0.138). These worst cases summarize variation across parameter settings, not the conditional risk across assignments within one setting.

Table 6: Distribution of block-level mean squared error by design across the 160 blocks under queen contiguity at $\tau = 1$, pooled over the five incidence configurations (32 blocks in each). At a fixed value of τ, each block contributes one scenario per design. Rows are sorted by median, which here coincides with the order of pooled mean MSE under queen contiguity (Table 2).

Design	Best	Q25	Median	Q75	Worst
Incidence-Guided Saturation	0.037	0.045	0.080	0.135	0.169
Balanced Quartiles	0.034	0.042	0.115	0.221	0.290
Isolation Buffer	0.128	0.150	0.159	0.169	0.206
High Incidence Focus	0.139	0.160	0.234	0.322	0.424
2×2 Blocking	0.048	0.062	0.271	0.580	0.719
Checkerboard	0.051	0.063	0.899	2.093	2.843

3.7 Allocation-Specific Risk

Under control-only spillover, the worst 10% of SRS allocations on the grid had mean conditional MSE 60% above that of the average SRS allocation (0.346 against 0.217). The saturation designs' worst-decile MSE was 0.54 to 0.55 times SRS's on the grid and 0.64 to 0.68 times in NC. Under both-arms spillover, their worst-decile MSE was 1.06 to 1.07 times SRS's on the grid and 0.93 to 0.94 times in NC (Table 9), so the small mean disadvantage there comes with no worse downside in NC.

Averaged over the 200 units per regime (fixed surfaces crossed with the extreme combinations of ρ and γ), Incidence-Guided Saturation's control-only mean MSE was 0.140 against 0.217 for SRS. Its estimated 90th percentile of allocation-specific MSE was 0.173 against 0.296, and its estimated worst-decile mean was 0.191 against 0.346, lower than SRS in all 200 units on both measures. Under both arms, the corresponding mean MSE was 0.046 against 0.043 and the worst-decile mean 0.058 against 0.054. Saturation Quadrants also performed favorably under control-only spillover. Table 9 in Section 4 compares every design with SRS on both

criteria. These results come from the extreme parameter settings only and give qualified support to saturation on downside risk. The precision check preserved the control-only direction, but outcome noise contributed substantially to the estimated variation across allocations, especially under both arms. Quantiles and worst-decile membership estimated from a finite number of outcomes remain uncertain. We therefore use the completed NC application below as the next setting-specific assessment rather than extrapolate exact tail protection from these settings.

3.8 Rook Contiguity

Under rook contiguity at $\tau = 1$, pooled over the five incidence configurations, the mean-MSE order was Incidence-Guided Saturation (0.072), Balanced Quartiles (0.084), 2×2 Blocking (0.128), Isolation Buffer (0.133), High Incidence Focus (0.206), and Checkerboard (0.480) (Table 2; Figure 16 in Appendix A5). The same order held within each of the five incidence configurations (Table 3). Incidence-Guided Saturation had the lowest MSE in 97 of the 160 rook blocks (61%) and Balanced Quartiles in 60 (38%). Coverage was between 0.948 and 0.952 for every design except Checkerboard, whose coverage was 0.162 (Figure 17 in Appendix A5). With SRS as a seventh member, the Friedman test rejected equal ranks ($\chi^2 = 795.77$, df $= 6$, 160 blocks, $p < 2.2 \times 10^{-16}$). Holm-adjusted Wilcoxon tests separated every pair except two: Balanced Quartiles against SRS, and 2×2 Blocking against Isolation Buffer, which were close and traded places at some values of τ. Nemenyi comparisons also left Incidence-Guided Saturation, Balanced Quartiles and SRS unseparated from one another. Incidence-Guided Saturation nevertheless had the lower MSE in 48 of the 50 independent configuration-by-surface units against Balanced Quartiles (Appendix A3), and its paired comparisons with SRS within each regime appear under Comparison with simple random sampling.

Checkerboard under rook contiguity is a different case: τ is not identified, and the coefficient on $\mathbf{Z}$ estimates $\tau - \gamma$ (Section 2). At $\tau = 1$, Checkerboard's mean bias was -0.502, -0.600, -0.704, and -0.802 at $\gamma = 0.5$, 0.6, 0.7, and 0.8, while its mean standard deviation stayed between

0.20 and 0.21. Squared bias, averaged over scenarios, accounted for 0.438 of its MSE of 0.480 (Figure 18 in Appendix A5). Its coverage fell from 0.337 at $\gamma = 0.5$ to 0.031 at $\gamma = 0.8$, and was between 0.146 and 0.171 at every level of ρ, against 0.949 to 0.952 under queen contiguity (Table 15 in Appendix A4). Because $\mathbf{WZ} = \mathbf{1} - \mathbf{Z}$, the two spillover regimes define the same outcome model. The observed MSEs, 0.477 under the both-arms regime and 0.483 under the control-only regime, differ only by Monte Carlo error. Under rook contiguity, Checkerboard's estimates were precise but centered on the wrong quantity, whereas under queen contiguity they were valid but imprecise. We keep these estimates in every ranking and flag them.

3.9 Non-Oracle Sensitivity Analysis

The non-oracle model, which omits the spillover term, was biased for every design. Table 17 in Appendix A6 gives both models' MSE, bias, and coverage for each design. At $\tau = 1$, and setting aside Checkerboard under rook contiguity, its bias ranged from -0.12 to -0.40 and its coverage from 0.54 to 0.91 across designs and neighbor types. For Checkerboard under rook contiguity, the two models coincide: once the aliased spillover column is dropped, the oracle model is the non-oracle model. Omitting the spillover term also removes a column that can be nearly collinear with $\mathbf{Z}$, and the non-oracle estimates were accordingly less variable for some designs. Under queen contiguity, the non-oracle MSE was lower than the oracle MSE for every design, most of all for Checkerboard (oracle 1.087, non-oracle 0.108) and 2×2 Blocking (oracle 0.319, non-oracle 0.121). Under rook contiguity it was higher for every design except 2×2 Blocking (0.128 under both models) and Checkerboard (identical). Where a design's non-oracle MSE was lower, however, its estimate was biased and its intervals under-covered, so the lower MSE does not support valid inference. These results do not change the recommendation: Incidence-Guided Saturation also had the lowest non-oracle MSE under both neighbor types (0.087 under queen contiguity and 0.086 under rook contiguity).

4 Application to Sudden Unexpected Death in North Carolina

This section repeats the design comparison on the observed North Carolina geography to inform planning of the SUD-prevention education pilot. It uses the outcome model, designs, estimator and performance criteria of Section 2. The first four subsections describe the observed inputs and the changes this setting requires, and the last four report the results.

4.1 Purpose and Observed Inputs

The application asks which allocation designs estimate a known education-intervention effect accurately on this geography, when some designs use historical SUD incidence to direct treatment. It supports planning an education intervention for healthcare professionals involved in SUD prevention. The application uses no observed intervention outcomes and no estimated relationship between local SUD incidence and education ability. Any eventual effect on SUD incidence requires a separate clinical evaluation. A real pilot might realize only one allocation per planning year, so both average estimation error and the risk of a poor allocation matter.

The assignment units are 58 community college service-area clusters that partition North Carolina's 100 counties under the study mapping (Figure 6). Northampton is assigned to Halifax Community College, Bertie to Martin Community College, and Hertford alone to Roanoke-Chowan Community College. These county-to-college assignments are analysis conventions, not exclusive service commitments. Observed county-year deaths at ages 18–64, and population estimates for the same ages from the Surveillance, Epidemiology, and End Results program [30], were aggregated to the same named clusters for each year, 2018–2021. SUD deaths were identified from death certificates with the case-adjudication algorithm of Gan and colleagues [31]. The corrected numerator supplied by Habib includes heart-failure deaths formerly excluded as presumed non-sudden. It totals 23,523 deaths over 25,594,321 person-years. The earlier numerator, which excluded them, reproduces the totals behind Habib's unpublished report

[32]. The application uses the corrected numerator. We do not infer undocumented upstream exclusion rules or zip-code allocation from the received county panel.

Annual incidence is $100,000 D_{iy}/P_{iy}$, and pooled incidence is $100,000 \sum_y D_{iy} / \sum_y P_{iy}$, with the latter population sum interpreted as person-years. All 58 clusters are present in each year, and counts and populations sum back to statewide totals. We hold these observed annual surfaces fixed, generate no synthetic incidence surface and report years separately (Figure 7). The county death-certificate source data are restricted and not publicly available. We report only 58-cluster summaries. The data were obtained under University of North Carolina at Chapel Hill Institutional Review Board protocol 14-2036, "Sudden Unexpected Death in North Carolina" (principal investigator Ross J. Simpson, Jr., Department of Medicine).




Figure 6: Assignment of North Carolina's 100 counties to the 58 community college service areas used as clusters in the planned application. Each county is colored by its primary serving college, and each service area carries a number keyed to the legend. Hatching marks Northampton County, assigned to Halifax Community College (24), and Bertie County, assigned to Martin Community College (30), which also lie within the broader service network of Roanoke-Chowan Community College (41). Roanoke-Chowan serves Hertford County alone in this analysis. The map shows county boundaries and the county-to-college assignment only. It does not depend on the SUD data.




Figure 7: Observed annual SUD incidence per 100,000 adults aged 18–64 in the 58 service-area clusters. These four fixed planning inputs direct incidence-aware allocation. They are not simulated outcomes or measures of education ability.

4.2 Geographic Adaptations and Treatment Budgets

Queen contiguity between service areas, computed from legal county boundaries, defines primary adjacency, and rook contiguity is a sensitivity analysis. Shared legal boundaries across water can create adjacency. Adjacency here is a prespecified geographic proxy for exposure, not a measured network of professional communication.

All eight designs and SRS are evaluated under the names used on the grid, adapted to the irregular map. Appendix A8 gives the rules in full and maps the fixed regions and example assignments. Checkerboard becomes a deterministic greedy graph-coloring assignment, an interspersion analog rather than a literal rectangular checkerboard or an exact bipartite coloring. High Incidence Focus treats the 29 highest annual-rate clusters, and Isolation Buffer draws a greedy random maximal independent set on the NC adjacency graph. SRS treats a random 29 of 58 clusters, and Balanced Quartiles and Balanced Halves stratify annual rate ranks and treat 29 overall.

The two saturation designs use one fixed four-region partition for all years, chosen for geographic compactness and balance without consulting outcomes. Saturation Quadrants randomly assigns 20/40/60/80% to these regions in each draw. Incidence-Guided Saturation ranks the regions by the mean rank of their clusters' annual per-capita rates and assigns 80/60/40/20% from highest to lowest. Mean raw rates and pooled regional rates serve as prespecified alternative regional summaries. On the NC map, 2×2 Blocking uses spatial blocks of nearby clusters, 14 irregular groups formed once per year, and treats half of each group, rounded, at random. Treatment budgets, the numbers of treated clusters, therefore differ across designs. We report them (Table 7) rather than modify the designs to force equal budgets.

Table 7: Primary queen application treatment budgets. Entries are mean treated-cluster counts / percent of annual population aged 18–64. Counts and population shares use the same sampled assignments. Population shares are recalculated for each year, including for designs whose assignments do not depend on annual incidence. Shares are geographic reach, not healthcare-professional enrollment.

Design	2018	2019	2020	2021
Checkerboard	27.00 / 50.4	27.00 / 50.4	27.00 / 50.4	27.00 / 50.7
High Incidence Focus	29.00 / 22.2	29.00 / 23.5	29.00 / 23.3	29.00 / 22.4
Saturation Quadrants	29.03 / 49.2	29.03 / 49.2	29.03 / 49.1	29.03 / 49.1
Isolation Buffer	15.89 / 26.7	15.89 / 26.7	15.89 / 26.7	15.89 / 26.7
2×2 Blocking	28.00 / 50.0	31.00 / 55.1	27.00 / 48.0	29.00 / 50.3
Balanced Quartiles	29.00 / 48.5	29.00 / 49.7	29.00 / 50.6	29.00 / 49.8
Balanced Halves	29.00 / 50.0	29.00 / 50.5	29.00 / 49.2	29.00 / 49.4
Incidence-Guided Saturation	29.00 / 53.2	29.00 / 45.1	29.00 / 47.9	29.00 / 51.8
Simple Random Sampling	29.00 / 49.5	29.00 / 49.5	29.00 / 49.5	29.00 / 49.5

4.3 Outcome Model, Evaluation and Sensitivity Analyses

For the primary education outcome, we set $\beta = 0$ in Equation 1, use the 58-cluster $\mathbf{W}$, and fix $\tau = 1$, $\sigma = 1$:

$$\mathbf{Y} = (\mathbf{I} - \rho\mathbf{W})^{-1}[\tau\mathbf{Z} + \mathbf{S}(\mathbf{Z}) + \varepsilon], \qquad \varepsilon \sim N(\mathbf{0}, \mathbf{I}). \tag{3}$$

Observed incidence affects assignments but neither baseline education nor the constant structural intervention effect. We estimate τ with the same validated maximum likelihood implementation as in the grid study, with an intercept, $\mathbf{Z}$ and the true regime-specific $\mathbf{S}(\mathbf{Z})$, without $\mathbf{X}$. As in

the grid model, τ is the coefficient before spatial propagation, not an average total effect after applying $(\mathbf{I} - \rho\mathbf{W})^{-1}$. For the main application and for the analyses of partial participation and sample size below, we report $\hat{\tau} \pm t_{0.975,\, n-p}\, \widehat{\mathrm{SE}}\sqrt{n/(n-p)}$, where n is the number of participating colleges and p the number of fitted coefficients plus ρ. We test $\tau = 0$ against the same t distribution. The maximum likelihood variance divides by n, and the normal reference distribution ignores the estimated parameters. With 58 or fewer clusters, both make the Wald interval too narrow.

Primary queen settings cross $\rho = 0, 0.2, 0.5$, $\gamma = 0.5, 0.8$, both regimes, four years and nine designs (432 reported settings). A matched hypothetical baseline sensitivity adds $\mathbf{X} = (\mathrm{rank}_{\mathrm{average}}(rate) - 0.5)/58$ with $\beta = 1$ to both the outcome baseline and the fitted covariates (432 settings). It changes baseline and adjustment together and is not an empirical incidence–education association. A rook-contiguity sensitivity analysis of the primary model uses the extreme values $\rho = 0, 0.5$ (288 settings), and the two alternative regional summaries add 96 Incidence-Guided Saturation settings. The full application reports 1,248 settings, computed from 936 distinct simulation settings, because reported settings with the same allocations and outcome model share one simulation.

We sampled $J = 100$ assignments and simulated $R = 100$ independent outcomes per distinct assignment. A design with only one possible assignment instead received $R = 1,000$ outcomes for that assignment, rather than 100 repeated copies of it counted as separate allocations. A prespecified adaptive schedule extended allocations or outcomes where needed until the Monte Carlo standard error of mean MSE was at most 5% of mean MSE and that of coverage at most 0.01. Two single-assignment settings in the matched sensitivity analysis required $R = 2,000$, and all randomized designs met these targets at $J = 100$ and $R = 100$ (Appendix A8). In the primary model, Checkerboard, Saturation Quadrants, Isolation Buffer and SRS reuse the same simulations across years, because annual incidence enters neither their allocation nor the

outcome model, so their repeated values are not independent annual confirmations.

For each allocation a, the repeated outcomes estimate the conditional MSE $m(a) = E_{\varepsilon}[(\hat{\tau} - \tau)^2 \mid a, \text{observed inputs}]$, the expected squared error of the estimate if a were the allocation realized. We report its distribution across sampled allocations, its estimated 90th percentile and the estimated mean among the worst 10% of sampled allocations, alongside unconditional mean MSE, bias and coverage. A separate tail refinement at queen $\rho = 0, 0.5$, $\gamma = 0.8$, both regimes and all years and designs kept the same allocations and extended the randomized designs to $R = 400$ outcomes per allocation, keeping $R = 1,000$ for single-assignment designs. Worst-decile assignments were identified with one half of the simulated outcomes and evaluated with the other half, to avoid selection bias. We recorded design-matrix rank, residual treatment information, aliased columns, warnings, invalid estimates or intervals, and boundary estimates of ρ.

We compared the nine strategies with the Friedman, Nemenyi and Holm-adjusted Wilcoxon tests used on the grid, treating the 24 combinations of year, ρ and γ as blocks, separately for each spillover regime and each value of β. The four years share one map and the strategies whose allocations ignore annual incidence share their simulations across years, so these p-values summarize consistency rather than independent evidence.

To check that the design comparison does not depend on the spatial model, we generated data at $N = 58$ with $\beta = 0$ from the spatial lag model and fitted them with both a conditional autoregressive (CAR) model [33, 34] and the spatial lag model. In the reverse direction, we generated data from a CAR model with the same mean and fitted them with both models. We also fitted two Bayesian models to the spatial lag data, a CAR model with the prior of Leroux and colleagues [35, 36] and a Bayesian spatial lag model [9]. Appendix A9 gives the four models, their priors, the Markov chain Monte Carlo settings and the convergence checks. Finally, we replaced the proportional spillover exposure by a binary indicator of any treated neighbor and by a count of treated neighbors scaled by the mean number of neighbors, with the same form in

the outcome model and the fit.

4.4 Partial Participation and Sample Size

All 58 colleges will be invited to take part after the pilot, but not every college will join. We therefore repeated the application for subsets of N participating colleges, $N \in \{15, 20, 25, 29, 30, 35, 40, 45, 50, 58\}$, under the education outcome model with $\beta = 0$. Under random volunteering, 50 subsets were drawn for each N and shared by every design and year, so designs are compared on the same participants. In a sensitivity analysis at $N = 20$ and $N = 29$, a college's chance of joining rose linearly with its incidence rank, so that the highest-burden college was three times as likely to join as the lowest. Each design was rebuilt on the participants with its own rule, and the four saturation regions were required to contain at least two colleges each. Spatial dependence links participating colleges only, so a participant with no participating neighbor has a zero row in the participants' weights matrix $\mathbf{W}_P$. Spillover exposure counts treated participating neighbors over all geographic neighbors, $e_j(\mathbf{Z}) = \sum_{k \in \mathcal{N}(j)} Z_k / |\mathcal{N}(j)|$, so a non-participating neighbor counts as untreated. Spillover scales with the effect, $\gamma = \kappa\tau$ with $\kappa \in \{0.5, 0.8\}$, and the effect τ took nine values from 0 to 2 in units of the college-level outcome standard deviation. Settings crossed these with $\rho \in \{0, 0.5\}$, both spillover regimes, the nine strategies and the four planning years. With fewer than 58 participants, each setting used 20 allocations and 10 outcomes on each of the 50 subsets (10,000 fits), and a design with a single possible allocation on a subset used 200 outcomes instead. With all 58 colleges, each setting used 100 allocations and 100 outcomes, as in the main application, and reproduced that application's MSE and coverage within Monte Carlo error. All effect sizes share the same subsets, allocations and noise, so power curves are smooth in τ. For each setting we estimated three quantities with the corrected t test above: power, the number of colleges needed for 80% power, and the smallest effect detectable with 80% power at each N.

The trial outcome is a score measured on each trained professional and averaged within each

college. We write a professional's score as a college effect plus individual variation, with total variance 1, so that effects are in individual standard-deviation units. The intraclass correlation coefficient (ICC) is the share of that variance that lies between colleges, so the between-college variance is the ICC and the within-college variance is $1 - \text{ICC}$. Averaging the scores of m professionals leaves the college part unchanged and divides the individual part by m, so the college mean has standard deviation $\sigma_c = \sqrt{\text{ICC} + (1 - \text{ICC})/m}$ [1, 2]. A college-level effect of τ standard deviations is therefore an individual-level standardized effect $d = \tau\sigma_c$. With $\beta = 0$, multiplying the effect and the noise by the same constant leaves $\hat{\tau}/\widehat{\text{SE}}$ unchanged, so power for any m, ICC and d follows from the simulated college-level results. Rerunning one setting with the effect and the noise both halved reproduced its estimates to within 6×10^{-8}. In a sensitivity analysis, the number of trained professionals grew with college population (m averaging 25 over participants, ICC = 0.05), so the noise variance differed between colleges. The fitted model stayed unweighted, as an analyst unaware of the difference would fit it.

4.5 Accuracy, Coverage and Reach

The main run generated 7,598,000 independent outcome fits. Every setting is complete and meets its prespecified precision targets for mean MSE and coverage. The largest relative Monte Carlo standard error of mean MSE is 0.049 and the largest Monte Carlo standard error of coverage is 0.00892. No setting produced warnings, aliased columns, estimates of ρ at the boundary of its parameter space or estimation failures. The tail refinement adds 2,280,000 independent outcomes. Counting the outcomes reused from the main run only once gives 9,878,000 distinct outcomes across the two stages.

Figure 8 compares the eight designs with SRS by year and regime. Under control-only spillover, Saturation Quadrants has descriptive mean MSE 0.223 against SRS 0.308, a 27.4% reduction. Incidence-Guided Saturation reduces mean MSE by 21.1–29.9% across the four observed years (Table 8). Both saturation designs have lower mean MSE than SRS in every primary parameter

setting, and approximate Monte Carlo intervals for each setting-specific difference excluded zero. Neither is uniquely best: as on the grid, the two performed similarly. Under control-only spillover, the performance of High Incidence Focus depends on the year, so we cannot recommend it for every year.

Under both-arms spillover, SRS mean MSE is 0.076, Saturation Quadrants 0.075, and Incidence-Guided Saturation ranges from 0.074 to 0.077 across years. SRS remains competitive with balancing, blocking and saturation. Small point differences do not establish equivalence. High Incidence Focus has low both-arms MSE in the primary model, but its allocation is deterministic for these fixed rates. Its low MSE is model-based accuracy conditional on that allocation, not evidence of randomization-based causal validity.

Mean coverage of the 95% intervals across the four years was between 94.1% and 94.9% for every design and regime, and between 94.1% and 95.1% in single years. The Wald interval covered only 92.6% to 93.6% (Table 24). Meeting the Monte Carlo precision targets did not repair that finite-sample undercoverage, but the corrected t interval described in Section 4.3 did (Appendix A9). Appendix A8 gives bias and coverage for every year, design and regime. Checkerboard's treatment effect is identified on this irregular graph, but weak treatment–spillover separation makes its estimates imprecise. On the rectangular grid under rook contiguity, by contrast, τ is not identified for Checkerboard.

Population shares put these results in context (Table 7). High Incidence Focus treats 29 clusters but only about 22–24% of working-age population, while Isolation Buffer treats a mean of 15.89 clusters and about 27%. These population denominators measure geographic reach, not the number of healthcare professionals educated, intervention cost or participant-level precision.

Incidence-Guided Saturation sends more treatment to high-incidence regions when incidence differs between regions. On the NC map it differs little, because the four regions' mean incidence ranks lie between 24 and 34 of 58 in every year. On average, Incidence-Guided Saturation treats

colleges holding 51.1% of the summed college incidence rates, against 50.4% for Saturation Quadrants and 62.2% for High Incidence Focus. Shares of deaths run the other way (49.2%, 49.6% and 35.4%), because the highest-rate colleges serve small populations. On the simulation grid, where regional incidence differed more, incidence guidance raised the treated share of incidence by 2.1 to 3.1 percentage points over Saturation Quadrants. Across surfaces, the gain rose with the spread of the regions' mean incidence ranks (correlation 0.84 to 0.99; Figure 23 in Appendix A9).




Figure 8: Completed primary application: yearly mean MSE divided by year- and regime-matched SRS MSE, for the eight other designs with queen weights and education outcomes. Each cell averages six ρ/γ settings equally before taking the ratio. Blue indicates lower error than SRS and orange higher error. Colors use a logarithmic ratio scale, and cells print the ratios. SRS mean MSE is 0.076 under both arms and 0.308 control-only. Years that share the same simulations are not independent replications. Absolute MSE, bias, coverage, budgets and setting-specific comparisons are in Appendix A8.

Table 8: Primary application yearly mean MSE, queen contiguity, with equal weights over the six ρ/γ pairs. Saturation Quadrants and SRS reuse the same simulations across years.

	Both arms		Control only		
Year	SRS	Incidence-Guided Saturation	SRS	Saturation Quadrants	Incidence-Guided Saturation
2018	0.076	0.074	0.308	0.223	0.243
2019	0.076	0.076	0.308	0.223	0.216
2020	0.076	0.077	0.308	0.223	0.220
2021	0.076	0.075	0.308	0.223	0.237

4.6 Allocation-Specific Risk in North Carolina

At the two refined queen settings, $\rho = 0$ and $\rho = 0.5$ with $\gamma = 0.8$, under control-only spillover, Saturation Quadrants' estimated 90th percentile of allocation-specific MSE is 31.8–32.9% below SRS and its estimated worst-decile mean 34.6–37.8% below. Incidence-Guided Saturation's corresponding reductions are 20.8–38.6% and 20.7–43.4%. The pattern persists under the split-half evaluation described above. Figure 22 in Appendix A8 shows the $\rho = 0.5$ setting. These reductions support a descriptive downside benefit alongside lower average error, conditional on the studied model and sampled assignments.

Table 9 compares every design with SRS on both criteria, mean conditional MSE and the mean of the worst 10% of sampled allocations, on the grid and at the refined NC settings. Under control-only spillover, both saturation designs had lower mean and worst-decile MSE than SRS in both settings. Isolation Buffer also had a lower worst decile than SRS under control-only spillover (0.62 of SRS on the grid and 0.91 in NC). Under both-arms spillover, its mean was 3.80 and 3.69 times that of SRS, and it treated fewer clusters. High Incidence Focus has a single allocation in NC. That allocation's MSE was below the SRS worst-decile mean under both regimes (0.76 under both arms and 0.64 under control-only spillover), with mean MSE close to SRS (0.93 and 1.03). On the grid, however, its both-arms mean was 3.81 times that of SRS, and its NC result depends on the incidence model, as the matched sensitivity analysis below shows. Balanced Quartiles and Balanced Halves matched SRS on both criteria. Checkerboard and 2×2 Blocking did not improve on SRS on either criterion in any setting.

Figure 9 shows the full allocation-to-allocation distribution for the six designs and SRS. Under control-only spillover, most Incidence-Guided Saturation allocations had lower MSE than the average SRS allocation in both studies, whereas the SRS distribution extended well above its mean.

The tail estimates remain uncertain. With $J = 100$, the worst decile contains only ten sampled

Table 9: Mean conditional MSE and worst-decile mean conditional MSE of each design divided by those of SRS in the same setting and spillover regime (below 1 is lower error than SRS). Grid: allocation-risk study, queen contiguity, $\tau = 1$, averaged over 200 units, each a fixed incidence surface with one extreme combination of ρ and γ. NC: refined queen settings $\rho \in \{0, 0.5\}$, $\gamma = 0.8$, averaged equally over 2018–2021 and both values of ρ. NC designs are the map adaptations (Checkerboard as a greedy graph-coloring assignment, 2×2 Blocking on spatial blocks of nearby clusters, and both saturation designs on four fixed regions). A design with one allocation has worst-decile mean equal to its mean.

	Grid				NC application			
	Both arms		Control only		Both arms		Control only	
Design	Mean	Worst 10%	Mean	Worst 10%	Mean	Worst 10%	Mean	Worst 10%
Checkerboard	1.41	1.11	9.94	6.22	2.68	2.20	3.02	1.88
High Incidence Focus	3.81	3.05	1.51	0.96	0.93	0.76	1.03	0.64
Saturation Quadrants	1.06	1.06	0.62	0.54	0.99	0.94	0.73	0.64
Isolation Buffer	3.80	3.97	0.75	0.62	3.69	4.75	0.93	0.91
2×2 Blocking	1.44	1.57	2.69	2.64	1.00	1.02	1.15	1.18
Balanced Quartiles	0.99	0.99	1.00	1.01	0.98	0.96	0.95	1.01
Balanced Halves	0.99	0.99	1.01	1.01	0.98	0.96	0.97	0.99
Incidence-Guided Saturation	1.07	1.07	0.65	0.55	0.98	0.93	0.75	0.68
Simple Random Sampling	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

draws. Extra outcomes reduce noise in $\hat{m}(a)$ but do not enlarge the allocation sample. All 112 reported settings in the tail refinement for designs with more than one possible assignment flag uncertain worst-decile membership. Under both arms, the Jaccard index of the worst deciles identified by the two outcome halves (allocations in both divided by allocations in either) was 0–0.25 for Incidence-Guided Saturation, and approximately 61–86% of the raw variance of estimated risk across allocations was attributable to outcome Monte Carlo noise. Saturation Quadrants' worst-decile membership was similarly unstable. Small both-arms tail differences therefore do not establish superior downside protection. Checkerboard and High Incidence Focus each have only one possible assignment for these inputs. Their 90th percentile and worst-decile mean equal their conditional mean MSE, which does not imply low error or absence of outcome uncertainty.

4.7 Sensitivity Analyses

In the matched hypothetical sensitivity analysis, which adds incidence to the baseline and adjusts for it, High Incidence Focus MSE rises to roughly 3.68–4.44 times its primary value under both arms and 1.42–2.52 times under control-only spillover. Because this design treats




Figure 9: Distribution of allocation-specific MSE for the six designs and simple random sampling (SRS), relative to the mean MSE of SRS in the same setting (queen weights). Simulation study: grid allocation-risk study at $\tau = 1$, 200 fixed surface/parameter settings per spillover regime. Application study: refined NC settings ($\rho = 0, 0.5$; $\gamma = 0.8$) in each year 2018–2021. For each allocation, MSE is estimated from repeated simulated outcomes (100 in the simulation study, at least 400 in the application study). Thin lines span the 5th to 95th percentiles of allocations and thick bars the 25th to 75th. Circles mark the mean. Percentiles are computed within each setting and then averaged, so bars show allocation-to-allocation spread. A design with one allocation per setting appears as a circle only. Outcome Monte Carlo noise in the per-allocation estimates widens the bars slightly.

the highest-incidence clusters, adjusting for incidence leaves less residual treatment information. Comparing rook and queen contiguity at the same extreme combinations of ρ and γ leaves the regime-specific conclusions broadly unchanged. Alternative regional summaries change the regional ordering in some years. Where an alternative summary gives the same ordering and ties, it gives the same set of possible assignments and so the same results. We retain the prespecified mean-rank rule rather than select a summary retrospectively. Appendix A8 reports the matched sensitivity table and regional ordering.

The design comparison did not depend on the spatial model used to generate or fit the data, with one exception (Appendix A9). Fitting a CAR model, generating the data from a CAR model, or

both, left the saturation designs with 0.76 to 0.82 times SRS's MSE under control-only spillover. Checkerboard and Isolation Buffer were still the worst designs under both-arms spillover. A Bayesian spatial lag model reproduced the maximum likelihood results, with posterior means correlated 0.999 with the maximum likelihood estimates, credible-interval coverage of 94.6% to 95.3% and the same design ordering. The exception is the Bayesian CAR model with strong spatial dependence ($\rho = 0.5$). Its estimates were biased by 0.14 to 0.22 even when its chains converged, its coverage was 88% to 90%, and it did not reproduce the saturation designs' control-only advantage. That model assumes a different dependence structure from the one that generated the data, and the correctly specified Bayesian model does not share the problem. Under a binary spillover exposure Isolation Buffer was never identified, and under a count exposure the saturation designs still had the lowest MSE under control-only spillover. Formal tests over the 24 combinations of year, ρ and γ rejected equal ranks for every regime and value of β (Friedman χ^2 from 135 to 180 on 8 degrees of freedom). Under control-only spillover, the two saturation designs had the two best average ranks.

4.8 Colleges Needed Under Partial Participation

Under both-arms spillover, the design hardly affected the number of colleges a trial needs. Every design except Checkerboard and Isolation Buffer needed 35 to 37 colleges for 80% power to detect a college-level effect of one standard deviation, and about 19 colleges for 1.5 standard deviations (Figure 10, Table 21). Checkerboard and Isolation Buffer did not reach 80% power at $\tau = 1$ even with all 58 colleges.

Under control-only spillover, no design reached 80% power at $\tau = 1$ with all 58 colleges. At $\tau = 1.5$ the two saturation designs needed 28 colleges, against 29 to 32 for SRS and the rank-based designs (High Incidence Focus, Balanced Quartiles and Balanced Halves). At that effect, 2×2 Blocking and Isolation Buffer failed to reach 80% power with 58 colleges in one of the four planning years. Power under control-only spillover rose slowly beyond about 40 colleges

(Figure 11). When nearly every college participates, nearly every control has a treated neighbor, so spillover exposure varies little and is hard to separate from treatment. Non-participating neighbors restore some of that variation, and so do the saturation designs. With all 58 colleges, the smallest effect detectable with 80% power under both-arms spillover was 0.76 to 0.78 college-level standard deviations for every design except Checkerboard (1.32) and Isolation Buffer (1.50). Under control-only spillover it was 1.24 to 1.25 for the two saturation designs, against 1.45 to 1.57 for SRS and the rank-based designs.




Figure 10: Number of participating colleges needed for 80% power with the corrected t test, by design, for a college-level effect of $\tau = 1$ standard deviation under both-arms spillover and $\tau = 1.5$ under control-only spillover, with random volunteering, $\rho = 0.5$ and $\gamma = 0.8\tau$. Dark bars show the mean over the 2018–2021 planning years and whiskers the range. Light bars mark designs that did not reach 80% power with all 58 colleges in the stated number of years, with the smallest number needed in the other years.

With $m = 25$ trained professionals per college and an ICC of 0.05, $\sigma_c = 0.30$. Under both-arms spillover, an individual-level effect of $d = 0.3$ then gives power 0.71 to 0.72 with 29 colleges and 0.96 with 58, for SRS and for both saturation designs. Under control-only spillover the same effect gives power 0.49 and 0.53 with SRS, and 0.51 and 0.64 with Incidence-Guided Saturation (Table 22 in Appendix A9). Letting the number of professionals grow with college population, at the same average of 25, reduced power by 0.097 on average across designs, settings and effect




Figure 11: Power of the corrected t test against the number of participating colleges for simple random sampling (SRS), the two saturation designs and Checkerboard, by spillover regime (columns) and college-level effect (rows), with random volunteering, $\rho = 0.5$ and $\gamma = 0.8\tau$. Lines show the mean over the 2018–2021 planning years and bands the range, which is narrower than the lines except near 58 colleges, and the dashed line marks 80% power. The two saturation designs nearly coincide. Each number of colleges uses its own 50 random participant subsets, so the small drop from 29 to 30 colleges reflects which subsets were drawn.

sizes and changed no design's relative standing.

The Wald test rejected a true null hypothesis in 11% to 13% of simulated trials with 15 colleges and in 6% to 7% with 58. With the corrected t test the rejection rate was 4.4% to 5.6%. The coverage of the corrected interval at $\tau = 1$ was between 94.0% and 95.6% for every design and regime at every number of colleges (Table 23 in Appendix A9). The colleges-needed numbers above therefore come from a test with the nominal size.

The regime-specific guidance held with fewer participants, but the size of the saturation advantage depended on participation (Table 25 in Appendix A9). Checkerboard and Isolation Buffer

remained worse than SRS under both-arms spillover at every number of colleges, and the rank-based designs' mean MSE was within 2% of that of SRS, except High Incidence Focus with 40 and 58 colleges (4% and 8% below). Under control-only spillover, the saturation designs' mean MSE was 22% below that of SRS with 58 colleges, 9% to 10% below with 40, 4% to 5% below with 29 and about 1% below with 20. With few participants, non-participating neighbors already create the exposure variation that saturation otherwise supplies. When the colleges with higher incidence were more likely to volunteer, the saturation designs' advantage over SRS was 2% or less at 20 and 29 colleges. Isolation Buffer went from matching SRS under control-only spillover with 58 colleges to 2.3 times SRS's MSE with 29 colleges and 6.2 times with 15.

The application supports considering either saturation strategy when control-only spillover is plausible, and SRS alongside other randomized strategies when both-arms exposure is expected. A trial team should consider likely spillover, recruitment, cluster and participant budgets, achievable measurement precision and interval calibration before selecting one realized allocation.

5 Discussion

5.1 Summary of Findings

We compared six treatment assignment designs in the detailed grid ranking, plus two related variants and SRS, for a spatial cluster randomized trial on a grid of 100 clusters. The comparison covered three mechanisms of heterogeneous baseline incidence, two spillover regimes, and a range of values for spatial dependence, spillover magnitude, and the treatment effect. Some findings held across the incidence configurations and the values of ρ, γ, and τ under queen contiguity. Others depended on the spillover regime, which a trial team may not know in advance.

We judged each design on two criteria: its average MSE, and the spread of MSE across the allocations it can produce. A trial realizes one allocation, so a design with a low average MSE can still give a poor estimate if some of its allocations perform badly. Chapter 2 compared

simple random and block stratified sampling on the same two criteria. For SRS under control-only spillover, the spread was large: on the grid, the worst 10% of SRS allocations had mean conditional MSE 0.346, against 0.217 for SRS allocations overall.

Under queen contiguity, Incidence-Guided Saturation had the lowest mean squared error (0.091) and Balanced Quartiles the second lowest (0.131), and the same two designs led under rook contiguity (0.072 and 0.084). Under queen contiguity, the order of the six designs was the same in each of the five incidence configurations and at every value of τ, and neither the strength of spatial dependence in the outcome nor the spillover magnitude changed it. The mechanism that generated the incidence surface changed each design's MSE by under 10%, except for High Incidence Focus. Coverage of the 95% intervals was close to 0.95 for every design under both neighbor types, except Checkerboard under rook contiguity, so the designs differed in precision and coverage did not separate them.

The spillover regime was the one factor that changed the queen ranking. Under queen contiguity at $\tau = 1$, Checkerboard and 2×2 Blocking were close to the best designs when spillover reached both arms and were the two worst when it reached only control clusters (MSE 0.062 and 2.111 for Checkerboard, 0.062 and 0.576 for 2×2 Blocking). Balanced Quartiles also lost ground under the control-only regime (0.042 and 0.219). Incidence-Guided Saturation, by contrast, was first or second among the six detailed designs under both regimes at every value of τ, with a both-arms MSE 8% above that of SRS. Its control-only MSE did rise with τ, and Isolation Buffer, whose MSE did not, matched or passed it under that regime at $\tau = 2$ and passed it at $\tau = 3$. For a design whose performance depends on the regime, average MSE does not show the risk of choosing it when the regime is unknown.

Checkerboard, the strict allocation of Chapter 2, failed for different reasons under the two neighbor types. Under queen contiguity its estimates stayed centered on τ with close to nominal coverage but were imprecise, because under the control-only regime only the boundary clusters

separate the spillover effect from the treatment effect. Under rook contiguity, τ is not identified, and its estimates were centered on $\tau - \gamma$. Checkerboard intersperses treated and control clusters as finely as the grid allows, and both failures come from the dependence this pattern creates between $\mathbf{Z}$ and the spillover covariate (Section 2).

These design-stage results assume an analysis that models spillover: every design was analyzed with a spatial lag model that included the spillover term. In the grid study, the estimates were close to unbiased for every design whose τ was identified: at $\tau = 1$, the absolute bias of each design under each regime was at most 0.048 under queen contiguity and 0.027 under rook contiguity. Given that model, the choice of design determined how precisely τ was estimated.

5.2 Design Guidance by Spillover Regime

When spillover is expected to reach mainly control clusters, Incidence-Guided Saturation and Saturation Quadrants had the lowest mean MSE and among the lowest worst-decile MSE (Table 9), so they are the designs we recommend over SRS. Isolation Buffer also limited downside in that regime, but it should be considered only when both-arms spillover is implausible and a smaller treated budget is acceptable. When spillover is expected to reach both arms, the spread of MSE across allocations was small for SRS and the balancing and saturation designs. SRS, Balanced Quartiles and Balanced Halves performed about equally. The saturation designs had mean MSE 4% to 8% above SRS on the grid and within 3% of it in NC, with worst-decile MSE within 7% of SRS's in both, so SRS and the saturation designs are both reasonable choices.

The number of colleges a trial needs depends far more on the spillover regime than on the design. Under both-arms spillover, 35 to 37 colleges detect a one-standard-deviation college-level effect with any design except Checkerboard and Isolation Buffer, whereas under control-only spillover even all 58 colleges do not. The saturation designs' advantage over SRS also shrinks as fewer colleges join.

High Incidence Focus gave one fixed allocation whose MSE in NC was below the SRS worst-decile mean under both regimes. Its accuracy is model-based rather than randomization-based, however. On the grid, its both-arms MSE was about four times that of SRS. Its MSE also rose 1.4–4.4-fold when baseline outcomes were related to incidence. It is a candidate only when historical incidence can be assumed unrelated to the outcome. Checkerboard and 2×2 Blocking did not improve on SRS on either criterion.

Saturation Quadrants, which assigns the same saturations without reference to incidence, performed similarly to Incidence-Guided Saturation (see Section 2.3). Their accuracy advantage over SRS under control-only spillover therefore comes from the shared saturation structure, and incidence guidance lets a trial direct its highest treatment saturations to the highest-incidence regions with little or no loss of estimation accuracy. How much treatment it redirects depends on how much incidence differs between regions, a few percentage points of incidence share on the grid and less than one on the NC map, whose regions have similar incidence.

5.3 Relation to Chapter 2

Chapter 2's practical argument considered reasonably good estimation together with protection against poor allocation in the small-grid settings it studied. We preserve both criteria while extending the designs, geography and incidence conditions. Our findings concern these new models and settings and do not compare numerical results across chapters directly. The rectangular Checkerboard and its graph adaptation illustrate why a restricted allocation's low assignment variation must be interpreted together with its level of estimation error. The application also separates incidence-guided assignment from assumptions about education outcomes.

5.4 Limitations

First, the primary estimator is an oracle. It includes the exact spillover exposure term, so its results are a best case for each design. We fit a non-oracle model that omits the spillover

term as a sensitivity analysis. It was biased for every design and its intervals under-covered, but Incidence-Guided Saturation still had the lowest MSE under both neighbor types. The non-oracle model is only one departure from the oracle. We did not study an analyst who includes a spillover term of the wrong form, such as one built on the wrong neighbor definition or a distance decay.

Second, in the synthetic grid study, the designs and the fitted model used the incidence surface that generated the outcome (the matched-surface assumption in Section 2). In practice, planning incidence is estimated from an earlier period and measured with error. The designs that assign treatment by incidence rank, and the covariate adjustment, would then use a noisy surface, and we did not study how that changes the comparison.

Third, in the Poisson mechanism every cluster had the same population of 100,000. Real clusters, including the community college service areas in Section 4, differ in population, so their observed rates differ in precision, and unequal populations may change how the designs that use incidence perform. In the application, letting the number of trained professionals grow with college population reduced power by about 0.1 for every design and changed no design's relative standing.

Fourth, the full synthetic comparison uses one regular 10×10 grid, with β and σ fixed at 1. The application adds one irregular 58-cluster geography and unequal observed populations, but is not a systematic sweep over graph sizes, structures or participant budgets. Some grid results depend on its boundary geometry, and the design adaptations in the application also change which assignments are possible.

Fifth, the simulation shares random draws by design. Blocks within an incidence configuration share its ten incidence surfaces, so the block-level tests treat dependent blocks as independent, which is why we also compared adjacent designs over the 50 independent configuration-by-surface units. The five values of τ also share their draws, so the stability of the design order across τ is

not an independent replication at each value (see Section 3.5). Settings and years that share the same simulations cannot be treated as independent confirmation.

Sixth, the simulation's base rate of 35 per 100,000 is not the rate of the county data described in Section 4 (see Section 2.2). We kept it deliberately, because the simulation is a general design study rather than a calibration to one data set. In the Poisson mechanism, incidence enters the designs and the fitted model only through the ranks of the observed rates, so the base rate affects the simulation only through the spatial pattern of those ranks and the number of tied rates.

Seventh, application results are conditional on a continuous education-outcome model with known spillover form and constant structural effect, not an observed education intervention or demonstrated reduction in SUD. Working-age population is a geographic denominator rather than a sample of healthcare professionals. Historical rates are held fixed, so uncertainty in their measurement and changes between planning and implementation are not propagated. The matched baseline sensitivity is hypothetical.

Eighth, the 95% Wald intervals under-covered in both the grid and the application, and the Wald test was anti-conservative with few colleges. A small-sample correction, a t reference distribution with a degrees-of-freedom-corrected standard error, restored coverage to between 94% and 96% for every design in the application at every number of participating colleges (Appendix A9) and to between 0.946 and 0.952 for every identified design on the grid. We therefore report it in both studies. The finite-outcome allocation-tail estimates do not remove noise from individual risks or establish population worst cases. Budgets also differ, so these are evaluations of the retained strategies, not an equal-cost optimization.

Ninth, the participation analysis assumes that colleges volunteer at random or with probability rising with incidence, and that non-participating colleges neither transmit nor receive spillover.

5.5 Future Work

The next trial-design steps are to specify the education endpoint, eligible professionals, implementation budget and plausible spillover network, then assess interval calibration for that protocol before randomization. Additional methodological work could study noisy planning incidence, effect heterogeneity, exposure networks beyond contiguity and a broader set of graph geometries. The trial endpoint here is a measured education score, an intermediate outcome. Designing for a later reduction in SUD incidence would need a count outcome model and is left for future work. A larger allocation sample could make the downside estimates more precise if that precision is needed for a final choice.

References

[1] Allan Donner and Neil Klar. *Design and analysis of cluster randomization trials in health research*. Arnold, 2000.

[2] Richard J. Hayes and Lawrence H. Moulton. *Cluster randomised trials*. Chapman and Hall/CRC, 2 edition, 2017.

[3] Donald B. Rubin. Statistics and causal inference: Comment: Which ifs have causal answers. *Journal of the American Statistical Association*, 81(396):961–962, 1986.

[4] Michael G Hudgens and M. Elizabeth Halloran. Toward causal inference with interference. *Journal of the American Statistical Association*, 103(482):832–842, 2008.

[5] W. R. Tobler. A computer movie simulating urban growth in the Detroit region. *Economic Geography*, 46:234, 1970.

[6] F. N. Binka, F. Indome, and T. Smith. Impact of spatial distribution of permethrin-impregnated bed nets on child mortality in rural northern Ghana. *The American Journal of Tropical Medicine and Hygiene*, 59(1):80–85, 1998.

[7] Edward Miguel and Michael Kremer. Worms: Identifying impacts on education and health in the presence of treatment externalities. *Econometrica*, 72(1):159–217, 2004.

[8] P. A. P. Moran. The interpretation of statistical maps. *Journal of the Royal Statistical Society Series B: Statistical Methodology*, 10(2):243–251, 1948.

[9] James LeSage and Robert Kelley Pace. *Introduction to spatial econometrics*. Chapman and Hall/CRC, 2009.

[10] Keith Ord. Estimation methods for models of spatial interaction. *Journal of the American Statistical Association*, 70(349):120–126, 1975.

[11] Roger Bivand. R packages for analyzing spatial data: A comparative case study with areal data. *Geographical Analysis*, 54(3):488–518, 2022.

[12] Christopher Jarvis, Gian Luca Di Tanna, Daniel Lewis, Neal Alexander, and W. John Edmunds. Spatial analysis of cluster randomised trials: a systematic review of analysis methods. *Emerging Themes in Epidemiology*, 14(1):12, 2017.

[13] Gillian M. Raab and Izzy Butcher. Balance in cluster randomized trials. *Statistics in Medicine*, 20(3):351–365, 2001.

[14] Lawrence H. Moulton. Covariate-based constrained randomization of group-randomized trials. *Clinical Trials*, 1(3):297–305, 2004.

[15] Amy M Crisp, M Elizabeth Halloran, Ira M Longini, Gonzalo Vazquez-Prokopec, and Natalie E Dean. Covariate-constrained randomization with cluster selection and substitution. *Clinical Trials*, 20(3):284–292, 2023.

[16] Sarah Baird, J. Aislinn Bohren, Craig McIntosh, and Berk Özler. Optimal design of experiments in the presence of interference. *The Review of Economics and Statistics*, 100(5):844–860, 2018.

[17] Robert S. McCann, Henk van den Berg, Willem Takken, Andrew G. Chetwynd, Emanuele Giorgi, Dianne J. Terlouw, and Peter J. Diggle. Reducing contamination risk in cluster-randomized infectious disease-intervention trials. *International Journal of Epidemiology*, 47(6):2015–2024, 2018.

[18] Michael P. Leung. Rate-optimal cluster-randomized designs for spatial interference. *The Annals of Statistics*, 50(5):3064–3087, 2022.

[19] Chencheng Cai, Xu Zhang, and Edoardo M. Airoldi. Independent-set design of experiments for estimating treatment and spillover effects under network interference. In *Proceedings of the 12th International Conference on Learning Representations (ICLR 2024)*, Vienna, Austria, 2024.

[20] Michael P. Leung. Cluster-randomized trials with cross-cluster interference. *Journal of the American Statistical Association*, pages 1361–1371, 2025.

[21] Samuel I. Watson and Thomas A. Smith. Design and analysis of randomized trials to estimate spatio-temporally heterogeneous treatment effects. *Journal of the American Statistical Association*, 121(553):502–512, 2026.

[22] Mojtaba Mirzaei, Golsa Joodi, Brittany Bogle, Sarah Chen, and Ross J. Simpson. Years of life and productivity loss because of adult sudden unexpected death in the United States. *Medical Care*, 57(7):498–502, 2019.

[23] Roger Bivand and Gianfranco Piras. Comparing implementations of estimation methods for spatial econometrics. *Journal of Statistical Software*, 63(18), 2015.

[24] Tim P. Morris, Ian R. White, and Michael J. Crowther. Using simulation studies to evaluate statistical methods. *Statistics in Medicine*, 38(11):2074–2102, 2019.

[25] Milton Friedman. The use of ranks to avoid the assumption of normality implicit in the analysis of variance. *Journal of the American Statistical Association*, 32(200):675–701, 1937.

[26] Peter Bjorn Nemenyi. *Distribution-Free Multiple Comparisons*. PhD thesis, Princeton University, Princeton, NJ, 1963.

[27] Janez Demšar. Statistical comparisons of classifiers over multiple data sets. *Journal of Machine Learning Research*, 7:1–30, 2006.

[28] Frank Wilcoxon. Individual comparisons by ranking methods. *Biometrics Bulletin*, 1(6):80–83, 1945.

[29] Sture Holm. A simple sequentially rejective multiple test procedure. *Scandinavian Journal of Statistics*, 6(2):65–70, 1979.

[30] National Cancer Institute, Surveillance, Epidemiology, and End Results Program. U.S. county population data 1969–2023. https://seer.cancer.gov/popdata/. Accessed 27 October 2026.

[31] Zoe Su Wen Gan, Wansuk Choi, Feng-Chang Lin, Rebecca Tippett, Golsa Joodi, Irion Pursell, and Ross Joseph Simpson. Factors underlying increased incidence of sudden unexpected death in rural counties in North Carolina. *Journal of General Internal Medicine*, 34(6):815–817, 2019.

[32] Ashkan Habib. Temporal trends and social determinants of sudden death mortality in North Carolina. Master's paper, Department of Biostatistics, University of North Carolina at Chapel Hill, Chapel Hill, NC, April 2026. Unpublished.

[33] Julian Besag. Spatial interaction and the statistical analysis of lattice systems. *Journal of the Royal Statistical Society: Series B (Methodological)*, 36(2):192–225, 1974.

[34] Noel A. C. Cressie. *Statistics for spatial data*. Wiley, 1993.

[35] Brian G. Leroux, Xingye Lei, and Norman E. Breslow. Estimation of disease rates in small areas: A new mixed model for spatial dependence. In M. Elizabeth Halloran and Donald Berry, editors, *Statistical Models in Epidemiology, the Environment, and Clinical Trials*,

volume 116 of *The IMA Volumes in Mathematics and its Applications*, pages 179–191. Springer, New York, NY, 2000.

[36] Duncan Lee. CARBayes: An R package for Bayesian spatial modeling with conditional autoregressive priors. *Journal of Statistical Software*, 55(13):1–24, 2013.

[37] John Geweke. Evaluating the accuracy of sampling-based approaches to the calculation of posterior moments. In José M. Bernardo, James O. Berger, A. Philip Dawid, and Adrian F. M. Smith, editors, *Bayesian Statistics 4*, pages 169–193. Oxford University Press, Oxford, 1992.

Appendix

A1. The Eight-Design Comparison

Table 10 defines, in the format of Table 1, the two related variants that are excluded from the detailed six-design grid ranking but included in the nine-design benchmark and the application in the body. Table 11 compares all eight designs and SRS at the primary scenario, $\tau = 1$.

Table 10: The two related variants outside the detailed six-design grid ranking, in the format of Table 1. Saturation Quadrants shares its mechanism with Incidence-Guided Saturation, and Balanced Halves with Balanced Quartiles (see Section 2.3). Incidence rank and clusters treated are defined as in Table 1.

Design	Assignment rule	Clusters treated	Deterministic
Saturation Quadrants	The grid is divided into its four 5×5 coordinate quadrants, which are given saturations of 20%, 40%, 60%, and 80% in an order drawn at random for each assignment, without reference to incidence; within each quadrant, that share of its 25 clusters is treated at random	50	No
Balanced Halves	Clusters are divided by incidence rank into two strata of 50; 25 clusters are treated at random in each stratum	50	No

We compared each excluded design with its retained counterpart using the Nemenyi and Holm-adjusted Wilcoxon signed-rank tests described in Section 2.5, applied here to all eight designs and SRS. Saturation Quadrants' mean squared error was 0.090, against 0.091 for Incidence-Guided Saturation, under queen contiguity (Nemenyi $p = 0.99$; Holm-adjusted Wilcoxon signed-rank $p = 0.62$), and 0.071 against 0.072 under rook contiguity (Nemenyi $p = 1.00$; Wilcoxon $p = 1.00$). Saturation Quadrants had the marginally lower mean under both neighbor types and the better average rank in this comparison (2.394 against 2.700 under queen contiguity and 2.587 against 2.650 under rook contiguity). Retaining Incidence-Guided Saturation as the representative of the saturation mechanism therefore does not rest on performance. Balanced Halves had a mean squared error of 0.130, against 0.131 for Balanced Quartiles, under queen contiguity (Nemenyi $p = 1.00$; Wilcoxon $p = 1.00$), and 0.084 against 0.084 under rook contiguity (Nemenyi $p = 1.00$;

Wilcoxon $p = 1.00$). Balanced Halves had the marginally lower mean and the better average rank under queen contiguity (3.831 against 3.906), and Balanced Quartiles had both under rook contiguity (3.369 against 3.569). The two designs differ only in how finely they stratify on incidence, and we retain the finer, four-stratum version. Under both neighbor types, each excluded design is adjacent to its retained counterpart in mean MSE (Table 11). The MSEs and coverages of the six retained designs are those of Table 2, given here to four and three decimal places.

Table 11: Performance of all eight designs and SRS at the primary scenario, $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity), pooled over the five incidence configurations. Each entry averages the 160 scenarios of one design and neighbor type (5 incidence configurations $\times$ 4 values of ρ $\times$ 4 values of γ $\times$ 2 spillover regimes), each summarizing 250 fits of the oracle model. Rows in both panels are in order of mean squared error (MSE) under queen contiguity. Retained marks the six designs compared in the body of this chapter, and SRS is the benchmark. Average rank is the mean of each design's within-block MSE rank among the eight designs and SRS over the 160 blocks (1 = lowest MSE), so it differs from the average rank in Table 2. Under rook contiguity, τ is not identified for Checkerboard. Its estimates are kept and flagged.

Design	Retained	MSE	Coverage	Average rank
Queen contiguity (primary)				
Saturation Quadrants	No	0.090	0.946	2.394
Incidence-Guided Saturation	Yes	0.091	0.947	2.700
Simple Random Sampling	Benchmark	0.128	0.948	3.788
Balanced Halves	No	0.130	0.946	3.831
Balanced Quartiles	Yes	0.131	0.946	3.906
Isolation Buffer	Yes	0.160	0.949	5.638
High Incidence Focus	Yes	0.245	0.948	7.763
2×2 Blocking	Yes	0.319	0.948	7.244
Checkerboard	Yes	1.087	0.950	7.737
Rook contiguity (sensitivity)				
Saturation Quadrants	No	0.071	0.949	2.587
Incidence-Guided Saturation	Yes	0.072	0.952	2.650
Simple Random Sampling	Benchmark	0.085	0.947	3.612
Balanced Halves	No	0.084	0.949	3.569
Balanced Quartiles	Yes	0.084	0.948	3.369
Isolation Buffer	Yes	0.133	0.950	6.050
High Incidence Focus	Yes	0.206	0.948	7.969
2×2 Blocking	Yes	0.128	0.948	6.206
Checkerboard (flagged)	Yes	0.480	0.162	8.988

A2. Simulation Mechanics

This section gives the mechanical details behind Section 2.5 (Section 2): the parameter grid, the random-number streams, the Monte Carlo structure, and the exact formulas for the metrics and their Monte Carlo standard errors.

Parameter grid. Table 12 lists the parameters that were crossed to form the 12,800 scenarios and the settings that were held fixed.

Table 12: Parameter grid of the original eight-design simulation. The crossed parameters form $5 \times 5 \times 2 \times 4 \times 4 \times 2 \times 8 = 12{,}800$ scenarios, 9,600 of them for the six designs compared in the body of this chapter. The settings in the lower panel are the same in every scenario.

Parameter	Values	Levels
Crossed		
Treatment effect τ	0.8, 1.0 (primary), 1.5, 2.0, 3.0	5
Incidence configuration	iid; spatially autocorrelated, $\rho_X \in \{0.20, 0.50\}$; Poisson, $\rho_X \in \{0.20, 0.50\}$	5
Neighbor type	Queen (primary), rook (sensitivity)	2
Outcome spatial dependence ρ	0, 0.01, 0.20, 0.50	4
Spillover magnitude γ	0.5, 0.6, 0.7, 0.8	4
Spillover regime	Both arms, control only (Equation 2)	2
Design	The six designs of Table 1 and the two of Table 10	8
Fixed		
Grid	Regular 10×10 grid, $N = 100$ clusters	
Outcome model (Equation 1)	$\beta = 1$, $\sigma = 1$	
Poisson mechanism	Base rate 35 per 100,000; $P = 100{,}000$ per cluster	
Incidence surfaces per configuration	$K = 10$	
Assignments per surface	$J = 25$ (Checkerboard: one assignment, used in every draw)	
Fits per scenario and estimator	$KJ = 250$, each with its own noise vector	
Estimators	Oracle (primary) and non-oracle (sensitivity), both fit to every simulated outcome	

Random-number streams. Every random draw in the simulation has its own seed, computed by hashing a key that names the draw. The key lists the draw's type (incidence surface, assignments, or noise) and the parameters that identify it, with numeric values written to a fixed number of decimal places so that equal values always give the same key. The random-number generator and its methods for normal and discrete draws are also fixed explicitly, so the streams do not depend on software defaults. Table 13 lists the three kinds of draw, the parameters in their keys, and the scenarios that therefore share them. Section 2 describes the consequences of

this scheme: independence from the order of execution, and common random numbers.

Table 13: Seed keys. Each key names the kind of draw and the parameters listed here. The incidence mechanism is iid, spatial, or Poisson, and the iid configuration, which has no ρ_X, uses 0 in its place. k indexes the incidence surface and d the design. A draw is shared by every scenario whose key parameters match its own.

Draw	Key parameters	Shared by
Incidence surface $\mathbf{X}_k$	Incidence mechanism, ρ_X, k	Every block, design, and value of τ of the configuration
The $J = 25$ assignments of design d on surface k	Incidence mechanism, ρ_X, neighbor type, ρ, γ, spillover regime, k, d	All five values of τ and both estimators
The 250 noise vectors of a block	Incidence mechanism, ρ_X, neighbor type, ρ, γ, spillover regime	All eight designs, all five values of τ, and both estimators

Monte Carlo structure and checkpoints. Within a scenario, fit (k, j), with $k = 1, \dots, 10$ and $j = 1, \dots, 25$, uses surface $\mathbf{X}_k$, assignment $\mathbf{Z}_{kj}$, and noise vector ε_{kj}, the (k, j) column of the block's 100×250 noise matrix (see Section 2.5). The unit of computation is a combination of incidence configuration, neighbor type, and ρ: 40 units, each covering 4 values of γ, 2 spillover regimes, 8 designs, 5 values of τ, 250 fits, and 2 estimators. The units ran in parallel, and the run was set to stop if any unit failed. Each unit's results are saved together with a record of the parameter settings, the simulation code, and the software versions that produced them. Saved results are reused only if all of these match the current run, so results from different code or settings are never combined.

Scenario metrics. For one scenario and estimator, let $f = 1, \dots, n$ index the valid fits, those with a finite estimate and standard error (here every fit was valid, so $n = 250$). Let $L_f, U_f = \hat{\tau}_f \mp t_{0.975,\, N-p}\, \widehat{\mathrm{SE}}_f \sqrt{N/(N-p)}$, with $N = 100$ clusters and p as defined in Section 2 (the Wald limits replace the multiplier by $z_{0.975} = \Phi^{-1}(0.975) \approx 1.96$), and let $\bar{\hat{\tau}} = n^{-1} \sum_f \hat{\tau}_f$. Then

$$\mathrm{Bias} = \frac{1}{n} \sum_{f=1}^{n} (\hat{\tau}_f - \tau), \qquad \mathrm{SD} = \left\{ \frac{1}{n-1} \sum_{f=1}^{n} \left(\hat{\tau}_f - \bar{\hat{\tau}} \right)^2 \right\}^{1/2}, \qquad \mathrm{MSE} = \frac{1}{n} \sum_{f=1}^{n} (\hat{\tau}_f - \tau)^2,$$

$$\text{Coverage} = \frac{1}{n}\sum_{f=1}^{n} \mathbb{I}\{L_f \le \tau \le U_f\}, \qquad \text{Power} = \frac{1}{n}\sum_{f=1}^{n} \mathbb{I}\{L_f > 0\},$$

so that $\text{MSE} = \text{Bias}^2 + (n-1)\,\text{SD}^2/n$.

Surface-level standard errors. For $m \in \{\text{Bias}, \text{MSE}, \text{Coverage}, \text{Power}\}$, let m_k be the same formula applied to the valid fits from surface k (here all 25). With $K = 10$ and $s(a_1, \dots, a_K) = \{(K-1)^{-1}\sum_k (a_k - \bar{a})^2\}^{1/2}$ the sample standard deviation,

$$\text{SE}(m) = \frac{s(m_1, \dots, m_K)}{\sqrt{K}}, \qquad m \pm t_{0.975,\,K-1}\,\text{SE}(m).$$

Because each surface contributes 25 fits, $m = K^{-1}\sum_k m_k$. For two designs d and d' in the same block at the same τ, the difference is paired at the surface level: with $\Delta_k = m_{d,k} - m_{d',k}$,

$$\text{SE}(m_d - m_{d'}) = \frac{s(\Delta_1, \dots, \Delta_K)}{\sqrt{K}},$$

with the same $t_{0.975,\,K-1}$ interval.

Standard errors pooled over configurations. For one design, neighbor type, and value of τ, let $\mathcal{B}_c$ be the 32 blocks of configuration c and $m_{b,k}$ the surface-k metric in block b. The configuration-by-surface means and the pooled metric are

$$\bar{m}_{c,k} = \frac{1}{32}\sum_{b \in \mathcal{B}_c} m_{b,k}, \qquad \bar{m} = \frac{1}{50}\sum_{c=1}^{5}\sum_{k=1}^{10} \bar{m}_{c,k},$$

where $\bar{m}$ equals the mean of the metric over the 160 scenarios, and

$$\text{SE}(\bar{m}) = \frac{s(\{\bar{m}_{c,k}\})}{\sqrt{50}},$$

with s taken over the 50 values $\bar{m}_{c,k}$. These are the standard errors in Table 2. For two designs d and d' adjacent in the mean-MSE order (Section 3.1), let $D_{c,k} = \bar{m}_{d,c,k} - \bar{m}_{d',c,k}$ for $m = \text{MSE}$.

The interval for the mean difference is $\bar{D} \pm t_{0.975,\,49}\, s(\{D_{c,k}\})/\sqrt{50}$, and the Wilcoxon signed-rank test, with the normal approximation, is applied to the 50 values $D_{c,k}$.

A3. Supplementary Statistical Comparisons

Below are the pairwise test results and two figures behind results stated in the body of this chapter.


Pairwise tests under queen contiguity. With SRS as a seventh member, the four pairs that Nemenyi comparisons did not separate were Balanced Quartiles against SRS ($p = 1.00$), 2×2 Blocking against High Incidence Focus ($p = 0.32$) and Checkerboard ($p = 0.39$), and Checkerboard against High Incidence Focus ($p = 1.00$). We also compared designs adjacent in the six-design mean-MSE order over the 50 independent configuration-by-surface units. The mean paired differences in MSE, with t_{49} 95% intervals, were -0.040 (-0.043, -0.037) for Incidence-Guided Saturation against Balanced Quartiles, -0.029 (-0.033, -0.026) for Balanced Quartiles against Isolation Buffer, -0.085 (-0.095, -0.075) for Isolation Buffer against High Incidence Focus, -0.074 (-0.086, -0.062) for High Incidence Focus against 2×2 Blocking, and -0.768 (-0.789, -0.746) for 2×2 Blocking against Checkerboard, with Wilcoxon $p \leq 4.9 \times 10^{-9}$ in every case. The better design of each pair had the lower MSE in all 50 units, except High Incidence Focus against 2×2 Blocking, where it did so in 48 (96%). This test follows the mean-MSE order, and it separated High Incidence Focus from 2×2 Blocking where the Nemenyi comparison of within-block ranks did not. It did so because each unit's MSE averages over both spillover regimes, and in that average the control-only losses of 2×2 Blocking outweigh its both-arms wins.

Pairwise tests under rook contiguity. Nemenyi comparisons, with SRS as a seventh member, separated 17 of 21 pairs. The four they did not separate were Incidence-Guided Saturation against Balanced Quartiles ($p = 0.66$) and SRS ($p = 0.14$), Balanced Quartiles against SRS ($p = 0.97$), and 2×2 Blocking against Isolation Buffer ($p = 1.00$). Holm-adjusted Wilcoxon


tests separated every pair except 2×2 Blocking against Isolation Buffer and Balanced Quartiles against SRS (both $p = 0.21$). In the surface-level comparison, Incidence-Guided Saturation had a lower MSE than Balanced Quartiles in 48 of the 50 units (mean difference -0.012; -0.014, -0.010; Wilcoxon $p = 9.9 \times 10^{-10}$). 2×2 Blocking and Isolation Buffer were close: 2×2 Blocking had the lower MSE in 36 of the 50 units (72%; mean difference -0.005; -0.008, -0.002; Wilcoxon $p = 0.0027$). Isolation Buffer, however, had the slightly better average rank (4.21 against 4.33), and the two designs traded places in mean MSE at $\tau = 3$. Every other adjacent pair differed in all 50 units. Within single incidence configurations, rook coverage was between 0.944 and 0.954 for every design except Checkerboard, whose coverage was between 0.155 and 0.165.

Figure 12 gives the Nemenyi critical-difference diagrams for the comparison of the six designs and SRS at $\tau = 1$, whose results are reported in Section 3.1 and Section 3.8. Each design is placed at its average within-block MSE rank among the six designs and SRS over the 160 blocks of its neighbor type. The red arrow shows the critical difference, 0.712 at $\alpha = 0.05$. Under queen contiguity, gray bars join Balanced Quartiles with SRS, and 2×2 Blocking with Checkerboard and High Incidence Focus. Under rook contiguity, they join Incidence-Guided Saturation, Balanced Quartiles and SRS, and Isolation Buffer with 2×2 Blocking. The rook diagram includes Checkerboard, for which τ is not identified, with its estimates kept and flagged.

Across the five values of τ, Figure 13 gives the coverage of each design, as summarized in Section 3.5. The shaded bands show ± 1 times the average of the scenario-level Monte Carlo standard errors of coverage. They describe the precision of a single scenario's coverage, not of the plotted average. The legend lists the designs in order of pooled mean MSE at $\tau = 1$ for the neighbor type of the panel (Table 2). The vertical axis runs from 0 to 1, so lines close to 0.95 overlap: all six under queen contiguity, between 0.946 and 0.950, and all but Checkerboard under rook contiguity, between 0.947 and 0.952. The lowest line under rook contiguity, which




(a) Queen contiguity (primary)




(b) Rook contiguity (sensitivity)

Figure 12: Nemenyi critical-difference diagrams for the six designs and simple random sampling (SRS) at $\tau = 1$, pooled over the five incidence configurations. Designs are placed at their average within-block MSE rank, given in parentheses (1 = lowest MSE). Gray bars join designs that the Nemenyi comparisons did not separate.

the legend does not mark, is Checkerboard, for which τ is not identified. The five values of τ share their assignments and noise.



(a) Queen contiguity (primary)



(b) Rook contiguity (sensitivity)

Figure 13: Coverage of the 95% confidence intervals by design across $\tau \in \{0.8, 1.0, 1.5, 2.0, 3.0\}$, pooled over the five incidence configurations. Each point averages the 160 scenarios of one design at one value of τ. The dashed red line marks the nominal 0.95 level, and the gray dashed line marks the mean coverage of simple random sampling.

A4. Additional Sensitivity Tables

Section 3.2 discusses mean squared error by level of outcome spatial dependence ρ (Table 14) and by level of spillover magnitude γ (Table 16). Checkerboard's coverage by level of ρ under

each neighbor type (Table 15) is discussed in Section 3.8.

Table 14: Mean squared error by design across the four levels of outcome spatial dependence ρ, under queen contiguity at $\tau = 1$, pooled over the five incidence configurations. Each entry averages 40 scenarios (5 incidence configurations $\times$ 4 values of $\gamma \times 2$ spillover regimes). Rows are ordered by pooled mean MSE under queen contiguity (Table 2).

Design	$\rho = 0$	$\rho = 0.01$	$\rho = 0.20$	$\rho = 0.50$
Incidence-Guided Saturation	0.090	0.087	0.093	0.093
Balanced Quartiles	0.129	0.129	0.132	0.133
Isolation Buffer	0.161	0.157	0.158	0.165
High Incidence Focus	0.243	0.242	0.249	0.248
2×2 Blocking	0.318	0.320	0.314	0.324
Checkerboard	1.095	1.077	1.084	1.092

Table 15: Checkerboard's 95% confidence interval coverage across the four levels of outcome spatial dependence ρ at $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity), pooled over the five incidence configurations. Each entry averages 40 scenarios (5 incidence configurations $\times$ 4 values of $\gamma \times 2$ spillover regimes). Under rook contiguity, τ is not identified for Checkerboard. Its estimates are kept and flagged. The nominal level is 0.95.

Neighbor type	$\rho = 0$	$\rho = 0.01$	$\rho = 0.20$	$\rho = 0.50$
Queen	0.950	0.952	0.949	0.949
Rook	0.171	0.168	0.161	0.146

Table 16: Mean squared error by design across the four levels of spillover magnitude γ at $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity), pooled over the five incidence configurations. Each entry averages 40 scenarios (5 incidence configurations $\times$ 4 values of ρ $\times$ 2 spillover regimes). Rows in both panels are ordered by pooled mean MSE under queen contiguity (Table 2). Under rook contiguity, τ is not identified for Checkerboard. Its estimates are kept and flagged.

Design	$\gamma = 0.5$	$\gamma = 0.6$	$\gamma = 0.7$	$\gamma = 0.8$
Queen contiguity				
Incidence-Guided Saturation	0.092	0.089	0.092	0.089
Balanced Quartiles	0.132	0.128	0.132	0.131
Isolation Buffer	0.159	0.163	0.160	0.159
High Incidence Focus	0.244	0.249	0.248	0.241
2×2 Blocking	0.312	0.314	0.328	0.323
Checkerboard	1.108	1.052	1.086	1.101
Rook contiguity				
Incidence-Guided Saturation	0.069	0.072	0.075	0.072
Balanced Quartiles	0.083	0.085	0.083	0.083
Isolation Buffer	0.131	0.133	0.134	0.133
High Incidence Focus	0.207	0.209	0.205	0.203
2×2 Blocking	0.129	0.129	0.127	0.128
Checkerboard (flagged)	0.295	0.403	0.538	0.684

A5. Coverage, Bias–Variance and Rook Contiguity Figures

Two queen-contiguity figures summarized in the Results come first: the coverage of each design (Figure 14) and the decomposition of MSE into squared bias and variance for one incidence configuration (Figure 15). The rook-contiguity versions of these two figures and of Figure 2 follow, as described in Section 3.8. Each rook figure has the layout of its queen counterpart, with the designs ordered for rook contiguity. Under rook contiguity, τ is not identified for Checkerboard ($\mathbf{WZ} = \mathbf{1} - \mathbf{Z}$). Its estimates are kept and flagged.




Figure 14: Coverage of the 95% confidence intervals by design at $\tau = 1$, under queen contiguity. Each box summarizes the coverage of the 160 scenarios of one design (5 incidence configurations $\times$ 4 values of ρ $\times$ 4 values of γ $\times$ 2 spillover regimes), each estimated from 250 fits. Designs are ordered by median coverage, not by MSE. The dashed red line marks the nominal 0.95 level, and the gray dotted line the median coverage of simple random sampling. Figure 17 shows rook contiguity.

Figure 16 corresponds to Figure 2.

In Figure 17, the rook version of Figure 14, every design except Checkerboard has coverage close to the nominal level. Checkerboard's coverage, 0.162 pooled over the five incidence configurations




Figure 15: Decomposition of mean squared error into squared bias and variance by design at $\tau = 1$ for one incidence configuration, Poisson with $\rho_X = 0.20$, under queen contiguity. For each design, the two stacked components are the squared bias and the variance (SD^2) of $\hat{\tau}$, each averaged over the 32 scenarios of that configuration (4 values of $\rho \times 4$ values of $\gamma \times 2$ spillover regimes). Designs are ordered by pooled mean MSE (Table 2). The gray dashed line marks the MSE of simple random sampling (SRS) in the same configuration. Figure 18 shows rook contiguity.

(Table 2), is far below it.

Nearly all of Checkerboard's MSE in Figure 18, the rook version of Figure 15, is squared bias, because its coefficient on $\mathbf{Z}$ estimates $\tau - \gamma$ (Section 2).




Figure 16: Mean squared error of the oracle estimate of τ by design at $\tau = 1$, under rook contiguity, with the layout of Figure 2. Checkerboard is flagged (τ not identified).




Figure 17: Coverage of the 95% confidence intervals by design at $\tau = 1$, under rook contiguity, with the layout of Figure 14. Checkerboard is flagged (τ not identified).




Figure 18: Squared bias and variance of $\hat{\tau}$ by design at $\tau = 1$ for the Poisson configuration with $\rho_X = 0.20$, under rook contiguity, with the layout of Figure 15. Checkerboard is flagged (τ not identified).

A6. Oracle and Non-Oracle Estimates

Table 17 gives the mean squared error, bias, and coverage of the oracle and non-oracle models for each of the six designs, as summarized in Section 3.9.

Table 17: Oracle and non-oracle estimates of τ by design at $\tau = 1$, under queen contiguity (primary) and rook contiguity (sensitivity), pooled over the five incidence configurations. Each entry averages the 160 scenarios of one design and neighbor type. The oracle model has the covariates $\mathbf{Z}$, Spill, and $\mathbf{X}_k$; the non-oracle model omits Spill. Rows in both panels are in order of oracle MSE under queen contiguity. Under rook contiguity, τ is not identified for Checkerboard ($\mathbf{WZ} = \mathbf{1} - \mathbf{Z}$). Its estimates are kept and flagged, and the two models coincide.

	Oracle			Non-oracle		
Design	MSE	Bias	Coverage	MSE	Bias	Coverage
Queen contiguity (primary)						
Incidence-Guided Saturation	0.091	0.032	0.947	0.087	−0.123	0.825
Balanced Quartiles	0.131	0.017	0.946	0.098	−0.176	0.786
Isolation Buffer	0.160	0.003	0.949	0.091	−0.175	0.892
High Incidence Focus	0.245	0.031	0.948	0.219	−0.180	0.907
2×2 Blocking	0.319	0.010	0.948	0.121	−0.244	0.727
Checkerboard	1.087	0.001	0.950	0.108	−0.206	0.758
Rook contiguity (sensitivity)						
Incidence-Guided Saturation	0.072	0.018	0.952	0.086	−0.121	0.825
Balanced Quartiles	0.084	0.008	0.948	0.097	−0.176	0.789
Isolation Buffer	0.133	0.003	0.950	0.211	−0.400	0.536
High Incidence Focus	0.206	0.018	0.948	0.223	−0.192	0.903
2×2 Blocking	0.128	0.004	0.948	0.128	−0.257	0.710
Checkerboard (flagged)	0.480	−0.652	0.162	0.480	−0.652	0.162

A7. Technical Notes

This section explains why the bias of Incidence-Guided Saturation and the coverage of Checkerboard under rook contiguity both grow with τ, as reported in the body of this chapter. It closes with block-level detail for the results across τ. The stored results keep neither $\hat{\rho}$ nor the standard error of each fit, so we re-ran every block for the six designs, both neighbor types, and all five values of τ, 2.4 million fits of the oracle model, recording $\hat{\rho}$ and the standard error. The re-run reproduced the stored results in all 9,600 scenarios. Numbers below that involve $\hat{\rho}$, the standard error, or the terms of Equation 4 come from this re-run. The others come from the stored results.

Identification Diagnostics

Two combinations of design and neighbor type weaken or remove the information that separates τ from the spillover term. Under rook contiguity, Checkerboard gives $\mathbf{WZ} = \mathbf{1} - \mathbf{Z}$ exactly, because every neighbor of a treated cluster is a control and every neighbor of a control is treated. Both spillover covariates then equal $\gamma(\mathbf{1} - \mathbf{Z})$, a linear combination of the intercept and $\mathbf{Z}$, so τ is not identified: the fitting routine drops the aliased spillover column, and the coefficient on $\mathbf{Z}$ estimates $\tau - \gamma$. Chapter 2 noted the same consequence of exact collinearity between treatment and spillover exposure, $\widehat{\beta} \approx \beta - \psi$ in its notation. The non-oracle model has no spillover column to drop, but its Checkerboard estimates under rook contiguity have the same defect. Under queen contiguity, each of the 64 interior clusters has four treated and four control neighbors, so $\mathbf{WZ} = 1/2$ at every interior cluster. Under the control-only regime the spillover covariate then equals $(\gamma/2)(\mathbf{1} - \mathbf{Z})$ at those clusters, a linear combination of the intercept and $\mathbf{Z}$, and only the 36 clusters on the grid boundary carry information that separates it from the intercept and $\mathbf{Z}$. As a result, τ is identified, but imprecisely. In the both-arms regime, the spillover covariate is the constant $\gamma/2$ at interior clusters, confounded with the intercept but not with $\mathbf{Z}$. Isolation Buffer under rook contiguity can also, rarely, draw exactly the checkerboard pattern, a maximal independent set that equals one color class of the grid. This happened in 4 of its 40,000 rook draws and affected one fit in each of 20 scenarios, 4 at each value of τ. We flag every fit in which the fitting routine reports an aliased column and every scenario in which some draw has $\text{rank}([\mathbf{1}, \mathbf{Z}, \mathbf{WZ}]) < 3$. Aliased estimates are kept in all summaries. In the exhibits, we flag Checkerboard under rook contiguity, where every fit is aliased. The Isolation Buffer scenarios, each with one aliased fit among its 250, are noted here and carry no flag in the exhibits.

Estimation Error and Its Dependence on τ

For one fit (k, j), write $\mathbf{Y}$, $\mathbf{Z}$, and ε for $\mathbf{Y}_{kj}$, $\mathbf{Z}_{kj}$, and ε_{kj} (Simulation design, resampling, and metrics). Let $\mathbf{V} = [\mathbf{1}, \mathbf{Z}, \mathbf{S}(\mathbf{Z}), \mathbf{X}_k]$ be the 100×4 covariate matrix of the oracle model, so

that Equation 1 reads $(\mathbf{I}-\rho\mathbf{W})\mathbf{Y}=\mathbf{V}\theta+\varepsilon$ with $\theta=(0,\tau,1,\beta)^{\top}$. Let $\mathbf{A}=(\mathbf{I}-\rho\mathbf{W})^{-1}$ and $\mathbf{V}^{+}=(\mathbf{V}^{\top}\mathbf{V})^{-1}\mathbf{V}^{\top}$, and for a vector $\mathbf{v}$ write $[\mathbf{V}^{+}\mathbf{v}]_{Z}$ for the coefficient on $\mathbf{Z}$ when $\mathbf{v}$ is regressed on the columns of $\mathbf{V}$ by least squares. Given $\hat{\rho}$, the estimated coefficients are $\mathbf{V}^{+}(\mathbf{I}-\hat{\rho}\mathbf{W})\mathbf{Y}$ (Section 2.4). Because $(\mathbf{I}-\hat{\rho}\mathbf{W})\mathbf{Y}=\mathbf{V}\theta+\varepsilon+(\rho-\hat{\rho})\mathbf{W}\mathbf{Y}$ and $\mathbf{W}\mathbf{Y}=\mathbf{W}\mathbf{A}(\mathbf{V}\theta+\varepsilon)$,

$$\hat{\tau}-\tau=[\mathbf{V}^{+}\varepsilon]_{Z}+(\rho-\hat{\rho})\,h+\tau(\rho-\hat{\rho})\,g, \tag{4}$$

where

$$g=[\mathbf{V}^{+}\mathbf{W}\mathbf{A}\mathbf{Z}]_{Z}, \qquad h=[\mathbf{V}^{+}\mathbf{W}\mathbf{A}\{\mathbf{S}(\mathbf{Z})+\beta\mathbf{X}_{k}+\varepsilon\}]_{Z}.$$

The first term has mean zero given $\mathbf{Z}$ and $\mathbf{X}_{k}$. The last term has a factor of τ. It is present exactly when $g\neq 0$, where g is the coefficient on $\mathbf{Z}$ when the lagged treatment $\mathbf{W}\mathbf{A}\mathbf{Z}=\mathbf{W}\mathbf{Z}+\rho\mathbf{W}^{2}\mathbf{Z}+\rho^{2}\mathbf{W}^{3}\mathbf{Z}+\cdots$ is regressed on the model's own covariates. The sign and size of the last term are set by the error in $\hat{\rho}$. The concentrated likelihood depends on $\mathbf{Y}$ only through the residual sum of squares of $(\mathbf{I}-\tilde{\rho}\mathbf{W})\mathbf{Y}$ on $\mathbf{V}$, and the part of that residual that involves τ is $\tau(\rho-\tilde{\rho})$ times the residual of $\mathbf{W}\mathbf{A}\mathbf{Z}$ on $\mathbf{V}$. If $\mathbf{W}\mathbf{A}\mathbf{Z}$ lies in the column space of $\mathbf{V}$, that part vanishes for every $\tilde{\rho}$, so $\hat{\rho}$ is the same at every value of τ. If, in addition, $g=0$, then $\hat{\tau}-\tau$ is the same at every value of τ. Equation 4 held on every re-run fit, with a largest residual of 4.2×10^{-13}. For Checkerboard under rook contiguity, it held in the reduced form given below.

For designs whose treated clusters have treated neighbors, the last term gives a small positive bias that grows with τ. Under queen contiguity, pooled over the 160 blocks, the bias of Incidence-Guided Saturation rose from 0.029 at $\tau=0.8$ to 0.047 at $\tau=3$ (Section 3.5), while that of Isolation Buffer stayed between 0.002 and 0.004. Almost all of the rise comes from the last term of Equation 4. In our fits, $\hat{\rho}$ was biased downward by about 0.06 on average (for Incidence-Guided Saturation, by 0.071 at $\tau=0.8$ and 0.054 at $\tau=3$). We observed this downward bias in these simulations but did not derive it or check it against a published finite-sample result. With $\rho-\hat{\rho}$ positive on average, the last term is positive and grows with τ for any design with $g>0$. For

Incidence-Guided Saturation, g averaged 0.371 over the queen fits, and the last term contributed 0.021 of the bias at $\tau = 0.8$ and 0.043 at $\tau = 3$. The first term contributed 0.001 at both values, and the second 0.007 and 0.002. For Isolation Buffer, g averaged 0.020, and the last term contributed 0.001 and 0.004.

Most of the difference in g comes from the control-only regime. Under the both-arms regime with $\rho = 0$, the lagged treatment is $\mathbf{WZ} = \mathbf{S}(\mathbf{Z})/\gamma$, one of the covariates, so $g = 0$ for every design. Under the control-only regime, $\mathbf{WZ} = \mathbf{S}(\mathbf{Z})/\gamma + \mathbf{Z} \circ \mathbf{WZ}$, and at $\rho = 0$, g is close to the average share of treated neighbors among treated clusters. That share is 0.57 for Incidence-Guided Saturation, whose treated clusters are concentrated in the high-saturation quadrants, and exactly 0 for Isolation Buffer, whose treated clusters have no treated neighbors. For Isolation Buffer, $\mathbf{Z} \circ \mathbf{WZ} = \mathbf{0}$, so the two regimes define the same spillover covariate and the same g, which is 0 at $\rho = 0$ and about 0.06 at $\rho = 0.5$. At $\rho = 0$, its $\hat{\rho}$ and its estimation error were the same at every value of τ, up to the optimizer's tolerance.

The same term explains why the control-only MSE of Incidence-Guided Saturation rose from 0.131 at $\tau = 0.8$ to 0.182 at $\tau = 3$ while that of Isolation Buffer did not. Under that regime, averaged over the 80 queen blocks, the variance of the last term of Equation 4 rose from 0.008 to 0.061 for Incidence-Guided Saturation, while the variance of the rest of the error changed little (0.119 and 0.115). The variance of the last term grew more slowly than τ^2 because $\hat{\rho}$ became less variable as τ grew. For Isolation Buffer, the variance of the last term stayed below 0.0002. The rise in bias slowed at larger values of τ for a related reason: the part of the likelihood that involves τ sharpens the likelihood around the true ρ as τ grows, so the downward bias of $\hat{\rho}$ shrank.

The decomposition also explains why the coverage of Checkerboard under rook contiguity rose with τ, from 0.150 at $\tau = 0.8$ to 0.464 at $\tau = 3$ (Section 3.5), although its coefficient on $\mathbf{Z}$ estimates $\tau - \gamma$ at every value of τ. For this design $\mathbf{WZ} = \mathbf{1} - \mathbf{Z}$, and because $\mathbf{W}$ is row-

standardized, $\mathbf{W}^2\mathbf{Z} = \mathbf{W}(\mathbf{1}-\mathbf{Z}) = \mathbf{Z}$. The powers of $\mathbf{W}$ applied to $\mathbf{Z}$ therefore alternate between $\mathbf{1}-\mathbf{Z}$ and $\mathbf{Z}$, and $\mathbf{WAZ} = \{(\mathbf{1}-\mathbf{Z}) + \rho\mathbf{Z}\}/(1-\rho^2)$ lies in the span of the intercept and $\mathbf{Z}$. The derivation of Equation 4 applies with the aliased spillover column dropped, $\mathbf{V} = [\mathbf{1}, \mathbf{Z}, \mathbf{X}_k]$ and $\theta = (\gamma, \tau-\gamma, \beta)^\top$, so that $\tau-\gamma$ takes the place of τ, and $g = -1/(1+\rho)$. Two consequences follow: $\hat{\rho}$ is the same at every value of τ, and

$$\hat{\tau} - \tau = -\gamma + \delta + (\tau - \gamma)\,\frac{\hat{\rho} - \rho}{1+\rho},$$

where δ collects the first two terms of that decomposition and, like $\hat{\rho}$, does not depend on τ. The error in $\hat{\rho}$ is therefore multiplied by $\tau-\gamma$, which grows with τ. The mean standard deviation of $\hat{\tau}$ rose from 0.202 at $\tau = 0.8$ to 0.327 at $\tau = 3$, and the standard error tracked it, rising on average from 0.199 to 0.322. With the bias held near $-\gamma$, wider intervals covered τ more often. The rise was largest at $\rho = 0$ (coverage 0.157 to 0.562) and smallest at $\rho = 0.5$ (0.142 to 0.284), consistent with the factor $1/(1+\rho)$. The same term raised the MSE from 0.477 to 0.567. About three quarters of that increase was variance, $(n-1)\mathrm{SD}^2/n$ averaged over scenarios (Appendix A2), which rose from 0.041 to 0.109. The other quarter was squared bias, which rose from 0.436 to 0.458 because $\hat{\rho}$ was biased slightly downward, moving the mean bias from -0.650 to -0.667.

Block-level detail. Under queen contiguity, the average rank of Incidence-Guided Saturation among the six designs rose from 1.41 at $\tau = 0.8$ to 1.85 at $\tau = 3$, while that of Balanced Quartiles stayed between 2.13 and 2.14 and that of Isolation Buffer fell from 3.71 to 3.31. Incidence-Guided Saturation had a lower MSE than Balanced Quartiles in 103, 102, 102, 102, and 101 of the 160 blocks at $\tau = 0.8$, 1, 1.5, 2, and 3, and a lower MSE than Isolation Buffer in 75, 73, 56, 40, and 12 of the 80 control-only blocks. Its worst case across blocks was the lowest of the six designs at $\tau \leq 1.5$, but at $\tau = 2$ and $\tau = 3$ that of Isolation Buffer was lower (0.207 against 0.210, and 0.208 against 0.238). Under rook contiguity, at $\tau = 3$, Incidence-Guided Saturation had a lower MSE than Isolation Buffer in 47 of the 80 control-only blocks, and its worst case across rook

blocks was the lowest of the six designs at every value of τ except $\tau = 3$, where that of Isolation Buffer was lower (0.173 against 0.174). The coverage of rook Checkerboard was 0.150, 0.162, 0.212, 0.286, and 0.464 at $\tau = 0.8$, 1, 1.5, 2, and 3.

A8. Observed-Incidence Application Detail

The primary application numbers come from the aggregate performance and allocation-risk summaries of the main run and of the separate tail refinement. Annual tables average the six queen parameter pairs equally, without pooled Monte Carlo intervals. Each random draw used a fixed, reproducible seed. An independent check recomputed performance from the stored fits and verified the annual treatment budgets, the regional orderings, and the allocations and outcomes reused from the main run in the tail refinement. The county death-certificate source data are restricted and not publicly available. We report only 58-cluster summaries.

For randomized designs, the prespecified refinement schedule allowed $J = 100, 200, 400$ and $R = 100, 200, 400, 1000, 2000, 4000$. Whichever source of Monte Carlo error, allocations or outcomes, contributed more to the shortfall from the precision targets was extended. All randomized designs met the targets at $J = 100$ and $R = 100$. For designs with a single possible assignment, only outcomes were extended. If an allocation occurs n_a times among J draws, its risk estimate enters the mean with weight n_a/J. The variance due to outcome noise therefore involves squared weights $(n_a/J)^2$, not n_a/J^2 as if duplicate estimates were independent. Bias and coverage use the same accounting of frequencies and covariances. The overall precision includes both variation across assignments and outcome noise given an assignment. A design whose sampled assignments happened to coincide is distinguished from one with only one possible assignment. Approximate Monte Carlo standard errors of setting-specific differences between designs treat the designs' random draws as independent, whereas averages across settings or models do not assume that shared allocations are independent. Settings with the same set of possible assignments shared their simulations, with annual treatment counts and population

shares recalculated.

We report the estimated variance of risk both raw and with the contribution of outcome Monte Carlo noise subtracted. Signed corrected estimates are retained without truncation at zero. None is negative in the NC refinement. Quantiles and worst-decile means use noisy estimated conditional risks. To avoid selection bias, worst-decile assignments were identified with one half of the simulated outcomes and evaluated with the other half, and the roles of the two halves were then reversed. The Jaccard overlap of the two worst deciles describes sampled tail membership, not a confidence interval or population tail probability. For a design with only one possible assignment, an overlap of one is uninformative.

Design adaptations. Before simulation, we checked the 58-cluster row-standardized contiguity matrix $\mathbf{W}$, its binary adjacency and its row order against the boundary geometry. On the NC map, Checkerboard visits clusters by decreasing degree, chooses the arm that conflicts least with assigned neighbors, breaks equal conflicts toward control, and complements the assignment if more than half are treated. In Balanced Quartiles and Balanced Halves, odd-size strata receive their necessary extra treatments at random. In Balanced Halves, one half receives 14 treatments and the other 15, with the extra-treatment half chosen randomly. The four-region partition used by both saturation designs was selected from 250 candidates generated by a geographic k-means procedure on standardized projected coordinates, by compactness and balance in reference population, cluster count and county count, without consulting outcomes. Reference population is pooled person-years divided by four. Incidence-Guided Saturation first ranks clusters by annual per-capita rates, averages their ranks equally within each region, ranks those four means, and assigns 80/60/40/20% from highest to lowest. Regional ties are broken randomly per allocation, and local treatment counts are rounded under the retained design rules. Per-capita cluster rates already account for population size. Regional mean ranks weight clusters equally, whereas pooled regional rates, deaths divided by population, weight larger clusters more heavily.

Mean raw rates and pooled regional rates are evaluated as prespecified sensitivities rather than chosen by performance. The grid rule averages $\mathbf{X}$ directly. Mean ranks align with its rank-scaled Poisson cases but are a deliberate adaptation for the application, not the exact rule used for continuous grid incidence. The 14 groups used by 2×2 Blocking are formed once per year by k-means on standardized projected coordinates, incidence ranks and log(1+population), then held fixed, and contain one to eight clusters. Half of each group, rounded, is treated at random, and the single-cluster group of each year remains control, because half of one cluster rounds to zero, so the yearly total treatments for 2×2 Blocking are 28, 31, 27 and 29. The groups are not literal square blocks.

The fixed regional criterion is $C = 3s_P + 1.5s_K + 1.5s_D + c/d_{\max}$, where s_P, s_K and s_D are the standard deviations of regional population, cluster and county shares. Here c averages within-region distances to regional centers and $d_{\max}$ is the maximum pairwise distance between the projected cluster coordinates. Table 18 gives the regional ordering under the primary and alternative summaries, recorded before performance was evaluated.

Table 18: Regional ordering from highest to lowest summary, using the fixed region IDs in Figure 19. Primary mean ranks weight clusters equally. Pooled regional rates weight cluster rates by population.

Year	Mean cluster rank	Mean cluster rate	Pooled regional rate
2018	2,1,3,4	2,4,1,3	4,3,2,1
2019	4,2,3,1	4,2,3,1	4,3,1,2
2020	2,4,1,3	2,4,1,3	4,3,2,1
2021	2,1,4,3	2,4,1,3	4,3,1,2

Allocation-risk estimates for the refined setting $\rho = 0.5$, $\gamma = 0.8$ (Figure 22) support the downside comparison in the body.

Table 19 gives MSE, bias and coverage for every design in every year. Budgets are in Table 7. More granular setting-specific results, precision components, residual treatment information and warning and failure records are kept as aggregate output tables. These records were checked, so the absence of warnings and failures is a verified result.




Figure 19: Fixed four-region partition used by both saturation designs in all years, chosen from 250 geographic candidates before outcome evaluation.




Figure 20: One illustrative queen assignment from each application strategy using 2018 observed incidence and fixed geography. These sampled assignments illustrate the adaptations and were not selected by observed performance.

For Incidence-Guided Saturation, Table 20 reports the matched annual mean-MSE ratios. Rook means use only the four extreme combinations of ρ and γ shared with the primary analysis. Means for the matched baseline sensitivity and the regional summaries use the six queen pairs. These are matched contrasts, not ratios of unmatched pooled analyses.




Figure 21: Primary queen setting-specific mean MSE ratios to year-matched SRS. Teal cells have lower MSE than SRS and red cells higher. Setting-specific Monte Carlo errors are kept in the aggregate output tables and not shown here. Parameters and spillover regimes are shown separately, and neighbor definitions are not pooled.

A9. Participation, Power and Sensitivity Analyses for the NC Application

Here we give the detail behind Section 4.8 and the sensitivity analyses of the application. All numbers come from aggregate summaries of runs that wrote to their own output folders, each



Figure 22: Allocation-specific conditional MSE in the refined primary queen setting $\rho = 0.5, \gamma = 0.8$, by year and spillover regime. Mean MSE, the estimated 90th percentile of allocation-specific MSE and the estimated worst-decile mean summarize the same $J = 100$ sampled assignments, with at least 400 independent outcomes per assignment of a randomized design or 1,000 for designs with a single possible assignment. These tail estimates rest on a finite number of outcomes and are descriptive, with uncertain membership. They are not quantiles of realized errors or a fresh allocation confirmation.

with a manifest of parameters, code hashes and package versions. These runs left the production application files unchanged. Unless stated otherwise, results use random volunteering, $\beta = 0$,

Table 19: Primary queen application performance by design and planning year. Each entry averages the six ρ/γ pairs of one spillover regime with equal weight. Coverage is that of the corrected t interval. Checkerboard, Saturation Quadrants, Isolation Buffer and SRS use the same simulations in every year, because annual incidence enters neither their allocation nor the outcome model, so their rows repeat and are not independent annual confirmation.

		Both arms			Control only		
Design	Year	MSE	Bias	Coverage	MSE	Bias	Coverage
Checkerboard	2018	0.216	-0.007	0.949	0.920	0.010	0.948
	2019	0.216	-0.007	0.949	0.920	0.010	0.948
	2020	0.216	-0.007	0.949	0.920	0.010	0.948
	2021	0.216	-0.007	0.949	0.920	0.010	0.948
High Incidence Focus	2018	0.072	0.016	0.948	0.214	0.024	0.948
	2019	0.072	0.006	0.951	0.430	0.023	0.945
	2020	0.073	0.009	0.946	0.259	0.033	0.946
	2021	0.070	0.010	0.951	0.353	0.030	0.945
Saturation Quadrants	2018	0.075	0.021	0.949	0.223	0.046	0.941
	2019	0.075	0.021	0.949	0.223	0.046	0.941
	2020	0.075	0.021	0.949	0.223	0.046	0.941
	2021	0.075	0.021	0.949	0.223	0.046	0.941
Isolation Buffer	2018	0.286	0.009	0.947	0.286	0.011	0.947
	2019	0.286	0.009	0.947	0.286	0.011	0.947
	2020	0.286	0.009	0.947	0.286	0.011	0.947
	2021	0.286	0.009	0.947	0.286	0.011	0.947
2×2 Blocking	2018	0.076	0.010	0.948	0.306	0.028	0.944
	2019	0.078	0.014	0.945	0.436	0.031	0.942
	2020	0.078	0.012	0.949	0.318	0.028	0.945
	2021	0.077	0.011	0.947	0.362	0.029	0.943
Balanced Quartiles	2018	0.076	0.017	0.947	0.294	0.031	0.944
	2019	0.076	0.017	0.948	0.306	0.037	0.944
	2020	0.075	0.016	0.947	0.289	0.036	0.943
	2021	0.075	0.018	0.948	0.284	0.035	0.944
Balanced Halves	2018	0.075	0.016	0.948	0.291	0.040	0.945
	2019	0.075	0.017	0.949	0.300	0.036	0.945
	2020	0.075	0.015	0.948	0.306	0.037	0.944
	2021	0.076	0.016	0.946	0.291	0.034	0.944
Incidence-Guided Saturation	2018	0.074	0.017	0.949	0.243	0.046	0.943
	2019	0.076	0.023	0.949	0.216	0.052	0.941
	2020	0.077	0.021	0.947	0.220	0.047	0.942
	2021	0.075	0.020	0.950	0.237	0.045	0.942
Simple Random Sampling	2018	0.076	0.013	0.947	0.308	0.038	0.945
	2019	0.076	0.013	0.947	0.308	0.038	0.945
	2020	0.076	0.013	0.947	0.308	0.038	0.945
	2021	0.076	0.013	0.947	0.308	0.038	0.945

$\kappa = 0.8$ and the corrected t test, and they average the four planning years.

Colleges needed and smallest detectable effect. Table 21 gives, for each strategy, the number of colleges needed for 80% power and the smallest college-level effect detectable with 80% power at 29 and 58 colleges. The number of colleges needed is interpolated monotonically

Table 20: Incidence-Guided Saturation sensitivity MSE divided by matched primary MSE, by year and regime. Baseline adds rank-scaled $\mathbf{X}$ to both generation and fit. Rook uses the matched extreme combinations of ρ and γ. Regional-summary alternatives preserve fixed regions.

Sensitivity	Regime	2018	2019	2020	2021
Baseline / adjusted	Both	1.016	1.030	1.015	1.035
Baseline / adjusted	Control	1.026	1.023	1.042	1.040
Rook contiguity	Both	1.005	0.998	0.985	0.998
Rook contiguity	Control	0.967	0.969	0.971	1.036
Mean regional rate	Both	1.034	1.000	1.000	1.031
Mean regional rate	Control	0.907	1.000	1.000	0.928
Pooled regional rate	Both	1.015	0.979	0.981	1.003
Pooled regional rate	Control	0.962	1.133	1.061	1.030

between the simulated values of N within each year, averaged over years and rounded up to a whole college. Results at $\rho = 0$ differed from those at $\rho = 0.5$ by about two colleges or fewer. Power curves are not always monotone in N: some drops in power between successive values of N are larger than Monte Carlo error, because the participant subsets differ between values of N. We report the dips rather than smooth them.

Table 21: Colleges needed for 80% power and smallest effect detectable with 80% power (MDE, college-level standard deviations), corrected t test, random volunteering, $\rho = 0.5$, spillover $\gamma = 0.8\tau$, mean over the 2018–2021 planning years. > 58: 80% power not reached with all 58 colleges in at least one year. > 2: 80% power not reached at the largest simulated effect, $\tau = 2$.

	Colleges needed		MDE, 29 colleges		MDE, 58 colleges	
Design	Both arms $\tau = 1$	Control only $\tau = 1.5$	Both	Control	Both	Control
Checkerboard	> 58	> 58	1.70	1.86	1.32	> 2
High Incidence Focus	35	30	1.13	1.51	0.76	1.57
Saturation Quadrants	36	28	1.14	1.47	0.76	1.24
Isolation Buffer	> 58	> 58	> 2	> 2	1.50	1.50
2×2 Blocking	37	> 58	1.15	1.63	0.78	1.60
Balanced Quartiles	36	31	1.14	1.50	0.77	1.46
Balanced Halves	36	29	1.13	1.49	0.77	1.46
Incidence-Guided Saturation	36	28	1.13	1.46	0.76	1.25
Simple Random Sampling	36	32	1.14	1.50	0.77	1.45

Interval calibration. We tried several corrections and adopted a method only if its coverage lay between 94.0% and 96.0% for every design and regime. On the stored fits of the main application ($\beta = 0$), the Wald interval covered 92.6% to 93.6% by design and regime. A t reference distribution alone gave 93.2% to 94.1%, a degrees-of-freedom-corrected standard error alone 93.5% to 94.4%, and the two together 94.1% to 94.9%. In a separate run of 500 fits per

Table 22: Power of the corrected t test for an individual-level standardized effect d with simple random sampling, by the number of trained professionals per college (m) and the intraclass correlation coefficient (ICC), with $\sigma_c = \sqrt{\text{ICC} + (1 - \text{ICC})/m}$ and $\tau = d/\sigma_c$. Random volunteering, $\rho = 0.5$, spillover $\gamma = 0.8\tau$, mean over the four planning years.

			Both arms				Control only			
			29 colleges		58 colleges		29 colleges		58 colleges	
m	ICC	σ_c	$d = 0.2$	$d = 0.3$	$d = 0.2$	$d = 0.3$	$d = 0.2$	$d = 0.3$	$d = 0.2$	$d = 0.3$
10	0.01	0.330	0.33	0.62	0.61	0.90	0.22	0.41	0.24	0.45
10	0.05	0.381	0.27	0.51	0.50	0.82	0.18	0.33	0.20	0.36
10	0.10	0.436	0.22	0.41	0.40	0.71	0.15	0.27	0.17	0.30
25	0.01	0.223	0.61	0.91	0.90	1.00	0.41	0.71	0.44	0.74
25	0.05	0.297	0.40	0.71	0.69	0.96	0.26	0.49	0.29	0.53
25	0.10	0.369	0.28	0.53	0.52	0.85	0.19	0.35	0.21	0.38
50	0.01	0.173	0.81	0.98	0.98	1.00	0.59	0.87	0.63	0.89
50	0.05	0.263	0.48	0.80	0.79	0.98	0.31	0.58	0.34	0.62
50	0.10	0.344	0.31	0.59	0.58	0.88	0.21	0.39	0.23	0.42

setting at 58 colleges, parametric percentile bootstrap intervals with 499 replicates covered 90.1% to 93.6%, parametric bootstrap-t intervals 93.2% to 95.8% and profile-likelihood intervals 91.8% to 94.7%. Only the t interval with the corrected standard error met the rule on the stored fits. In the separate 500-fit run it covered 92.8% to 95.8% and narrowly missed the rule there, which every other method also missed. Table 23 shows its size and coverage at each number of participating colleges. Table 24 compares the Wald and corrected intervals for each design in the grid study and the main application.

Table 23: Size and coverage of the Wald and corrected t tests by the number of participating colleges, random volunteering, $\beta = 0$, all designs, regimes, values of ρ and κ, and years. Size is the rejection rate of a true null hypothesis $\tau = 0$ (range over designs). Coverage is at $\tau = 1$, with the range over design-by-regime means in parentheses. All entries are percentages.

Colleges	Wald size	Corrected t size	Wald coverage	Corrected t coverage
15	11.1–12.8	4.4–5.4	87.7	94.9 (94.5–95.6)
20	9.5–10.4	4.7–5.4	89.8	94.8 (94.4–95.3)
25	8.4–9.5	4.7–5.5	90.9	94.8 (94.4–95.2)
29	8.3–8.8	5.0–5.5	91.6	94.8 (94.4–95.1)
30	7.9–8.6	5.0–5.5	91.7	94.7 (94.4–95.0)
35	7.6–8.1	5.1–5.5	92.2	94.7 (94.2–95.1)
40	7.4–7.7	5.2–5.5	92.5	94.7 (94.2–94.9)
45	6.9–7.5	5.0–5.6	92.7	94.7 (94.3–95.2)
50	7.0–7.3	5.2–5.6	92.9	94.6 (94.2–95.1)
58	6.3–7.0	5.0–5.5	93.2	94.6 (94.0–95.1)

Guidance under partial participation. Table 25 gives each strategy's mean MSE relative to

Table 24: Coverage of the 95% Wald interval and the corrected t interval (t reference distribution with a degrees-of-freedom-corrected standard error), the interval reported throughout, for the six designs and SRS. Grid: oracle model at $\tau = 1$, pooled over the five incidence configurations and both spillover regimes (160 scenarios per entry). Application: queen weights, $\beta = 0$, averaged over the four planning years and the six ρ/γ pairs of each regime. Both intervals were computed from the same fits. [a]Under rook contiguity on the grid, τ is not identified for Checkerboard.

	Grid, queen		Grid, rook		NC, both arms		NC, control only	
Design	Wald	t	Wald	t	Wald	t	Wald	t
Incidence-Guided Saturation	0.937	0.947	0.942	0.952	0.935	0.949	0.927	0.942
Balanced Quartiles	0.936	0.946	0.940	0.948	0.933	0.948	0.929	0.944
Isolation Buffer	0.939	0.949	0.939	0.950	0.932	0.947	0.931	0.947
High Incidence Focus	0.938	0.948	0.939	0.948	0.934	0.949	0.931	0.946
2×2 Blocking	0.939	0.948	0.938	0.948	0.932	0.947	0.929	0.944
Checkerboard[a]	0.941	0.950	0.150	0.162	0.936	0.949	0.933	0.948
Simple Random Sampling	0.938	0.948	0.938	0.947	0.932	0.947	0.929	0.945

SRS at $\tau = 1$ for 20, 29, 40 and 58 participating colleges. When colleges with higher incidence were more likely to volunteer, the ratios at 20 and 29 colleges were within 0.02 of 1 for both saturation designs and Balanced Quartiles under either regime, and within 0.03 for Balanced Halves. Checkerboard and Isolation Buffer remained the worst designs. The four saturation regions were rebuilt on the participants with at least two colleges required in every region. Before that requirement was imposed, a region with fewer than two colleges occurred in 1 of the 50 random subsets at 15 colleges and in one incidence-weighted subset at 20 colleges. Imposing it changed the regions of only two distinct participant subsets and changed no ratio in Table 25 by more than 0.01.

Targeting. With all 58 colleges, Incidence-Guided Saturation's mean share of the summed college incidence rates in treated colleges was 51.1%, against 50.4% for Saturation Quadrants, 50.0% for SRS and 62.2% for High Incidence Focus. Its mean share of deaths was 49.2%, against 49.6%, 49.7% and 35.4%. On the grid, the gain of Incidence-Guided Saturation over Saturation Quadrants in treated incidence share averaged 2.1 to 3.1 percentage points across the five incidence configurations, while the treated incidence share of High Incidence Focus itself reached 0.75 to 0.77 by giving up randomization over the whole map. Grid clusters have equal

Table 25: Mean MSE relative to simple random sampling (SRS) at $\tau = 1$ by the number of participating colleges, random volunteering, mean over 16 blocks (year $\times$ ρ $\times$ κ). Below 1 is lower error than SRS.

	Both arms				Control only			
Design	20	29	40	58	20	29	40	58
Checkerboard	1.88	2.18	2.23	2.82	1.18	1.38	1.80	3.10
High Incidence Focus	0.98	0.97	0.96	0.92	0.99	1.00	0.99	1.06
Saturation Quadrants	1.00	0.98	1.00	1.00	0.99	0.96	0.90	0.78
Isolation Buffer	5.92	4.21	3.74	3.87	3.61	2.25	1.51	0.99
2×2 Blocking	1.03	1.01	1.02	1.03	1.08	1.11	1.11	1.18
Balanced Quartiles	1.00	0.99	0.99	1.01	1.00	0.99	0.99	1.02
Balanced Halves	0.99	0.98	0.98	1.00	0.99	0.97	1.01	1.01
Incidence-Guided Saturation	0.99	0.97	1.00	1.00	0.99	0.95	0.91	0.78
Simple Random Sampling	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

populations, so rate share and death share coincide there. Figure 23 shows that the gain rose almost linearly with the spread of the regions' mean incidence ranks, and that the NC regions lie at the low end of that spread.




Figure 23: Gain in treated incidence share from incidence guidance (Incidence-Guided Saturation minus Saturation Quadrants) against the spread of the regions' mean incidence ranks, the largest minus the smallest regional mean rank divided by the number of clusters. Filled symbols are the 50 grid surfaces (queen, production allocations) by incidence configuration, with a least-squares line fitted to them. Open triangles are the fixed NC regions in each of the four planning years, whose spread divides by 58 clusters rather than 100.

Formal tests on the NC results. Friedman tests over the 24 combinations of year, ρ and γ

rejected equal ranks of the nine strategies in all four combinations of regime and β ($\chi^2 = 135.3$, 153.8, 150.7 and 179.8 on 8 degrees of freedom, $p \leq 2.3 \times 10^{-25}$; Nemenyi critical difference 2.45). Under control-only spillover, Saturation Quadrants and Incidence-Guided Saturation had the two best average ranks (1.67 and 1.79 with $\beta = 0$; 1.29 and 1.71 with $\beta = 1$), and SRS ranked seventh with $\beta = 0$ and sixth with $\beta = 1$. Under both-arms spillover with $\beta = 0$, High Incidence Focus ranked first (1.88) and SRS sixth (5.17), with the balancing and saturation designs between them. These tests treat the 24 blocks as independent, although the years share one map and some strategies share their simulations across years. They therefore describe the consistency of the ordering rather than independent evidence.

Unequal numbers of trained professionals. With m proportional to college population and averaging 25, and ICC = 0.05, power fell by 0.097 on average across designs, settings and effect sizes. For $d = 0.3$ under both-arms spillover, the mean power over the nine strategies fell from 0.59 to 0.46 with 20 colleges and from 0.88 to 0.77 with 58. MSE rose by a factor of 1.24 to 1.84 across designs and settings, and no design gained relative to the others.

Estimation models. Every model in the sensitivity analysis has the mean $\mu = \alpha\mathbf{1} + \tau\mathbf{Z} + \text{Spill}$ with the proportional spillover covariate of the main analysis, and uses the 58-college queen geography. The spatial lag model of the main analysis is $\mathbf{Y} = \rho\mathbf{W}\mathbf{Y} + \mu + \varepsilon$, $\varepsilon \sim N(\mathbf{0}, \sigma^2\mathbf{I})$. The CAR model is $\mathbf{Y} = \mu + \mathbf{u}$, $\mathbf{u} \sim N\{\mathbf{0}, \sigma^2(\mathbf{I} - \lambda\mathbf{S})^{-1}\}$, where $\mathbf{S}$ is the symmetric matrix similar to the row-standardized $\mathbf{W}$ [10]. We fitted it by maximum likelihood with the `spautolm` function of the R package `spatialreg` [11]. For the reverse comparison, data were generated as $\mathbf{Y} = \mu + \mathbf{L}\varepsilon$ with $\mathbf{L}\mathbf{L}^\top = (\mathbf{I} - \rho\mathbf{S})^{-1}$ and the same values of ρ as the spatial lag data. These runs used four years, $\rho \in \{0, 0.2, 0.5\}$, $\gamma \in \{0.5, 0.8\}$, both regimes and the nine strategies, with 500 fits per setting.

The Bayesian CAR model [35] is $Y_j = \mu_j + \phi_j + e_j$, $e_j \sim N(0, \nu^2)$, with

$$\phi_j \mid \phi_{-j} \sim N\left(\frac{\lambda \sum_k a_{jk}\phi_k}{\lambda \sum_k a_{jk} + 1 - \lambda},\ \frac{\sigma_\phi^2}{\lambda \sum_k a_{jk} + 1 - \lambda}\right),$$

where a_{jk} is the binary queen adjacency. We used the defaults of the `S.CARleroux` function of the R package `CARBayes` [36], version 6.1.1: independent $N(0, 10^5)$ priors for the regression coefficients, inverse-gamma(1, 0.01) priors for ν^2 and σ_ϕ^2, and a uniform(0, 1) prior for λ. Each chain ran 25,000 iterations, discarding the first 5,000 and thinning by 5. At $\rho = 0.5$, where fewer than half the chains converged, we reran the same data with 100,000 iterations, discarding the first 20,000 and thinning by 20. The Bayesian spatial lag model [9] has the same form as the maximum likelihood model, with the defaults of the `spBreg_lag` function of `spatialreg`, version 1.4.3: a $N(\mathbf{0}, 10^{12}\mathbf{I})$ prior for the regression coefficients, the prior $p(\sigma^2) \propto 1/\sigma^2$, a Beta(1.01, 1.01) prior for ρ rescaled to its feasible interval, and 10,000 draws of which the first 2,000 were discarded. Both Bayesian models used four years, $\rho \in \{0, 0.5\}$, $\gamma = 0.8$, both regimes and the nine strategies, with 100 fits per setting (14,400 fits per model), and both were fitted to the same data as the maximum likelihood model. We report the posterior mean of τ and the 95% equal-tailed credible interval. A chain was counted as converged when the effective sample size of τ was at least 400 and the absolute Geweke z statistic [37] was below 1.96.

With the longer chains, 83.1% of the Bayesian CAR chains at $\rho = 0.5$ converged, against 46.2% for the shorter chains, but 12.5% still had an absolute Geweke z of at least 1.96, against about 5% expected by chance. Among converged chains, the Bayesian CAR estimate was biased by +0.14 under both-arms spillover and +0.22 under control-only spillover, with credible-interval coverage of 90.4% and 87.7%. For maximum likelihood on the same data, the biases were +0.02 and +0.03 and the corrected t coverage 95.0% and 94.6%. Of the Bayesian spatial lag chains, 94.9% converged. The median effective sample size of τ was 8,000 (minimum 5,897), and 5.1% of chains had an absolute Geweke z of at least 1.96. The model's posterior means correlated

0.999 with the maximum likelihood estimates (mean absolute difference 0.017). Its bias was at most 0.04 in absolute value in every combination of ρ and regime, and its credible intervals covered 94.6% to 95.3% over all chains (94.5% to 95.3% over converged chains). The Spearman correlation of its design ordering with that of maximum likelihood averaged 0.96 to 1.00 across the four combinations of ρ and regime (0.83 in the lowest single block), and the best design agreed in every block. Tables 26 and 27 give each strategy's MSE relative to SRS under each model.

Table 26: Mean MSE relative to simple random sampling (SRS) under four combinations of data-generating model and fitted model: spatial lag (SAR) or conditional autoregressive (CAR). 58 colleges, $\beta = 0$, mean over 24 blocks (year $\times$ ρ $\times$ γ). Below 1 is lower error than SRS.

	Both arms				Control only			
Data	SAR	SAR	CAR	CAR	SAR	SAR	CAR	CAR
Fit	SAR	CAR	SAR	CAR	SAR	CAR	SAR	CAR
Checkerboard	2.88	2.83	2.93	3.09	2.99	2.64	3.01	3.00
High Incidence Focus	1.06	1.02	1.07	1.07	1.08	1.03	1.10	1.09
Saturation Quadrants	1.04	1.02	1.04	1.03	0.79	0.81	0.81	0.78
Isolation Buffer	4.11	4.13	4.16	4.45	1.03	0.95	1.03	1.05
2×2 Blocking	0.98	0.99	1.00	1.02	1.21	1.17	1.22	1.22
Balanced Quartiles	1.04	1.05	1.04	1.06	1.03	1.00	1.03	1.02
Balanced Halves	1.04	1.03	1.05	1.04	1.02	0.98	1.03	0.99
Incidence-Guided Saturation	1.03	1.04	1.04	1.03	0.81	0.82	0.81	0.76
Simple Random Sampling	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

Table 27: Mean MSE relative to simple random sampling (SRS) at $\rho = 0.5$ for maximum likelihood (ML), the Bayesian spatial lag model (Bayes SAR) and the Bayesian CAR model with converged chains only (Bayes CAR), all fitted to the same spatial lag data. 58 colleges, $\beta = 0$, $\gamma = 0.8$, mean over the four planning years.

	Both arms			Control only		
Design	ML	Bayes SAR	Bayes CAR	ML	Bayes SAR	Bayes CAR
Checkerboard	3.14	3.18	2.90	3.16	3.16	2.31
High Incidence Focus	0.96	0.96	0.83	1.19	1.19	1.04
Saturation Quadrants	1.12	1.10	1.11	0.86	0.86	1.05
Isolation Buffer	3.89	3.94	3.80	1.01	1.02	0.87
2×2 Blocking	1.14	1.14	1.11	1.48	1.48	1.34
Balanced Quartiles	1.00	1.00	1.05	1.10	1.10	1.15
Balanced Halves	0.97	0.97	0.99	1.05	1.06	1.01
Incidence-Guided Saturation	1.12	1.10	1.13	0.81	0.81	0.95
Simple Random Sampling	1.00	1.00	1.00	1.00	1.00	1.00

Spillover form. Under the binary form, $\mathbf{S}(\mathbf{Z}) = \gamma\, \mathbb{I}\{\text{any treated queen neighbor}\}$, times $\mathbf{1} - \mathbf{Z}$ under control-only spillover. Under the count form, $\mathbf{S}(\mathbf{Z}) = (\gamma/\bar{d})\times$ (number of treated queen

neighbors), where $\bar{d} = 4.93$ is the mean number of queen neighbors, so a college of average degree with every neighbor treated receives γ, as under the proportional form. Table 28 compares the three forms. With the binary form, Isolation Buffer is never identified, because every control has a treated neighbor, and under control-only spillover no strategy was identified in every fit. The saturation designs were identified most often there (in 89.7% and 91.7% of fits) and, among identified fits, had MSE 0.70 to 0.71 times that of SRS.

Table 28: Mean MSE relative to simple random sampling (SRS) under three spillover forms, 58 colleges, $\beta = 0$, mean over 16 blocks (year $\times$ ρ $\times$ γ). n.i.: not identified in every fit (the spillover covariate is aliased with the intercept and treatment in some or all allocations).

	Both arms			Control only		
Design	Proportional	Count	Binary	Proportional	Count	Binary
Checkerboard	2.97	1.78	1.07	3.09	1.41	n.i.
High Incidence Focus	0.91	0.92	0.96	1.03	1.04	n.i.
Saturation Quadrants	1.01	1.02	1.03	0.76	0.81	n.i.
Isolation Buffer	3.82	3.84	n.i.	0.95	1.16	n.i.
2×2 Blocking	1.04	1.03	1.00	1.17	1.07	n.i.
Balanced Quartiles	1.01	1.01	1.00	0.99	0.99	n.i.
Balanced Halves	1.02	1.02	1.02	0.98	0.99	n.i.
Incidence-Guided Saturation	1.01	1.03	1.04	0.75	0.79	n.i.
Simple Random Sampling	1.00	1.00	1.00	1.00	1.00	n.i.